AGENDA

City of Hapeville

3468 North Fulton Avenue

Hapeville, Georgia 30354

Design Review Committee

June 19, 2019

6:00 PM

- 1. Welcome And Introduction
- 2. Approval Of Minutes
 - 2.I. Design Review Committee Minutes: May 15, 2019

Documents:

DRC MINUTES MAY 15, 2019.PDF

3. Tia Muse/Brooke Fortenberry 3303 North Whitney Avenue Documents:

3303 NORTH WHITNEY AVENUE DRC APP.PDF

4. Tia Muse/Brooke Fortenberry 3341 North Whitney Avenue Documents:

3341 NORTH WHITNEY AVENUE DRC APP.PDF

5. Tia Muse/Brooke Fortenberry 3377 Lavista Drive Documents:

3377 LAVISTA DRIVE DRC APP.PDF

6. Casey Busch 600 South Central Avenue

Documents:

600 SOUTH CENTRAL AVENUE DRC APP.PDF

7. Paula Smith 3365 Northside Drive

Documents:

3365 NORTHSIDE DRIVE DRC APP.PDF

8. Michael Miles 831 Custer Street

Documents:

831 CUSTER STREET DRC APP.PDF

- 9. New Business
 - 9.I. Village Walk Hapeville Item Tabled @ May 15th DRC Meeting

Documents:

VILLAGE WALK HAPEVILLE.PDF

- 10. Next Scheduled Meeting Wednesday, July 17, 2019
- 11. Adjourn

Design Review Committee Meeting Minutes

May 15, 2019

I. Call to Order

Jonathan Love called to order the regular meeting of the Design Review Committee at 6:09 PM on May 15, 2019 in the Hapeville City Hall Conference Room.

II. Roll Call

Jonathan Love (Chairman) conducted a roll call. The following persons were present Rick Ferrero, John Stalvey (acting secretary) and Planner's Lynn Patterson and Michael Smith (non-voting).

III. Approval of Minutes

John Stalvey made a motion to approve the minutes from April 19, 2019. Rick Ferrero seconded, motion passed 3-0

IV. Applications

- a) 232 Birch Street Mariano Alvarado and Alexander Tapia attending Rick Ferrero made a motion to approve the application with the following condition:
 - 1. Top and bottom rail material and size must be compliant with requirements and must be painted or stained

John Stalvey seconded, motion passed 3-0

b) 632 South Central Avenue - Bianca Howard attending

Jonathan Love made a motion to approve the application with the condition that the paint meets standards identified in the Planner's Report and will include a topcoat or varnish that will guarantee a 5-year lifespan

Rick Ferrero seconded, motion passed 3-0

c) 3418 Dogwood Drive - Bianca Howard attending

Jonathan Love made a motion to approve the application with the condition that the paint meets the requirements identified in the Planner's Report, will include a topcoat or varnish that will guarantee a 5-year lifespan and that size requirements for the text portion of the mural doesn't exceed maximum size requirements

John Stalvey seconded, motion passed 3-0

d) 3472 Rainey Avenue - Tony McSwain attending

John Stalvey made a motion to approve the application with the following conditions:

- 1. Convert master bath area from 2' to a 1' offset and use board and batten on the exterior instead of stucco (reference home at 3388 Colville Avenue)
- 2. Chimney will stack and go to grade; Chimney height must meet requirements
- 3. Light to be located at front door
- 4. Roof shingle information must be provided and meet standards
- 5. Must include building numbers on plan
- 6. Gutter and downspout material must be provided and meet standards
- 7. Any exposed slab must have mock foundation
- 8. Add window to dining room area
- 9. Provide specifications on windows and must meet standards; glass must be recessed from façade

Design Exceptions:

- 10. A design exception will be made to allow PVC columns
- 11. An exception to be given to the porch width requirement; due to width of home and lot a driveway would not fit if porch extended further
- 12. A design exception given to allow for windowsill height less than 30"

Jonathan Love seconded, motion passed 3-0

e) Village Walk @ Hapeville - Scott Johnson and Trey Baltz attending

The site will eventually be subdivided and will be partial residential and partial commercial. As such, the residential and commercial will be split and include different standards and separate votes.

Residential

Jonathan Love made a motion to table the vote until such time that the applicant can correct several items on the plan to include the following:

- The façade and roof form of the townhomes cannot be mirrored or repeating; it is suggested to add offsets in the units (no more than 3 per offset)
- 2. Mechanical features must be included and show screening
- 3. No GBG windows to be used; must provide window and window trim dimensions
- 4. Plans must include building numbers and a light next to the doors
- 5. Provide roof shingle warranty information that must meet standards
- 6. Roof overhang will be a minimum of 12" beyond façade

7. Provide a landscape plan that shows sidewalk connecting units to commercial area and each unit to the sidewalk to meet ADA requirements. Landscape plan must include details of the wall and screening to be used along the Central Avenue portion of the property

Design Exceptions:

8. A design exception will be provided to allow 26' width on driveway at request of Fire Marshal

Rick Ferrero seconded, motion passed 3-0

Commercial

Jonathan Love made a motion to table the vote until applicant can update items on the plan to include the following:

- 1. Building heights must be at least 24' tall
- 2. Provide building numbers on plan
- 3. Must include information on material and look of proposed screening wall along Central Avenue
- 4. Upgrade landscape plan to include street trees
- 5. Sidewalk shown on landscape plan must wrap from Colville side to rear parking area
- 6. Provide plans to include mechanical features and screening
- 7. Provide height and material of dumpster screening for all dumpsters
- 8. Provide pedestrian scale streetlights
- 9. Awnings must have square aluminum tubing frame
- 10. Commercial properties must use full depth brick

Design Exceptions:

- 11. Exception to allow for 5' sidewalk along Colville Avenue to allow for 6' width in parking area for safety concerns
- 12. An exception to not require hardscape along Colville Avenue frontage to allow for more plantings and maintain the park like feel that is desired
- 13. A design exception will be given to allow for a 26' driveway at the request of the Fire Marshal

Rick Ferrero seconded, motion passed 3-0

V. New Business

None

VI. Next Scheduled Meeting is Wednesday, June 19, 2019 at 6:00 PM

VII.	Adjournment Jonathan Love made a Motion passed 3-0	a motion to adjourn, John Stalvey seconded.
	Minutes submitted by:	John Stalvey, Acting Secretary
	Minutes approved by:	 Jonathan Love, Chairman



DEPARTMENT OF PLANNING AND ZONING PLANNER'S REPORT

DATE: June 5, 2019
TO: Tonya Hutson
FROM: Lynn Patterson

RE: Design Review – 3303 North Whitney Avenue

BACKGROUND

The City of Hapeville has received a Design Review Application from Tia Muse and Brooke Fortenberry for the addition of solar panels to the roof of the existing building at 3303 North Whitney Avenue.

The property is zoned R-1, One-Family Detached, and is subject to the Neighborhood Conservation Area of the Architectural Design Standards.

CODE

- (e) Roof and chimney standards.
 - 1. Principal building roofs for one-family detached dwellings shall have a minimum usable life of thirty (30) years, per manufacturer's warranty.
 - 2. Roof shingles shall be slate, cedar, or asphalt.
 - 3. Roof tiles shall be clay, terra cotta or concrete.
 - 4. Metal roofs are:
 - a. Permitted on one-family and two-family detached dwellings if approved by the design review committee; and
 - b. Permitted on multifamily and townhouse dwellings only when screened from the adjacent street by a parapet wall.
 - 5. Gutters shall be copper, aluminum or galvanized steel.
 - 6. Downspouts shall match gutters in material and finish.
 - 7. Roof forms shall be based on architectural style.
 - 8. All roofs, excluding dormers, shall overhang a minimum of 12 inches beyond the facade.
 - 9. Dormers are permitted on all style homes (unless specified), but shall not be taller than the main roof to which they are attached.
 - 10. Chimneys exposed to the public view may not be faced in wood or cement based siding and may not be of an exposed metal or ceramic pipe. All chimneys shall be wrapped in a brick, stone or suitable masonry finish material.
 - 11. Chimneys on exterior building walls shall begin at grade.
 - Chimneys shall begin at grade and be faced with brick or stacked stone; extend chimneys between three and six feet above the roof line.

FINDINGS

The Architectural Design Standards do not provide guidance for the installation of roof-mounted solar panels. As solar panels are not directly allowed by the code, a Design Exception would be required.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE: May 15, 2019
NOTE:	All applications must be typed or neatly printed. Applications or an authorized representative is required to personally appear at the Design Review Meeting to answer questions.
	The Design Review Committee meets the third Wednesday of each month. Every attempt will be made to place your application for review on the next month's agenda following the submittal of a completed application with supporting documents; however, that may not always be possible. The City reserves the right to schedule applications as deemed necessary.
Applicant:	Tia Muse/Brooke Fortenberry contact Number: 770-485-7438
Applicants Ad	dress: 2931 Lewis St Ste 300 Kennesaw GA 30144
E-Mail Address	s: <u>tia muse @ Creative solarusa</u> Coning Classification:
	oposed Work: 3303 N Whitney Ave Hapeville GA 30354
	FORMATION MUST BE PROVIDED): 14 009800140271
Property Owner	er: Travis Horsley Contact Number:
Project Desc Solar P	ription (including occupancy type): installing 4.80 KW of anels to roof top
Contractors I	Name: Alan Carrier Contact Number: 678-779-6248
	on: <u>Tia Muse</u> <u>Contact Number: 770-485-7438</u>
property. I do laccurate, and I application and reserves that rig I further unders full. I hereby ac write the Englis voluntarily com	application to the City of Hapeville, to the Design Review Committee for the above referenced hereby swear or affirm that the information provided here and above is true, complete and understand that any inaccuracies may be considered just cause for invalidation of this any action taken on this application. I understand that the City of Hapeville, Georgia, ght to enforce any and all ordinances regardless of any action or approval on this application. Stand that it is my/our responsibility to conform with all of City of Hapeville's Ordinances in cknowledge that all requirements of the City of Hapeville shall be adhered to. I can read and sh language and/or this document has been read and explained to me and I have full and pleted this application. I understand that it is a felony to make false statements or writings to eville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for violation thereof.
Applicante	Signaturo

e):	
Commercial	Mixed-Use Development
onstruction	Addition to Existing Commercial Building
Residential Structure	Accessory Structure
Landscaping	New Single Family Residential Construction
rels	
posed New Construction	on:
sting building:	
tion: <u>\$12, 480</u>	
ials on the exterior of th	e <u>existing</u> structure:
-Cell Solar po 27-60-2-US m	xterior facade of the new structure: anels (data sheet provided) nicro inverters (data sheet provided) (data sheet provided)
	Commercial construction Residential Structure Landscaping Dels Exposed New Construction String building: Finals on the exterior of the

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does **NOT** make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)

swear or affirm that before receipt of an application, I have received this notice and I read and write the English language or I have had someone read and explain this document to me.



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

I, the undersigned, agree that with following:	my signature and submission to the (City of Hapeville, I have done the
proposed project. The Archite	rchitectural Design Guidelines and relectural Design Guidelines may be four apeville/codes/code of ordinances?	nd here:
✓ Ensured that my proposed pro of Ordinances.	oject meets all of the required criteria	a per the City of Hapeville Code
Submitted my application mat Design Review Committee me	terials in full by the published deadlin eeting.	e for review by Staff prior to the
	eficiencies or components of the prop th in the Code. This explanation shou	
Understood that any deficience Design Review Committee me	cies in the application must be resolve eeting or the application may not be p	ed at least 10 days prior to the presented to the DRC for review.
iSubmitted architectural drawi Community Services or Plannii	ings and details for all projects unless ng & Zoning Department.	allowed in writing by the
	d revisions by the Design Review Comepartment for review prior to request	
Tia Muse	Sia Muse	5-6-19
Printed Name	Signature	Date

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.

Google Maps 3308 N Whitney Ave




Google

Hapeville, Georgia

Street View - Sep 2018

5/30/2019, 11:44 AM 1 of 1



NOTES:

1 SHINGLE ROOF. ROOF DECKING IS PLANK, CONVENTIONAL FRAMING: 2X6 RAFTERS 16" O/C AT MAIN HOUSE, PITCH IS 9:12. 2X4 RAFTERS 20" O/C AT SHED, PITCH IS 7:12. 2X4 RAFTERS 24" O/C AT 2:12 ROOF, PITCH IS 2:12. PRE-MEASURE ALL AREAS TO CLEAR OBSTACLES AND ENSURE PROPER FIT, LEAVING SUFFICIENT ROOM FOR SETBACKS AND ACCESS PATHS.

2 MARK AND ATTACH MOUNTS & RAILS ACCORDING TO LAYOUT & MOUNT AND RAIL PATTERNS. RAIL SPACING IS 33" PORTRAIT, 20" LANDSCAPE, 27" TRANSITIONING BETWEEN THE TWO. RAIL SPACING VARIES TO ACCOMMODATE TILT LEGS. MOUNTS ARE AT VARYING INTERVALS, MAXIMUM DISTANCE BETWEEN MOUNT AND RAIL-EDGE OR SPLICE IS 24". (MAX MOUNTING SPAN 7') (INNER 50% OF PANEL SHOULD) BE BETWEEN RAILS.)

USE FIXED TILT LEG KITS W/ 20" NORTH TILT LEG FOR 2:12 ROOF AT 2-FT RAIL SPANS AND 5 FT B/W PANELS. USE FIXED TILT LEG KITS W/ 25" NORTH TILT LEG FOR 9:12 ROOF AT 3'6" RAIL SPANS.

- 3 MOUNT ENPHASE **Q TRUNK CABLE AND 1Q7 MICROINVERTERS,** NOTING STRING CONFIGURATION AND RECORDING MICROINVERTER S/N'S. INSTALL TERMINATORS AND UNUSED CONNECTOR CAPS. RUN ALL GROUNDS. MULTIPLE JUMPERS. USE LFMC AND 600V PV WIRE.
- MOUNT & CONNECT PANELS CENTERED OVER RAILS, RECORDING PANEL S/N'S. RAIL OVERHANGS ARE APROX. 2-3" PAST PANELS. CONNECT ALL JUMPERS, MANAGE WIRES. SEPARATION DISTANCE BETWEEN ADJACENT PANELS ‡-½" 4

INSTALL AND WIRE JUNCTION BOX, COORDINATING WITH ELECTRICIAN FOR PATH OFF ROOF. RUNS ARE 600V

2

COORDINATE WITH ELECTRICIAN AND HOME OWNER FOR TRENCH AND OTHER LINES THAT WILL CO-OCCUPY TRENCH 9

ORITH PMERICAN BOOM	CERTIFIED	2 SP.	MERGY PRACTITION
CK'D			
ВУ	REG		
DESCRIPTION	PROPOSAL v1		
DATE	01/27/19		

REVISIONS



Richard Gale



STRING CONFIGURATION (NTS)	A A A A A A A A A A A A A A A A A A A
24 α Ω α Φ 0 α ∞ α ∞ α ∞ α Ω α Ω α Ω α Ω α Ω Ω Ω Ω Ω	
	5


RATED WITH THE FOLLOWING MINIMUMS MET:


OVERHEAD MOCK-UP (NTS)

Creative Solar USA, Inc.

Kennesaw, 6a 30144 Russell Seifert: 770-378-9668 www.creativesolarusa.com 2931 Lewis Street

				RFG
		30354		FNG/DBA:
SOLAR PV ARRAY		, HAPEVILLE, GA	(11 LANDSCAPE)	DATE: 01-27-2019
WOUNT	SLEY	TNEY AVE	PUT: 8.5 X	DATE:
5.1 KW ROOF	TRAVIS HOR	3303 N WHI	1" = 12' (OUT	1 OF 1
TITLE:	CUSTOMER:	ADDRESS:	SCALE:	PAGE:
TITLE: 5.1 KW ROOF-MOUNT SOLAR PV ARRAY	CUSTOMER: TRAVIS HORSLEY	ADDRESS: 3303 N WHITNEY AVE, HAPEVILLE, GA 30354	SCALE: 1" = 12' (OUTPUT: 8.5 X 11 LANDSCAPE)	





With its top performance and completely black design the new TREAK BLK 54 1 is the ideal solution for all residential rooftop applications thanks to its innovative cell technology (CANTUM). The world-record cell design was developed to achieve the best performance under real conditions - even with low radiation intensity and on clear, hot summer days.



LOW ELECTRICITY GENERATION COSTS

Higher yield per surface area and lower BOS costs thanks to higher power classes and an efficiency rate of up to $16.3\,\%$.



INNOVATIVE ALL WEATHER TECHNOLOGY

Optimal yields, whatever the weather with excellent low-light and temperature hehavior.



ENDURING HIGH PERFORMANCE

Long-term yield security with Anti-PID Technology's Hot-Spot-Protect and Traceable Quality fra Q12



EXTREME WEATHER RATING

High tech a uninum alloy trame, certified for high show. (5400 Pa) and wind loads (4000 Pa) regarding IEC



MAXIMUM COST REDUCTIONS

Up to 10% lower logistics costs due to higher module capacity per box



A RELIABLE INVESTMENT

Inclusive 12-year product warranty and 25-year imear performance guarantes .



THE IDEAL SOLUTION FOR:











APT with confidence for it at a filtery sgaura geological part conductive par tall for loosered module particle. 25 C.

her data sorre on teat for it objet ofern gluris.



41 4pibs (18.8 sg) Weight

Front Cover D. Dam (3. 2 mm) thermally are stressed glass with anti-reflection technology

Composite from Back Cover


Black anodized aligninum Frame

6 < 10 monerowstalline Q ANTUM solar cells Cell

) with 4 0.8 m = 2.34 5.4 5 $k_{\rm s}$ (2.95). From 165 TI errors (11.90 mm/s) [15.19 mm/ Protection class (PSP) with bypass diades Junction box


4 mm; Solar cable, (=) \$39,37 m (1,000 mm), (-) \$39,37 m (1,000 mm) Cable

Multi-Contact MC4 or MC4 intermaleable, IP68 Connector



31	ECTRICAL CHARACTERISTICS		Total Section of the			
	VERICLASS			790	296	300
MIN	IMUM PERFORMANCE AT STANDARD TEST	CONDITIONS, 576	POWER TOLERANCE	~5 W / -0 W i		
	Power at MPP:	$P_{w^{\rm op}}$	(W)	290	295	300
	Short Circuit Current	$t_{\rm id}$	(A)	74 gs H	** /11	9.77
mum mum	Open Circuit Voltage	V_{∞}	(W)	39-19	39.48	39.76
E N	Current at MPP*	1,,,,,	(A)	9.07		9.26
	Voltage at MPP*	V	(Y)	11 96	15.19	32.41
	Efficiency*	η	[%]	.17.4	17.7	- 1 4 C
1/15	IMUM PERFORMANCE AT NORMAL OPERAT	TING CONDITIONS N	OC.			
	Power at MPP ²	Pv··	(W)	214.4	718.i	221.8
Hom	Short Circuit Current	t.	(A)		7 W2	p. 494
100	Open Circuit Voltage	V_{∞}	[V]	*6 E1	2 to (1)	87.19
M	Current at MPP*	lere	TAT	1.2		7.27
	Voltage at MPP*	V	(A)	30 12	30.30	30,49


Q CELLS PERFORMANCE WARRANTY



At least 48% or nominal power during that year. Thereafter may (2.6% dispendible) also year 48 bast 92.5% at immediate cover up to 101 years. At least 83 or 5 of nominal solver up to 25 years.

Full war at the in accordance with the Advanty beam of the CCTEC cults represented where respective courts.

PERFORMANCE AT LOW IRRADIANCE



Typical module assistances of a car consistance conditions compared to ATC conditions in the Chickwest

TEMPERATURE COEFFICIENTS

Temperature Coefficient of I _{sc}	C.	[%2K]	L(1 ()	Temperature Coefficient of V _×	#	(% /K)	-0.28
Temperature Coefficient of P	٧	1%-/K1	0.39	Normal Operating Cell Temperature	NOCT	I FI	113 +5,4145 +3701


PROPERTIES FOR SYSTEM O	ESIGN			
Maximum System Voltage V,	(V)	1000 BC: 1000 OU	Safety Class	Þ
Maximum Series Fuse Rating	[A DC]	2.9	Fire Rating	CHECH TYPE I TULI
Design load, push (UL) ²	[fbs/ft*]	75 (haittPa-	Permitted module temperature on continuous duty	40 F in to -185 F 1 40 C up to -85 C
Basses land, seek (1913)	11he /442	10 m 176 for Par	can octaliat on manual	

QUALIFICATIONS AND CERTIFICATES PACKAGING INFORMATION	
	32
BEC 8 1715 (ELLT) (EL 61730 (Ed. Exact) cation (flav A Number of Pallets per 53' Container	3C
Number at Pallets per 40' Container	261
Pallet Dimensions (L x W x H) 98 7 m x 45 7 m x 45 7 m x 46 7 m x 46 7 m x 47	
Pather Weight 5430 oct 1643	*61

NOTE Institution instructor, which the followed Skie tox, extra accordant mentions in a policy or other bey to this allows or observed the batter with above or tailetic and

Enphase IQ 7 and IQ 7+ Microinverters

9.9 (4) 2 9.9



CENTERED SERVICES CO.

The high-powered smart grid-ready

Enphase IQ 7 Micro** and Enphase IQ 7+ Micro**

dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enchase IQ System, the IQ 7 and IQ 7+ Microinverters integrate with the Enchase IQ Envoy", Enphase IQ Battery 1, and the Enphase Enlighten I monitoring and analysis software

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.

Lasy to Install

- · ...chiweighi anu sinole
- Fuster installation with improved, lighter two tyre capling
- Redi mrepic shuldown conofen; (NEC 2014 8 2017)

Productive and Reliable

- Opinnized for high powered 60 cell and 72 be 12 modules.
- More than a million bours of testing.
- Classif double-insulated enploaure
- Ut listed

Smart Grid Ready

- Complies with advanced grid support, voltage and frequency refer through requirements:
- Remotely updates to respond to changing and requirements
- · Contigurable for varying quid profiles.
- Meets CA Rule 21 (UL 1741-SAL

10 - Micro systematic support if get stabilities.



Enphase 10 7 and 10 7+ Microinverters


INPUT DATA (DC)	107-60-2-US / 107-60-B-US		IQ7PLU5-72-2-US / IQ7PLUS-72-8-US		
Commonly used module painings	235 W - 350 W -	-	235 W - 440 W -		
Module compatibility	60-cell PV modules only		68 cell and 72 cell PV modules		
Maximum input DC voltage	48 V		60 V		
Peak power tracking voltage	27 V 37 V		27 V - 45 V		
Operating range	16 V - 48 V		15 V - 60 V		
Min/Max start voltage	22 V - 48 V		22 V 160 V		
Max DC short circuit current (module (sc)	15 A		15 A		
Overvoltage class UC port			14		
DC port backfeed current	0 A		0 A		
ov array configuration			ial DC side protection required: A per branch circuit		
OUTPUT DATA (AC)	10 7 Microinve	erter	IQ 7+ Microin	verter	
Peak output power	250 VA		295 VA		
Maximum cantinuous outquit power	240 VA		240 94		
Nominal (L.L.) voltage/range ^z	240 V / 211-264 V	208 V / 183-229 V	240 V / 211-264 V	208 V / 183-229 V	
Maximum continuous output current	1.0 A (240 V)	1 15 A (208 V)	121A (240 V)	1 39 A (208 V)	
Naminal frequency	60 Hz		60 Hz		
Extended frequency range	47 68 Hz		47 68 Hz		
4C short circuit fault current over 3 cycles	5.8 Arms		5.8 Arms		
Maximum units per 20 A (I-1) branch streuit?	16 (240 VAC)	13 (208 VAC)	13 (24f) VAC)	11 (208 MAC)	
Overvoltage class AC port					
AC port backfeed current	0 A		0.4		
Power factor setting	1.0		1.0		
Power factor (adjustable)	0.85 leading 1	0.85 lagging	0.85 leading	185 lagging	
EFFICIENCY	@240 V	@208 V	@240 V	@20B V	
Peak efficiency	976%	97.6 %	97.5 %	973%	
CEC weighted efficiency	970%	97.0 %	97.0 %	97,0%	
MECHANICAL DATA	PARTICIPATION CONTRACTOR CONTRACT		THE RESIDENCE OF THE PROPERTY		
Ambient temperature range	-40°C to +65°C				
Relative humidity range	4% to 100% (car	adensina)			
			Iditional O DCC 5 a	idapter)	
Connector type (107-60-8-US & 107PLUS-72-9-US)	MC4 for Amphenol H4 UEX with additional Q-DCC 5 adapter) Friends PV2 (MC4 intermateable) Adaptors for modules with MC4 or UEX connectors. PV2 to MC4 order ECA S20 S27 PV2 to UEX order ECA-S20-S25				
Ojmensions (WxHxD)	212 mm x 175 n	nm x 30 2 mm (with	nout bracket)		
to be a second of the contract	212 mm x 175 mm x 30 2 mm (without bracket) 1.08 kg (2.38 hrs)				
	1 08 kg (2 38 lb)				
Weight	1 08 kg (2 38 lb. Natural convect				
Weight Ceating					
Weight Ceoling Approved for wet locations	Natural convect				
Weight Cooling Approved for wet locations Pollution degree	Natural convect Yes PD3	iron - No fans	n resistant polome	rië enblosure	
Weight Ceoling Approved for wet locations Pollution degree Englesure	Natural convect Yes PD3 Class II double-	ion - No fans Insulated corrosio	n resistant polyme	ne emblosure	
Weight Coofing Approved for wet locations Pollution degree Environmental category / UV exposure rating	Natural convect Yes PD3	ion - No fans Insulated corrosio	n resistant polyme	ne enclosure	
Weight Cealing Approved for wet locations Pollution degree Environmental category / UV exposure rating FEATURES	Natural convect Yes PD3 Class II double- NEMA Type 6 /	ion - No fans Insulated, corresio outdoor	n resistant polyme	ne enclosure	
Weight Confing Approved for wet locations Pollution degree Engineure Environmental category / UV exposure rating FEATURES Communication	Natural convect Yes PD3 Class II double- NEMA Type 6 /	insulated corresio outdoor nimunication (PLC)			
Weight Confing Approved for wet locations Pollution degree Enciosure Environmental category / UV exposure rating FEATURES Communication Monitoring	Natural convect Yes PD3 Class II double- NEMA Type 6 / Power Line Con Enlighten Maria Both options re	insulated corresio outdoor nimunication (PLC) iger and MyEnlighte guire installation of	en monitoring optic an Enphase IQ En	ens soy.	
Weight Cooling Approved for wet locations	Natural convect Yes PD3 Class II double- NEMA Type 6 / Power Line Con Enlighten Mans Both options re The AC and DC disconnect requ	inn - No fans Insulated, corresio outdoor nmunication (PLC) iger and MyEnlighte guire installation of connectors have buired by NEC 690.	en monitoring optic an Enphase IQ En	EDS	
Weight Cooling Approved for wet locations Pollution degree Enciesure Environmental category / UV exposure rating FEATURES Communication Monitoring	Natural convectives PD3 Class II double- NEMA Type 6 / Power Line Con Enlighten Mans Both options re The AC and BC disconnect requ CA Rine 21 (IIL UL 62109-4, UL) CAN/CSA-C22. This product is	insulated corresion outdoor nmunication (PLC) oper and MvEnlighte quire installation of the connectors have becomed by NEC 690. 1741-SAI 12EE1547, ECC 2 NO 1071-01. UL Listed as PV Rain outdoor on the connectors of the connec	en monitoring optic fan Enphase (Q En een evaluated and : Part 15 Class 8. (p.d Shut Dewn Equ	ons voy. approved by UL for use as the load-break	

No enforced DCDAC ratio. See the compatibility calculator at https://enphase.com/en/us/support/modele-compatibility
 Nomenal voltage range can be extended deviand nominal directioned by the stillty
 Limits may vary. Refer to local requirements to define the number of micromyetters per pranch in your area.





Roof Mount System



Built for solar's toughest roofs.

IronRidge builds the strongest roof mounting system in solar. Every component has been tested to the limit and proven in extreme environments.

Our rigorous approach has led to unique structural features, such as curved rails and reinforced flashings, and is also why our products are fully certified, code compliant and backed by a 20-year warranty.



Strength Tested

All components evaluated for superior structural performance.



PE Certified

Pre-stamped engineering letters available in most states.



Class A Fire Rating

Certified to maintain the fire resistance rating of the existing roof.



Design Software

Online tool generates a complete bill of materials in minutes.



Integrated Grounding

UL 2703 system eliminates separate module grounding components.



20 Year Warranty

Twice the protection offered by competitors.

XR Rails

XR10 Rail



A low-profile mounting rail for regions with light snow.

- · 6' spanning capability
- Moderate load capability
- · Clear & black anod, finish

XR100 Rail



The ultimate residential solar mounting rail.

- · 8' spanning capability
- · Heavy load capability
- · Clear & black anod, finish

XR1000 Rail



A heavyweight mounting rail for commercial projects.

- · 12' spanning capability
- Extreme load capability
- · Clear anodized finish

Internal Splices 💮



All rails use internal splices for seamless connections.

- Self-tapping screws
- · Varying versions for rails
- · Grounding Straps offered

Attachments

FlashFoot



Anchor, flash, and mount with all-in-one attachments.

- · Ships with all hardware
- · IBC & IRC compliant
- · Certified with XR Rails

Slotted L-Feet



Drop-in design for rapid rail attachment.

- · High-friction serrated face
- · Heavy-duty profile shape
- Clear & black anod, finish

Standoffs



Raise flush or tilted systems to various heights.

- · Works with vent flashing
- · Ships pre-assembled
- · 4" and 7" Lengths

Tilt Legs



Tilt assembly to desired angle, up to 45 degrees.

- · Attaches directly to rail
- · Ships with all hardware
- Fixed and adjustable

Clamps & Grounding

End Clamps



Slide in clamps and secure modules at ends of rails.

- · Mill finish & black anod.
- Sizes from 1.22" to 2.3"
- · Optional Under Clamps

Grounding Mid Clamps



Attach and ground modules in the middle of the rail.

- · Parallel bonding T-bolt
- · Reusable up to 10 times
- · Mill & black stainless

T-Bolt Grounding Lugs



Ground system using the rail's top slot.

- · Easy top-slot mounting
- · Eliminates pre-drilling
- · Swivels in any direction


Accessories



Provide a finished and organized look for rails.

- Snap-in Wire Clips
- · Perfected End Caps
- · UV-protected polymer

Free Resources



Design Assistant

Go from rough layout to fully engineered system. For free.

Go to IronRidge.com/rm

İ

NABCEP Certified Training

Earn free continuing education credits, while learning more about our systems.

Go to IronRidge.com/training



DEPARTMENT OF PLANNING AND ZONING PLANNER'S REPORT

DATE: June 5, 2019
TO: Tonya Hutson
FROM: Lynn Patterson

RE: Design Review – 3341 North Whitney Avenue

BACKGROUND

The City of Hapeville has received a Design Review Application from Tia Muse and Brooke Fortenberry for the addition of solar panels to the roof of the existing building at 3341 North Whitney Avenue.

The property is zoned R-1, One-Family Detached, and is subject to the Neighborhood Conservation Area of the Architectural Design Standards.

CODE

- (e) Roof and chimney standards.
 - 1. Principal building roofs for one-family detached dwellings shall have a minimum usable life of thirty (30) years, per manufacturer's warranty.
 - 2. Roof shingles shall be slate, cedar, or asphalt.
 - 3. Roof tiles shall be clay, terra cotta or concrete.
 - 4. Metal roofs are:
 - a. Permitted on one-family and two-family detached dwellings if approved by the design review committee; and
 - b. Permitted on multifamily and townhouse dwellings only when screened from the adjacent street by a parapet wall.
 - 5. Gutters shall be copper, aluminum or galvanized steel.
 - 6. Downspouts shall match gutters in material and finish.
 - 7. Roof forms shall be based on architectural style.
 - 8. All roofs, excluding dormers, shall overhang a minimum of 12 inches beyond the facade.
 - 9. Dormers are permitted on all style homes (unless specified), but shall not be taller than the main roof to which they are attached.
 - 10. Chimneys exposed to the public view may not be faced in wood or cement based siding and may not be of an exposed metal or ceramic pipe. All chimneys shall be wrapped in a brick, stone or suitable masonry finish material.
 - 11. Chimneys on exterior building walls shall begin at grade.
 - 12. Chimneys shall begin at grade and be faced with brick or stacked stone; extend chimneys between three and six feet above the roof line.

FINDINGS

The Architectural Design Standards do not provide guidance for the installation of roof-mounted solar panels. As solar panels are not directly allowed by the code, a Design Exception would be required.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE:	
NOTE:	All applications must be typed or neauthorized representative is required to personnecting to answer questions.	
	The Design Review Committee meets the Every attempt will be made to place your month's agenda following the submittal supporting documents; however, that may reserves the right to schedule applications as	application for review on the next of a completed application with not always be possible. The City
Applicant: 1	a Muse Brooke Fortenberry contac	t Number: <u>770-485-7438</u>
	dress: 2931 Lewis St. Ste 31	
	s: <u>tia .muse@creative solarusa.com</u> Zoning	
Address of Pro	oposed Work: 3341 N Whitney Ave	Hapeville GA 30354
	FORMATION MUST BE PROVIDED): 14 000	
Property Own	er: Marcus Fellingham Conta	ct Number:
Project Desc	ription (including occupancy type): <u>Insti</u> lar panels to roof top	ralling 5.90 KW
Contractors	Name: Alan Carrier	Contact Number: <u>678-779-6248</u>
Contact Pers	on: Tia Muse	Contact Number: <u>770 -485-7438</u>
property. I do accurate, and I application and reserves that rig I further unders full. I hereby accurate the Englis voluntarily com	application to the City of Hapeville, to the Design Rehereby swear or affirm that the information provided understand that any inaccuracies may be considered any action taken on this application. I understand that it is my/our responsibility to conform with cknowledge that all requirements of the City of Hapesh language and/or this document has been readeled this application. I understand that it is a felowerled Georgia pursuant to O.C.G.A. 16-10-20 and I means the control of the City of Hapesh language and/or this document has been readeled this application.	ed here and above is true, complete and dered just cause for invalidation of this cand that the City of Hapeville, Georgia, any action or approval on this application. It all of City of Hapeville's Ordinances in eville shall be adhered to. I can read and and explained to me and I have full and my to make false statements or writings to
Jia Mu	<u> </u>	5-6-19 Date
Annlicants	Signature	Date

Project Class (check one):	
Residential	Commercial	Mixed-Use Development
Project Type:		
New Commercial Cor	struction	Addition to Existing Commercial Building
Addition to Existing R	esidential Structure	Accessory Structure
Site Plan, Grading & l	andscaping	New Single Family Residential Construction
_√Other Solar Pa	nels	
Total Square Footage of prop	osed New Construction	on:
Total Square Footage of exis	ting building:	
Estimated Cost of Construction	on: \$15,250	
List/Describe Building Materia	als on the exterior of th	ne <u>existing</u> structure:
(20) Hanwha Q-(20) Enphase IQ.	Tells Solar pa	exterior facade of the new structure: nels (data Sheet provided) nicro inverters (data Sheet provided) m (data Sheet provided)



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

I, the undersigned, agree that with my signature and submission to the City of Hapeville, I have done the following:
Read the City of Hapeville's Architectural Design Guidelines and relevant Code sections for my proposed project. The Architectural Design Guidelines may be found here: https://library.municode.com/ga/hapeville/codes/code of ordinances?nodeld=PTIICOOR CH81ARDEST
Ensured that my proposed project meets all of the required criteria per the City of Hapeville Code of Ordinances.
Submitted my application materials in full by the published deadline for review by Staff prior to the Design Review Committee meeting.
✓ Identified and explained all deficiencies or components of the proposed project that do not meet with the requirements set forth in the Code. This explanation should be submitted as a separate document in the application.
Understood that any deficiencies in the application must be resolved at least 10 days prior to the Design Review Committee meeting or the application may not be presented to the DRC for review.
$\sqrt{\ }$ Submitted architectural drawings and details for all projects unless allowed in writing by the Community Services or Planning & Zoning Department.
Agreed to submit any required revisions by the Design Review Committee with updated drawings to the Community Services Department for review prior to requesting any permits.
Tia Muse Sia Muse 5-6-19
Printed Name Signature Date

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.

Google Maps 3341 N Whitney Ave




Hapeville, Georgia

Google

Street View - Sep 2018

5/30/2019, 11:46 AM 1 of 1



NOTES:

- 1 SHINGLE ROOF. ROOF DECKING IS 2X6 PLANK, 2X6 RAFTERS 16" O/C, CONVENTIONAL FRAMING; PITCH IS 7:12. PRE-MEASURE ALL AREAS TO CLEAR OBSTACLES AND ENSURE PROPER FIT, LEAVING SUFFICIENT ROOM FOR SETBACKS AND ACCESS PATHS.
- 2 MARK AND ATTACH MOUNTS & RAILS ACCORDING TO LAYOUT & MOUNT AND RAIL PATTERNS. RAIL SPACING IS 33". MOUNTS ARE AT VARYING INTERVALS, MAXIMUM DISTANCE BETWEEN MOUNT AND RAIL-EDGE OR SPLICE IS 24". (MAX MOUNTING SPAN 7') (INNER 50% OF PANEL SHOULD BE BETWEEN RAILS.) LEAVE ROOM FOR FUTURE PANELS.
- 3 MOUNT ENPHASE Q T**RUNK CABLE AND 1Q7 MICROINVERTERS,** NOTING STRING CONFIGURATION AND RECORDING MICROINVERTER S/N'S. INSTALL TERMINATORS AND UNUSED CONNECTOR CAPS, RUN ALL GROUNDS. USE LFMC AND 600V PV WIRE.
- INSTALL SOLADECKS, VERIFYING POSITION IN ATTIC BEFORE PENETRATING ROOF, AND WIRE HOME RUNS. RUNS ARE 600V.
- 5 MOUNT & CONNECT PANELS CENTERED OVER RAILS, RECORDING PANEL S/N'S. RAIL OVERHANGS ARE APROX. 2-3" PAST PANELS. CONNECT ALL JUMPERS. MANAGE WIRES. SEPARATION DISTANCE BETWEEN ADJACENT PANELS \$ 1-15"

	DORIN PMERICAN BO	CERTIFIED	The badles	ON PRACTIFIC
	CK'D			
	ВУ	REG		
REVISIONS	DESCRIPTION	PROPOSAL v1		
	DATE	03/16/19		






¥ 01	8 2
₹0	80
₹ 60	യയ
A L	87
₹ 00	89
∡ ſŪ	മഹ
4 4	O 4
₹ m	മന
₹ (V)	8 2
4 m	8 4

STRING CONFIGURATION

RATED WITH THE FOLLOWING MINIMUMS MET:

- *BUILDING MEAN ROOF HEIGHT <= 30 FT
 *RAFTER SPACING 24" MAX
 *RISK CATEGORY II
 *WIND EXPOSURE B
 *WIND SPEED <= 110 MPH
 *GROUND SNOW LOAD <= 15 PSF
 *ARAY DIS TRIBUTED WEIGHT < 4.0 PSF
 *ARAY DIS TRIBUTED WEIGHT < 4.0 PSF
 *ARAY BENEATH MODULE FRAME <= 7"
 *MAX GAP BENEATH MODULE FRAME <= 7"
 *UPLIFT, DOWN FORCE, AND SHEAR FORCE OF
 167 LB, 258 LB, AND 135 LB RESPECTIVELY





OVERHEAD MOCK-UP (NTS)

Creative Solar USA, Inc.

Kennesaw, 6a 30144 Russell Seifert: 770-378-9668 www.creativesolarusa.com 2931 Lewis Street

				REG REG
		30354		ENG/DRA:
TITLE: 5.9 KW ROOF-MOUNT SOLAR PV ARRAY	JGHAM	ADDRESS: 3341 N WHITNEY AVE, HAPEVILLE, GA 30354	SCALE: 1" = 12' (OUTPUT: 8.5 X 11 LANDSCAPE)	DATE: 03-05-2019
F-MOUNT	US FELLT	TNEY AVE	PUT: 8.5 >	DATE:
5.9 KW ROOF	CUSTOMER: JOE & MARCUS FELLINGHAM	3341 N WHI	1" = 12' (OUT	1 OF 1
TITLE	CUSTOMER:	ADDRESS:	SCALE	PAGE:





With its top performance and completely black design the new Last Ar Black List the ideal solution for all residential rooftop applications thanks to its innovative cell technology a ANTUM. The world-record cell design was developed to achieve the best performance under real conditions – even with low radiation intensity and on clear, hot summer days.



LOW ELECTRICITY GENERATION COSTS

Higher yield per surface area and lower BCS costs thanks to nigher power classes and an officiency rate of up to $18.3\,\%$.



INNOVATIVE ALL WEATHER TECHNOLOGY

Optimal yields, whatever the weather with excellent low-light and temperature hendyler.



ENDURING HIGH PERFORMANCE

Long-term yield security with Anti-PIO Technology'. Hot-Spot-Protect and Traceable Quality Traught



EXTREME WEATHER RATING

High tech a ununum alloy trame, certified for high show (5400 Pa) and wind loads (4000 Pa) regarding IEC.



MAXIMUM COST REDUCTIONS

Up to 100%, ower logistics costs due to higher module capacity per box



A RELIABLE INVESTMENT

Inclusive 17-year product warranty and 75-year linear performance guarantee .



CELLS







AST transcendings on Early 15 key against grounded with recode their all the movement models surface 25 C. 168 to

the data ships on tear for percenofers above.





Engineered in Germany



41 45 (51 H8 84g) Weight

3) IBm (4-2 mm) thermally are stressed glass with eat-rebection technology. Front Cover

Composite film Back Cover

Brack anodized aluminum Frame

 6×10 modernystalline G ANTUM solar cells. Cell

p. 68.8 BByr. v. d. 47.8 Bd in v. 0.00 (r. Burrish) 77 mm. v. 111 Offmin v. 15.19 mm f. Pratection mass 1967, with availst diades. function box

ferm Solar:able (4) ≥39.37 m:1000 mmd, (4.≥33.37 m:1000 mm Cable

Multi Contact MC4 or MC4 intermateable, IP68 Connector




31	ECTRICAL CHARACTERISTICS					
204	VER CLASS			290	795	300
19/15	IMUM PERFORMANCE AT STANDARD TEST CONC	ITIONS STE	CHOWER TOLERAN	CE -5W / OW)		
	Power at MPP	$P_{\mathbf{w}^{\mathrm{op}}}$	EW3	290	295	300
	Short Circuit Current*	16.	[A]	9.63	P / ft	977
100	Open Circuit Voltage*	V_{∞}	IVI	39-19	39.48	39.76
Minemaka	Current at MPP*	1,,,,	(A)	9.07		9.26
-	Voltage at MPP*	Vun	{ ∀ }	11.96	25 · · · · · · · · · · · · · · · · · · ·	32 47
	Efficiency*	rı	12/1	17.4		- 'K ()
7/16	MUM PERFORMANCE AT NORMAL OPERATING O	ONDITIONS N	(OC			
	Power at MPP ²	Pw	(W)	214 4	1.817	221.8
E	Short Circuit Current*	L	(A)		2.80	7.88
Minimum	Open Circuit Voltage	\mathbf{W}_{p}	{ V }	In n	SE DY	*: 1°*
Ž	Current at MPP*	1000	(A)	* 12	7.20	7.27
	Voltage at MPP*	¥	1 4 3	90-12	30.30	30,49

Q CELLS PERFORMANCE WARRANTY

As least till to the commal person during first geal. The stather have 2.6 is proportion, services of least 92 only of months above up to 111 years, 61 have 82 only of minimus some up to 112 years.

All data within more extract transports. Full some type or acceptance with the warrant beans of the ACLL Evalue organisation of some extraction of the ACLL Evalue organisation. If you respective could be




TEMPERATURE COEFFICIENTS

Temperature Coefficient of Is:	e.	1% / KT	-11 fjd	Temperature Coefficient of V _x	B	(%7%)	-11.28
Tampersture Coefficient of P		1%-/K1	.0.39	Normal Operating Cell Temperature	NOCT	1 F1	113 +5,4 (45 + 310)

PROPERTIES FOR SYSTEM D	ESIGN			
Maximum System Voltage V,	(¥)	1,000 (EC) 1,000 (UL)	Safety Class	1-
Maximum Series Fuse Rating	[A DC]	20	Fire Rating	CHECK TYPE : NAL
Design load, push (UL) ²	Hbs/#t*	75 (3G00Pa)	Permitted module temperature on continuous duty	- 40 ° in to - 195 ° 40 °C in to - 85 °C
Design load, pull (UL)?	Hbs/MF.	Bre (2666Pa)	see installation manua-	

QUALIFICATI	ONS AND CERT	IFICATES	PACKAGING INFORMATION	
	in to Textain CE vis		Number of Modules per Pallet	32
FEC # 121 9 (Ed.C)	FEE 64 730 FEG.1:	approation thank A	Number of Pallets per 53' Container	30
	-	(E)	Number of Pallets per 40' Container	24,
DAE	CE	OF.	Pallet Dimensions (t x W x H)	•8 (co. 45 Jury 46 Lur 745 mor • 1150 mor - 1170 mor -
			Patiet Weight	1346 oc 1861 x81

ROTE Installation ending the Compile the Compile the Compile and Compile and Association and Association and the Compile and Association and A



CERTIFIED SHED IS CO. ESPISION

The high-powered smart grid-ready

Enphase IQ 7 Micro¹¹ and Enphase IQ 7+ Micro¹² dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enchase IQ System, the IQ 7 and IQ 7+ Microinverters integrate with the Enchase IQ Envoy ", Enphase IQ Battery ", and the Enphase Enlighten" monitoring and analysis software.

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power on festing, enabling Enphase to provide an industry-leading warranty of up to 25 years.

Lasy to install

- · Lightweight and sample
- · Paster installation with improved, lighter two weedabling
- Buft mapa statidown conclum: (N=C 2014 % 2017).

Productive and Reliable

- Optimized for high powered 60 cell and 72 de 1 produles.
- More than a million bours of testing.
- Classif double-insulated end asunc
- ill Hetan

Smart Grid Ready

- Complies with advanced and support, voltage and frequency add through requirements
- Remotely updates to respond to changing quo requirements
- + Contigurable for varying god profiles.
- Meets CA Rule 21 (Ut. 1741-SA);
- · Harry in Micro stressing to support it are immouled



Enphase 10.7 and 10.7+ Microinverters

INPUT DATA (DC)	107-60-2-US / 107-60-B-US		IQ7PLUS-72-2-US / IQ7PLUS-72-B-US			
Commonly used module pairings'	235 W - 350 W	235 W - 350 W +		235 W - 440 W +		
Module compatibility	60-cell PV modules only		60-cell and 72-cell PV modules			
Maximum input DC voltage	48 V		60 V			
Peak power tracking voltage	27 V 37 V	27 V 37 V				
Operating range	16 V - 48 V		15 V - 60 V			
Min/Max start voltage	22 V. 48 V		22 V + 60 V			
Max DC short circuit current (module isc)	15 A		15 A			
Overvoltage class UE port			. 1			
DC port backfeed current	0 A		O.A.			
Pvi array configuration	1 x 1 unground	ed array: No additio	nal DC side protec	tion reduced.		
	AC side protect	on requires max 20	lA per branch circ	urt		
OUTPUT DATA (AC)	IQ 7 Microinv	erter	IQ 7+ Microin	iverler		
Peak output power	250 VA		295 VA			
Maximum continuous output power	240 VA		290 VA			
Norminal (L-L) voltage/range ²	240 V /	208 V /	240 V /	208 V /		
and the second transfer of the second second when the second seco	211-264 V	183-229 V	211-264 V	183-229 V		
Maximum continuous output current	10 A (240 V)	115 A (208 V)	121A(240 V)	1 39 A (208 V)		
Nominal frequency	60 Hz		60 Hz			
Extended frequency range	47 68 Hz		47 68 Hz			
AC short circuit fault current over 3 cycles	5 8 Arms		5.8 Arms			
Maximum units per 29 A it -l 1 branch o rout	16 (240 VAC)	13 (288 VAD)	13 (240 VAC)	11 (209 VAC)		
Overvoltage class AC port			H			
AC port hackfeed current	0 A		0.4			
Power factor setting	1.0		1.0			
Power factor (adjustable)	0.85 leading	0.85 lagging	0.85 leading	0.85 lagging		
EFFICIENCY	@240 V	@208 V	@240 V	@208 V		
Peak efficiency	976%	97.6 %	975%	97 3 %		
CEC weighted efficiency	970%	97.0%	970"			
MECHANICAL DATA			A CONTRACTOR OF THE PROPERTY O	воир на во на селоно от при во от том по от том от от том от т Станува на при		
Ambient temperature range	-40°C to +65°C					
Relative humidity range	4% to 100% ico					
Cannector type (IQ7 60 2 US & IQ7PLUS 72 2 US			Iditional Q-DCC 5	adapter)		
Connector type (107-60-6-US & 107PT US-72-8-US	Friends PV2 (V Adaptors for an PV2 to MC4 to PV2 to UTX to	IC4 intermateable) others with MC4 or incer ECA 320 S27 rder LC4-S20 S25	UTX connectors			
Dimensions (WxHxĐ)	212 mm x 175 r	nm x 30.2 mm (with	nout bracket)			
Weight	1 08 kg (2 38 lb					
Cooling	Natural convec	tion - No fans				
Approved for wet locations	Yes					
Pollution degree	PD3					
Enclosure		insulated corrosio	n resistant polyme	ario enclosure		
Environmental category / UV exposure rating	NEMA Type 6					
FEATURES			gorg, varynubrischostenbooren oren onzenie presidenterioren			
	Power Line Co.	nmunication (PLC)				
Communication		ager and MyEnlighte	e monitorina ent	E3.11.12		
Menitoring		eger and Myshlighte guire installation of				
Disconnecting means			een evaluated and	approved by UL for use as the load-break		
Compliance	UL 62109-1, UL CAN/CSA-C22 This product is NFC 2017 sect	disconnect required by NEC 690. CA Rule 21 (UL 1741-SA) UL 62109-1, UL1741-SA) UL 62109-1, UL1741/EEE1547, FCC Part 15 Class B, ICES-0003 Class B, CAN/CSA C22 2 NO. 1671 B1 This product is UL Listed as PV Rapid Shut Down Equipment and conforms with NEC-2014 and NEC 2017 section 690.12 and C22 ± 2015 Rule 64 218 Rapid Shutdown of PV Systems, for AQ and C22 ± 2015 Rule 64 218 Rapid Shutdown of PV Systems.				


^{1.} We enforced PCAC care. Sentine compatibility calculator at https://enphase.com/en-us/support/module-compatibility
2. Normal values range can be extended beyond applical if required by the lability
3. Limits may vary. Refer to local requirements to define the number of microrrychers per branch in your area.







Roof Mount System



Built for solar's toughest roofs.

IronRidge builds the strongest roof mounting system in solar. Every component has been tested to the limit and proven in extreme environments.

Our rigorous approach has led to unique structural features, such as curved rails and reinforced flashings, and is also why our products are fully certified, code compliant and backed by a 20-year warranty.



Strength Tested

All components evaluated for superior structural performance.



PE Certified

Pre-stamped engineering letters available in most states.



Class A Fire Rating

Certified to maintain the fire resistance rating of the existing roof.



Design Software

Online tool generates a complete bill of materials in minutes.



Integrated Grounding

UL 2703 system eliminates separate module grounding components.



20 Year Warranty

Twice the protection offered by competitors.

XR Rails

XR10 Rail



A low-profile mounting rail for regions with light snow.

- · 6' spanning capability
- Moderate load capability
- Clear & black anod, finish

XR100 Rail



The ultimate residential solar mounting rail.

- · 8' spanning capability
- Heavy load capability
- · Clear & black anod, finish

XR1000 Rail



A heavyweight mounting rail for commercial projects.

- · 12' spanning capability
- · Extreme load capability
- · Clear anodized finish

Internal Splices



All rails use internal splices for seamless connections.

- · Self-tapping screws
- · Varying versions for rails
- · Grounding Straps offered

Attachments

FlashFoot



Anchor, flash, and mount with all-in-one attachments.

- · Ships with all hardware
- · IBC & IRC compliant
- · Certified with XR Rails

Slotted L-Feet



Drop-in design for rapid rail attachment.

- · High-friction serrated face
- · Heavy-duty profile shape
- · Clear & black anod, finish

Standoffs



Raise flush or tilted systems to various heights.

- · Works with vent flashing
- · Ships pre-assembled
- 4" and 7" Lengths

Tilt Legs



Tilt assembly to desired angle, up to 45 degrees.

- · Attaches directly to rail
- · Ships with all hardware
- Fixed and adjustable

Clamps & Grounding

End Clamps



Slide in clamps and secure modules at ends of rails.

- · Mill finish & black anod.
- Sizes from 1.22" to 2.3"
- Optional Under Clamps

Grounding Mid Clamps



Attach and ground modules in the middle of the rail.

- · Parallel bonding T-bolt
- Reusable up to 10 times
- · Mill & black stainless

T-Bolt Grounding Lugs



Ground system using the rail's top slot.

- · Easy top-slot mounting
- Eliminates pre-drilling
- · Swivels in any direction


Accessories



Provide a finished and organized look for rails.

- Snap-in Wire Clips
- · Perfected End Caps
- · UV-protected polymer

Free Resources



Design Assistant

Go from rough layout to fully engineered system. For free,

Go to IronRidge.com/rm

I DE

NABCEP Certified Training

Earn free continuing education credits, while learning more about our systems.

Go to IronRidge.com/training



DEPARTMENT OF PLANNING AND ZONING PLANNER'S REPORT

DATE: June 5, 2019
TO: Tonya Hutson
FROM: Lynn Patterson

RE: Design Review – 3377 La Vista Drive

BACKGROUND

The City of Hapeville has received a Design Review Application from Tia Muse and Brooke Fortenberry for the addition of solar panels to the roof of the existing building at 3377 La Vista Drive.

The property is zoned R-1, One-Family Detached, and is subject to the Neighborhood Conservation Area, Subarea E, of the Architectural Design Standards.

CODE

- (e) Roof and chimney standards.
 - 1. Principal building roofs for one-family detached dwellings shall have a minimum usable life of thirty (30) years, per manufacturer's warranty.
 - 2. Roof shingles shall be slate, cedar, or asphalt.
 - 3. Roof tiles shall be clay, terra cotta or concrete.
 - 4. Metal roofs are:
 - a. Permitted on one-family and two-family detached dwellings if approved by the design review committee; and
 - b. Permitted on multifamily and townhouse dwellings only when screened from the adjacent street by a parapet wall.
 - 5. Gutters shall be copper, aluminum or galvanized steel.
 - 6. Downspouts shall match gutters in material and finish.
 - 7. Roof forms shall be based on architectural style.
 - 8. All roofs, excluding dormers, shall overhang a minimum of 12 inches beyond the facade.
 - 9. Dormers are permitted on all style homes (unless specified), but shall not be taller than the main roof to which they are attached.
 - 10. Chimneys exposed to the public view may not be faced in wood or cement based siding and may not be of an exposed metal or ceramic pipe. All chimneys shall be wrapped in a brick, stone or suitable masonry finish material.
 - 11. Chimneys on exterior building walls shall begin at grade.
 - 12. Chimneys shall begin at grade and be faced with brick or stacked stone; extend chimneys between three and six feet above the roof line.

FINDINGS

The Architectural Design Standards do not provide guidance for the installation of roof-mounted solar panels. As solar panels are not directly allowed by the code, a Design Exception would be required.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE:
NOTE:	All applications must be typed or neatly printed. Applications or an authorized representative is required to personally appear at the Design Review Meeting to answer questions.
	The Design Review Committee meets the third Wednesday of each month. Every attempt will be made to place your application for review on the next month's agenda following the submittal of a completed application with supporting documents; however, that may not always be possible. The City reserves the right to schedule applications as deemed necessary.
Applicant: Tio	a Muse Brooke Forten berry Contact Number: 770-485-7438
Applicants Add	dress: 2931 Lewis St Ste 300 Kennesaw GA 30144
	s: tig. muse & Creative solarusa, com Zoning Classification:
Address of Pro	oposed Work: 3377 La Vista Dr Hapeville GA 30354
	FORMATION MUST BE PROVIDED): 14 006600010233
Property Owne	er: Isaac Bear Contact Number: 404-862-1886
Project Desci	ar panels to rooftop
Contractors N	Name: Alan Carrier Contact Number: 678-779-6248
Contact Person	on: Ta Muse Contact Number: 770-485-7438
property. I do haccurate, and I application and reserves that rig I further understfull. I hereby ac write the Englis voluntarily comp	pplication to the City of Hapeville, to the Design Review Committee for the above referenced hereby swear or affirm that the information provided here and above is true, complete and understand that any inaccuracies may be considered just cause for invalidation of this any action taken on this application. I understand that the City of Hapeville, Georgia, that to enforce any and all ordinances regardless of any action or approval on this application. I tand that it is my/our responsibility to conform with all of City of Hapeville's Ordinances in knowledge that all requirements of the City of Hapeville shall be adhered to. I can read and in language and/or this document has been read and explained to me and I have full and poleted this application. I understand that it is a felony to make false statements or writings to ville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for violation thereof.
LiaMu	S-6-19
Annlicante 9	Signature

Project Class (check	one):	
Residential	Commercial	Mixed-Use Development
Project Type:		
New Commercial	Construction	Addition to Existing Commercial Building
Addition to Existing	ng Residential Structure	Accessory Structure
Site Plan, Gradin		ew Single Family Residential Construction
Total Square Footage of	proposed New Construction:	
Total Square Footage of	existing building:	
Estimated Cost of Const	ruction: \$14,535	
		existing structure:
(19) Hanwha Q	-Cell Solar Panels	(data sheet provided) rters (data sheet provided)

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does NOT make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)

application, I have received this notice and I read and write the English language or I have had someone read and explain this document to me.



DEPARTMENT OF PLANNING AND ZONING


DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

I, the undersigned, agree that with my signature and submission to the City of Hapeville, I have done the following: $\frac{1}{2}$
Read the City of Hapeville's Architectural Design Guidelines and relevant Code sections for my proposed project. The Architectural Design Guidelines may be found here: https://library.municode.com/ga/hapeville/codes/code of ordinances?nodeld=PTIICOOR CH81ARDEST
Ensured that my proposed project meets all of the required criteria per the City of Hapeville Code of Ordinances.
Submitted my application materials in full by the published deadline for review by Staff prior to the Design Review Committee meeting.
Identified and explained all deficiencies or components of the proposed project that do not meet with the requirements set forth in the Code. This explanation should be submitted as a separate document in the application.
Understood that any deficiencies in the application must be resolved at least 10 days prior to the Design Review Committee meeting or the application may not be presented to the DRC for review.
Submitted architectural drawings and details for all projects unless allowed in writing by the Community Services or Planning & Zoning Department.
Agreed to submit any required revisions by the Design Review Committee with updated drawings to the Community Services Department for review prior to requesting any permits.
Tia Muse Signature S-6-19 Printed Name Signature Date
rifficed traffic

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.

Google Maps 3377 La Vista Dr




Hapeville, Georgia


Google

Street View - Oct 2018

5/30/2019, 11:49 AM



5.7 KW ROOF-MOUNT SOLAR PV ARRAY



NOTES:

1 SHINGLE ROOF, ROOF DECKING IS 1X6 PLANK, 2X6 RAFTERS 22" O/C, CONVENTIONAL FRAMING; PITCH IS 6:12. PRE-MEASURE ALL AREAS TO CLEAR OBSTACLES AND ENSURE PROPER FIT, LEAVING SUFFICIENT ROOM FOR SETBACKS AND ACCESS PATHS.

0/0 243TERS

> 5-P RAIL PAIR: 10' + 7'

10-P RAIL PAIR: 14'+11'+8'6"

- 2 MARK AND ATTACH MOUNTS & RAILS ACCORDING TO LAYOUT & MOUNT AND RAIL PATTERNS. RAIL SPACING IS 33". MOUNTS ARE AT VARYING INTERVALS. MAXIMUM DISTANCE BETWEEN MOUNT AND RAIL-EDGE OR SPLICE IS 24". (MAX MOUNTING SPAN 7') (INNER 50% OF PANEL SHOULD BE BETWEEN RAILS.)
- 3 MOUNT ENPHASE **Q TRUNK CABLE AND IQ7 MICROINVERTERS**, NOTING STRING CONFIGURATION AND RECORDING MICROINVERTER S/N/S. INSTALL TERMINATORS AND UNUSED CONNECTOR CAPS. RUN ALL GROUNDS. USE LFMC AND 600V PV WIRE.
- INSTALL SOLADECK, VERIFYING POSITION IN ATTIC BEFORE PENETRATING ROOF, AND WIRE HOME RUNS. RUNS ARE 600V.
- 5 MOUNT & CONNECT PANELS CENTERED OVER RAILS, RECORDING PANEL S/N'S. RAIL OVERHANGS ARE APROX. 2-3" PAST PANELS. CONNECT ALL JUMPERS, MANAGE WIRES, SEPARATION DISTANCE BETWEEN ADJACENT PANELS \$-15"

	ABMA WASOL	CERT	Swar	ACTITIO.
	CK'D			
	ВУ	RE6		
REVISIONS	DESCRIPTION	PROPOSAL v1		
	DATE	05/13/19		





മഥ	00 x0		
8 4	4.8		Z
മന			TIO
8 2		AA	STRING CONFIGURATION (NTS)
8 4		11 12	NFIG (NTS)
٧	∀ 0		N Z
K 57	40		90
4 m	₹ 60		TRI
44	4 N		S
< r∪	₹ •0		

SATED WITH THE FOLLOWING MINIMUMS MET:

- *BUILDING MEAN ROOF HEIGHT <= 30 FT
 *RAFTER SPACING 24" MAX
 *RISK CATEGORY II
 *WIND EXPOSIBE B
 *WIND SPEED <= 110 MPH
 *GROUND SNOW LOAD <= 15 PSF
 ARRAY DISTRIBUTED WEIGHT <+ 4.0 PSF
 AND <= 35 LBS PER ATTACHMENT
 *MAX GAP BENEATH MODULE FRAME <= 7"
 *MAX GAP BENEATH MODULE FRAME <= 7"
 *WAT SAP BENEATH MODULE FRAME <= 7"
 *WAT SAP BENEATH MODULE FRAME <= 7"
 *VPILFT, DOWN FORCE, AND SHEAR FORCE OF
 167 LB, 258 LB, AND 135 LB RESPECTIVELY



OVERHEAD MOCK-UP (NTS)

Creative Solar USA, Inc.

Kennesaw, 6a 30144 Russell Seifert: 770-378-9668 www.creativesolarusa.com 2931 Lewis Street

REG	ENG/DRA:	05-13-2019	DATE:	1 OF 1	PAGE:	
		SCALE: 1" = 12' (OUTPUT: 8.5 X 11 LANDSCAPE)	PUT: 8.5 X	1" = 12' (OUT	SCALE:	
	54	ADDRESS: 3377 LA VISTA DR, HAPEVILLE, GA 30354	TA DR, HA	3377 LA VIS	ADDRESS:	
				CUSTOMER: ISAAC BEAR	CUSTOMER:	
		TITLE: 5.7 KW ROOF-MOUNT SOLAR PV ARRAY	F-MOUNT	5.7 KW ROOI	TITLE:	

(4) - #10 XHHW, (1) - #8 XHHW GND #8 4-WIRE REG EXISTING GRID **DESCRIPTION** #12 Q CABLE (ENPHASE) Creative Solar USA, Inc. ENG/DRA: CONDUIT AND WIRE SCHEDULE 5.7 KW DC PV ARRAY - SINGLE-LINE ELECTRICAL 2931 Lewis Street Kennesaw, 6a 30144 Russell Seifert: 770-378-9668 www.creativesolarusa.com 3377 LA VISTA DR, HAPEVILLE, GA 30354 **EXISTING EXISTING** VTILITU METER 05-13-2019 OR LOAD-SIDE TAP AT METER BREAKER ADD (1) 2P 30A CIRCUIT BREAKER CONDUIT DATE: **EXISTING** 120/240V N/A IMC ISAAC BEAR (m) 1 OF 1 NON # OF RUN m2 8# AC DISCONNECT 3R FUSIBLE BLADED 60A 240V, 1-PH ADDRESS: SCALE: CUSTOMER: PV UTILITY PAGE: (9) CKD COMBINED MAX CONTINUOUS AC OUTPUT CURRENT AT (2) 2P 20A CIRCUIT BREAKERS 4. COMBINER BOX WITH IQ ENVOY REG 8 240V OF 19A. 5.7 KW DC PV ARRAY - SINGLE-LINE ELECTRICAL 4 REVISIONS DESCRIPTION PROPOSAL v1 (7) **BRANCH #2** (1) AC BRANCH CIRCUIT JUNCTION BOX /SOLADECK BRANCH #1 3. TRANSITION BOX 05/13/19 DATE NOITISNA91 XO8 $^{\circ}$ MICROTIVERTERS. ROOF-MOUNTED, UNDER EACH PANEL. MAX CONTINUOUS AC OUTPUT POWER 240VA NOMINAL AC OUTPUT CURRENT AT 240V SINGLE PHASE OF 1.0A. (2) BRANCHES AT (12 & 7) INVERTERS FER STRING, CONNECTED IN SERIES. (MAX I6 UNITS FER ZOR BRANCH, 240VAC). (2) STRINGS IN PRABLLEL. MAX CONT AC OUTPUT POWER 4,560 VA TOTAL. MAX CONTINUOUS AC OUTPUT CURRENT AT 240V OF EACH PROTECTED AT 20A. NEC 2014 & 2017 SECTION 690.12 COMPLIANT #12, 1000V (-PER NEC 690.43 PANELS ARE GROUNDED TO STRUCTURE VIA WEEB GROUNDING CLIPS OR BONDING CLAMPS 7A PER 7-INVERTER BRANCH, 12A PER 12-INVERTER BRANCH, (19) ENPHASE IQ7-60-2-US UL1741/IEEE1547 2. INVERTERS -Q CABLE Q CABLE (12 AWG) BLACK-L1 RED-L2 2 <u>₽</u> ~ 12 12 EQUIPMENT GROUND TO STRUCTURE VIA WEEBS OR EQUIVALENT TERMINATOR CAP INSTALLED ON END OF CABLE SHORT CIRCUIT CURRENT 9.72A. EACH WIRED TO INDIVIDUAL INVERTERS. 5,700 WATTS TOTAL. UL1703 (19) JINKO SOLAR EAGLE PERC 60 JKM300M-60, 300W PV PANELS 60-CELL, MOND-CRYSTALLINE. ROOF-MOUNTED. 1. PV ARRAY SOURCE CIRCUIT



Eagle PERC 60 280-300 Watt

MONO CRYSTALLINE MODULE


Positive power tolerance of 0~+3%

ISO9001:2008-ISO14001:2004-OHSAS18001

IEC61215-IEC61730 certified products.







KEY FEATURES

4 Busbar Solar Cell:

 purbar rolar coll adoptit new technology to improve the left clandy of manufes offer a better aesthete appearance making I perfect for metter installation.



High Efficiency:

righer madure convenion efficier cyrup to 18 33° . I benefit from Paus viates Ammiter Boar Contact (PSPC), technology,



PID RESISTANT:

united bower degradation of Engle module caused by PiD effect is quaranteed under strict testing condition (55% 1789 APP). Penals from mass production



low-light Performance:

Advanced glass and solar delimitace texturng allow for excellent performance in low light environment



Severe Weather Resilience:

Cartitled to withstaurd wind load (2400 Parcal) and show load (5400 Parcal)



Durability against extreme environmental conditions:

eignisal mist and ammenia resistance codited by Tury MDRD















LINEAR PERFORMANCE WARRANTY

10 Year Product Warranty . 25 Year Linear Power Warranty




Engineering Drawings



Packaging Configuration

Electrical Performance & Temperature Dependenc



Mechanical	Characteristics
e Type	Mone crystalline PERC 156 - 156 mm to inche
No.of cells	60 (6×10)
Distance	teste in a sillarer segni z sitte vitin segn
Weight	19.0 kg (41.9 lbs)
	Fight 11 second on the first temperations
Frame	Anodized Aluminium Alloy
g men en Hein	1997 The general

Output Cables, 1034 1 > 4 Omm! Length, 900mm or Customized Length

SPECIFICATIONS

Module Type	JEM/SOPASO	#KM285D-60	KM200M-60	JKM295M-60	JRM300M-80
	STE NOCT	STC NOCT	STE NOCT	STC NOCE	STC NOCT
Maximum Howel Photos	PROME SCHOOL	PREMA POTAN		295Wo 220We	30074n 224VVp
Maximum Power Voltage (Vmp)	31 8V 29 7V	32 07/ 39 97/	32.2V 30.2V	32.4V 30.4V	32.6V 30 6V
Maxim to Prove Corseil (Imp.)	881A 701A		9,70A 115A	9,10A 7,24A	9.21A 7.32A
Open-circuit Voltage (Voc)	39.6V 36.2V	38.7V 36.4V	39 5V 36 6V	39.7V 36.8V	40.1V 37.0V
Short elever Current (Isc)	9.496 7.626	ALTA COMA	91.50 1916	PARTA PERA	9.72A #.D1A
Module Efficiency STC (%)	17.11%	17,41%	17.72%	18.02%	18 33%
Operating (emperature) C.			4117 415		
Maximum system voltage			1000VDG (IEC.)		
Maximum series have rating					
Power tolerance			0-+3%		
Principlature coefficients of Empo					
Temperature coefficients of Voc					
Tereberature coefficients of ki					
Nominal operating cell temperature (NOCT)			45±27		













Wind Speed Imys

[•] Proper measurement trilerance: ± 4%

Enphase IQ 7 and IQ 7+ Microinverters


The high-powered smart grid-ready

Enphase IQ 7 Micro** and Enphase IQ 7+ Micro**

dramatically simplify the installation process while achieving the highest system efficiency.

Part of the Enchase IQ System, the IQ 7 and IQ 7+ Microinverters integrate with the Enchase IQ Envoy™, Enphase IQ Battery *, and the Enphase Enlighten™ monitoring and analysis software

IQ Series Microinverters extend the reliability standards set forth by previous generations and undergo over a million hours of power on testing, enabling Enphase to provide an industry-leading warranty of up to 25 years.



Easy to Install

- · Lightweight and simple
- Faster installation with intoroved, lighter two wire sabling.
- Built mirapid shutdown compliant (NEC 2014 & 2017).

Productive and Reliable

- Optimized for high powered 60 cell and 72 qga* modules.
- More than a million hours of testing.
- · Class II double-insulated enclosure
- Ul listen

Smart Grid Ready

- Compiles with advanced and support, voltage and frequency ride through requirements
- Remotely updates to respond to changing grid requirements
- Configurable for varying quid profiles.
- Meets CA Rule 21 (UL 1741-SA)

as it; if Micro is required to support it? cell requires.





Enphase IQ 7 and IQ 7+ Microinverters

INPUT DATA (DC)	107-60-2-US	1Q7-50-B-US	107PLUS-72-2	-US / 107PLUS-72-B-US	
Commonly used module pairings'	235 W - 350 W -		235 W - 440 W	*	
Module compatibility	60 cell PV mod	ules only	60-cell and 72-cell PV modules 60-V		
Maximum input DC voltage	48 V				
Peak power tracking voltage	27 V 37 V		27 V - 45 V		
Operating range	16 V - 48 V		16 V - 60 V		
Miry/May start voltage	22 V / 48 V		22 V / 60 V		
Max DC short circuit current (module (sc)	15 A		15 A		
Qvervoltage class (16 port			11		
DC port backfeed current	0 A		0 A		
PM acray configuration		ed array. No additio ron requires max. 20			
OUTPUT DATA (AC)	10 7 Microinve	erter	10,7+ Microin	verter	
Peak output power	250 VA		295 VA		
Maximum cantiqueus output power	246 VA		290 VA		
Nominal (L-L) voltage/range ²	240 V / 211-264 V	208 V / 183-229 V	240 V / 211-264 V	208 V / 183-229 V	
Maximum continuous output current	1 0 A (240 V)	115 A (208 V)	121A (240 V)	1 39 A (208 V)	
Nominal frequency	60 Hz		60 Hz		
Extended frequency range	47-68 Hz		47 68 Hz		
AC short circuit fault current over 3 cycles	5 8 Arms		5.8 Arms		
Maximum units per 20 A (I-I) branch circuit	16 (240 VAC)	13 (208 VAC)	13 (240 VAC)	11 (208 VAC)	
Overvoltage class AC port			111		
AC port backfeed current	0 A		0.4		
Power factor setting	1.0		1.0		
Power factor (adjustable)	0.85 leading	0.85 lagging	0.85 leading	n as lagging	
EFFICIENCY	@240 V	@208 V	@240 V	@208 V	
Peak efficiency	976%	97.6 %	975%	973%	
CEC weighted efficiency	970%	97.0 %	97.0 %	97.0 %	
MECHANICAL DATA	and proceedings of the Confession of Confess	nazada dapon e Manglasia y Administrada e Santa Antonio y Anglasia	Share, e fermane me Spirit di Spirit in Ferman in agricum supprimi purpagni	One were the fiber of the first security by the disk good process and the grant consequency above accommon and gry party and the security of the grant of the gra	
Ambient temperature range	-40°C to +65°C				
Refative humidity range	4% to 700% (condensing)				
Connector type (IQ7-60-2-US & IQ7PLUS-72-2-US)	MC4 for Amphe	mol H4 UTX, with ac	iditional Q-DCC-5	adapter)	
Connector type (IG7-63-B-US & IG7P(FUS-72-B-US)					
Dimensions (WxHxD)	212 mm x 175 n	nm x 30.2 mm (with	nout bracket)		
Weight	1 08 kg (2 38 lb	6)			
Cooling	Natural convect	ion - No fans			
Approved for wet locations	Ves				
Pallution degree	PD3				
Enclasure	Class II double-	insulated corrosio	n resistant polyme	ric enclosure	
Environmental category / UV exposure rating	NEMA Type 6 /		, , , , , , , , , , , , , , , , , , , ,		
FEATURES					
Communication	Power Line Con	nmunication (PLC)			
Monitorina		ger and MyEnlighte	er mon it arina optic	ons	
Disconnecting means	Both options re	quire installation of	f an Enphase IQ En		
	disconnect requ	urred by NEC 690		AL STATE	
Complance	CAN/CSA-C22	1741/1 <u>EEE 1</u> 547, FOC 2 NO 107.1-01		CES-6000 Class B, upment and conforms with NEC-2014 and	
				8 Rapid Shetdown of PV Systems, for AC acturer's instructions	


^{1.} No enforced by "Afficians. See the compatibility calculator at https://enphase.com/en-us/support/module-compatibility
2. Normal voltage tongs can be extended beyond normal if required by the stillty
3. Limits may vary Before local requirements to define the number of microim-orien per stanch in your area.







Roof Mount System



Built for solar's toughest roofs.

IronRidge builds the strongest roof mounting system in solar. Every component has been tested to the limit and proven in extreme environments.

Our rigorous approach has led to unique structural features, such as curved rails and reinforced flashings, and is also why our products are fully certified, code compliant and backed by a 20-year warranty.



Strength Tested

All components evaluated for superior structural performance.



PE Certified

Pre-stamped engineering letters available in most states.



Class A Fire Rating

Certified to maintain the fire resistance rating of the existing roof.



Design Software

Online tool generates a complete bill of materials in minutes.



Integrated Grounding

UL 2703 system eliminates separate module grounding components.



20 Year Warranty

Twice the protection offered by competitors.

XR Rails

XR10 Rail



A low-profile mounting rail for regions with light snow.

- · 6' spanning capability
- · Moderate load capability
- · Clear & black anod, finish

XR100 Rail



The ultimate residential solar mounting rail.

- 8' spanning capability
- · Heavy load capability
- · Clear & black anod, finish

XR1000 Rail



A heavyweight mounting rail for commercial projects.

- · 12' spanning capability
- · Extreme load capability
- · Clear anodized finish

Internal Splices



All rails use internal splices for seamless connections.

- · Self-tapping screws
- · Varying versions for rails
- Grounding Straps offered

Attachments

FlashFoot



Anchor, flash, and mount with all-in-one attachments.

- · Ships with all hardware
- · IBC & IRC compliant
- · Certified with XR Rails

Slotted L-Feet



Drop-in design for rapid rail attachment.

- · High-friction serrated face
- · Heavy-duty profile shape
- · Clear & black anod, finish

Standoffs



Raise flush or tilted systems to various heights.

- · Works with vent flashing
- · Ships pre-assembled
- · 4" and 7" Lengths

Tilt Legs



Tilt assembly to desired angle, up to 45 degrees.

- · Attaches directly to rail
- · Ships with all hardware
- · Fixed and adjustable

Clamps & Grounding

End Clamps



Slide in clamps and secure modules at ends of rails.

- · Mill finish & black anod.
- Sizes from 1.22" to 2.3"
- · Optional Under Clamps

Grounding Mid Clamps 💮



Attach and ground modules in the middle of the rail.

- Parallel bonding T-bolt
- Reusable up to 10 times
- · Mill & black stainless

T-Bolt Grounding Lugs



Ground system using the rail's top slot.

- Easy top-slot mounting
- Eliminates pre-drilling
- · Swivels in any direction

Accessories



Provide a finished and organized look for rails.

- · Snap-in Wire Clips
- · Perfected End Caps
- · UV-protected polymer

Free Resources



Design Assistant

Go from rough layout to fully engineered system. For free.

Go to IronRidge.com/rm

İ

NABCEP Certified Training

Earn free continuing education credits, while learning more about our systems.

Go to IronRidge.com/training



DEPARTMENT OF PLANNING AND ZONING PLANNER'S REPORT

DATE: June 4, 2019
TO: Tonya Hutson
FROM: Lynn Patterson

RE: Design Review – 600 South Central Avenue

BACKGROUND

The City of Hapeville has received a Design Review Application from Casey Montana Busch for the addition of solar panels to the roof of the existing building at 600 South Central Avenue.

The property is zoned RMU, Residential Mixed-Use, and is subject to the Commercial/Mixed-Use Area, Subarea B, of the Architectural Design Standards.

CODE

Sec. 81-1-6. - Commercial/mixed-use area.

- (f) Roof and chimney standards.
 - 1. Principal building roofs for one-family detached dwellings shall have a minimum usable life of 30 years, per manufacturer's warranty.
 - 2. Roof shingles shall be slate, cedar, or asphalt.
 - 3. Roof tiles shall be clay, terra cotta or concrete.
 - 4. Street-facing gutters shall be copper, aluminum or galvanized steel.
 - 5. Downspouts shall match gutters in material and finish.
 - 6. Metal flashing, where utilized, shall be copper or factory-finished sheet metal and shall be of a color that blends with other building materials.
 - Chimneys visible from a public right-of-way shall not be faced in wood or fiber cement siding and shall not be a metal or ceramic pipe. Chimneys shall be wrapped in a full-depth brick, stone or masonry finish material.
 - 8. Chimneys located on an exterior building wall shall begin at grade.
 - 9. Flat roofs shall be permitted.
 - 10. Buildings with sloped roofs not completely screened from the adjacent street by a parapet shall have a pitch between 4:12 and 12:12. Mansard roofs are prohibited. Pitched-roof materials are limited to roof shingles, natural slate, wood shake, factory-finished sheet metal, and terra cotta tile, unless determined to be historically appropriate by the planning and zoning manager.
 - 11. Roof-mounted lights and flagpoles are prohibited. Roof-mounted satellite dishes or telecommunication devices shall be screened from public view and shall blend with the background of the building as practical.

12. In subarea A roof lines shall appear flat from the adjacent street and roof structures shall be vertically screened by a parapet wall.

FINDINGS

The Architectural Design Standards do not provide guidance for the installation of roof-mounted solar panels. As solar panels are not directly allowed by the code, a Design Exception would be required.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE: JUN 0 4 2019		
NOTE:	All applications must be ty authorized representative is required. Meeting to answer questions.		
	The Design Review Committee Every attempt will be made to month's agenda following the supporting documents; howeve reserves the right to schedule ap	place your application for submittal of a complete r, that may not always be	review on the next ed application with possible. The City
Applicant:	Casey Montana Busch	Contact Number:	678-672-8822
Applicants Add	dress: 615 Deer Run SW	Lilburn, GA 30047	
E-Mail Address	s: _montana@altenergyse.co	m Zoning Classification:	Commercial
Address of Pro	pposed Work:600 S Cer	ntral Ave. Hapeville GA	30354
Parcel ID# (INF	ORMATION MUST BE PROVIDED)	: 14 009800200513	
Property Owne	er: Dr. Jay Prakash	Contact Number:	
	ription (including occupancy ty stem. Commercial building (ounted, ballasted
	Name: <u>Alternative Energy S</u>		
I hereby make approperty. I do haccurate, and I application and reserves that rig I further underst full. I hereby acwrite the English voluntarily compthe City of Hapen	pplication to the City of Hapeville, to hereby swear or affirm that the informunderstand that any inaccuracies many action taken on this application to enforce any and all ordinances mand that it is my/our responsibility to knowledge that all requirements of the language and/or this document hableted this application. I understand to ville, Georgia pursuant to O.C.G.A. 16	the Design Review Committee formation provided here and above may be considered just cause form. I understand that the City regardless of any action or approposition of City of Hajardles of the City of Hajardles been read and explained to reat it is a felony to make false st	or the above referenced is true, complete and for invalidation of this of Hapeville, Georgia, aval on this application. peville's Ordinances in ered to. I can read and the and I have full and attements or writings to or violation thereof.

Project Class (check one):
ResidentialCommercialMixed-Use Development
Project Type:
New Commercial ConstructionAddition to Existing Commercial Building
Addition to Existing Residential StructureAccessory Structure
Site Plan, Grading & LandscapingNew Single Family Residential Construction
Other Installation of roof-mounted, ballasted solar PV system
Total Square Footage of proposed New Construction: PV System Footprint: Approx 4500sqft
Total Square Footage of existing building: Rooftop: Approx 6000sqft
Estimated Cost of Construction:\$172,000.00
List/Describe Building Materials on the exterior of the existing structure:
The solar panels will be installed on the flat roof via a non-penetrating, fully ballasted mounting system. They will not be visible from the ground. The conduit from the
roof will be installed inside of a chase and will not be visible from the outside.
List/Describe Building Materials <u>proposed</u> for the exterior facade of the new structure:
No changes to the exterior facade.

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does NOT make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)

Casey Montana Busch wear or affirm that before receipt of an application, I have received this notice and I read and write the English language or I have had someone read and explain this document to me.



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

I, the undersigned, agree that with my signature and submission to the City of Hapeville, I have done t following:
Read the City of Hapeville's Architectural Design Guidelines and relevant Code sections for my proposed project. The Architectural Design Guidelines may be found here: https://library.municode.com/ga/hapeville/codes/code of ordinances?nodeId=PTIICOOR CH81ARDES
Ensured that my proposed project meets all of the required criteria per the City of Hapeville Code of Ordinances.
Submitted my application materials in full by the published deadline for review by Staff prior to the Design Review Committee meeting.
Identified and explained all deficiencies or components of the proposed project that do not meet with the requirements set forth in the Code. This explanation should be submitted as a separate document in the application.
✓ Understood that any deficiencies in the application must be resolved at least 10 days prior to the Design Review Committee meeting or the application may not be presented to the DRC for review
✓ Submitted architectural drawings and details for all projects unless allowed in writing by the Community Services or Planning & Zoning Department.
Agreed to submit any required revisions by the Design Review Committee with updated drawings to the Community Services Department for review prior to requesting any permits.
Casey Montana Busch Printed Name Signature Date
Printed Name Signature Date
Should you have any questions, please do not hesitate to contact the Community Services Department

at 404-669-2120.


Thank you for interest and investment in the City of Hapeville.

One-Line Diagram

600 S Central Ave. Hapeville, GA 30354

38.2kW Solar PV System

(106) RISEN RSM72-6-360M PV Modules



Alternative Energy Southeast
Atlanta, GA | Phone: 770.490.6178
Info@AltEnergySE.com | www.AltEnergySE.com

Page #6: Obstructions 600 S Central Ave Atlanta GA 30354 US Roof Vent, Roof Drain, other thing Roof Drain (flush) 2x2x2 Roof Vent Roof Drain (flush) 42' Cooling Tower **Cooling Tower** Roof Drain (flush) 2x2x2 Roof Vent 26' 1: 4'L x 4'W x 3'H 2: 10' x 9' x 7' 3: 9' x 2' x 3' 4: 3' x 4' x .5' Roof Vent, Roof Hatch, other thing

Alternative Energy Solutions; Sollega Solar Project; 600 S Central Ave, Hapeville, GA 30354, USA





FastRack510™

The simple solar racking solution for flat roof or ground mount PV installations.

- 5° or 10° mounting solution
- · Simple, modular, one piece design
- · Universal design compatible with all framed modules
- · Fully ballasted, heat welded, anchored and hybrid options
- Roof friendly with round edges and low point loads

- · One size bolt with all top down connections
- · Injection molded with Ultramid® by BASF
- · Engineering and ballast layout services available
- · UL 1703 Class "A" Type 1 and 2 Module
- · UL 467 Integrated grounding
- · 100% Recyclable

Easy to install:







2 Add Ballast and Clamps




Attach Modules





FastRack510™








The Simple Solar Racking Solution™

Tilt Angle	5°	10°	
Row Spacing	10" (254 mm)	13" (330 mm)	
Leading Edge	8" (203 mm)	5.3" (135 mm)	
Compatible Modules	All-framed modules 31" - 44" in width (787 mm and 1117 mm)		
Weight	4.5 lbs. (2 kg)		
Ballast Requirements	4" x 8" x 16" Roof Paver (31.5 lbs each) based on ASTM Designation C1491 – 01a.		
Material	BASF Ultramid [®] glass reinforced nylon		
Module Orientation	Landscape		
Wind Load Criteria	Meets ASCE 7-10 up to 165 mph		
UL Certification	UL 1703: Class 'A' Type 1,2,3 Module, UL467		
Warranty	25 Year Limited Warranty		
Dimensions	(LxWxH) 24.25 x 29 x 14" 616 x 737 x 356mm		
Disassembly	Simple disassembly and 100% recyclable content		
Patent	Patented design: US		



HIGH PERFORMANCE MONOCRYSTALLINE PERC MODULE

RSM72-6-360M-380M

72 CELL MONOCRYSTALLINE MODULE

360-380Wp POWER OUTPUT RANGE

1500VDC MAXIMUM SYSTEM VOLTAGE

19.6% MAXIMUM EFFICIENCY



About Risen Energy

Risen Energy is a leading, global tier 1 manufacturer of high-performance solar photovoltaic products and provider of total business solutions for residential, commercial and utility-scale power generation. The company, founded in 1986, and publicly listed in 2010, compels value generation for its chosen global customers. Techno-commercial innovation, underpinned by consummate quality and support, encircle Risen Energy's total Solar PV business solutions which are among the most powerful and cost-effective in the industry. With local market presence and strong financial bankability status, we are committed, and able, to building strategic, mutually beneficial collaborations with our partners, as together we capitalise on the rising value of green energy.

KEY SALIENT FEATURES



Global, Tier 1 bankable brand, with independently certified state-of-the-art automated manufacturing



Industry leading lowest thermal co-efficient of power



Industry leading 12 years product warranty



Excellent low irradiance performance



Excellent PID resistance



Positive tight power tolerance



Dual stage 100% EL Inspection warranting defect-free product



Module Imp binning radically reduces string mismatch losses



Warranted reliability and stringent quality assurances well beyond certified requirements



Certified to withstand severe environmental conditions

- Anti-reflective & anti-soiling surface minimise power loss from dirt and dust
- Severe salt mist, ammonia & blown sand resistance, for seaside, farm and desert environments
- Excellent mechanical load 2400Pa & snow load 5400Pa resistance







ISO9001 ISO14001 OHSAS18001 IEC TS 62941






















Tashan Industry Zone, Meilin, Ninghai 315609,Ningbo | PRC


Tel: +86-574-59953239 Fax: +86-574-59953599


E-mail: marketing@risenenergy.com Website: www.risenenergy.com
















ELECTRICAL DATA (STC)					
Model Number	RSM72-6-360M	RSM72-6-365M	RSM72-6-370M	RSM72-6-375M	RSM72-6-380N
Rated Power in Watts-Pmax(Wp)	360	365	370	375	380
Open Circuit Voltage-Voc(V)	47.30	47.70	48.15	48.60	48.95
Short Circuit Current-Isc(A)	9.80	9.85	9.90	9.95	10.00
Maximum Power Voltage-Vmpp(V)	38.95	39.25	39.60	39.95	40.25
Maximum Power Current-Impp(A)	9.25	9.30	9.35	9.40	9.45
Module Efficiency (%)	18.6	18.8	19.1	19.3	19.6

STC: Irradiance 1000 W/m², Cell Temperature 25°C, Air Mass AM1.5 according to EN 60904-3.

ELECTRICAL DATA (NMOT)					
Model Number	RSM72-6-360M	RSM72-6-365M	RSM72-6-370M	RSM72-6-375M	RSM72-6-380N
Maximum Power-Pmax (Wp)	269.3	272.8	276.8	280.7	284.3
Open Circuit Voltage-Voc (V)	43.50	43.90	44.30	44.70	45.00
Short Circuit Current-Isc (A)	8.04	8.08	8.12	8.16	8.20
Maximum Power Voltage-Vmpp (V)	35.70	36.00	36.30	36.60	36.90
Maximum Power Current-Impp (A)	7.55	7.59	7.63	7.67	7.71

NMOT: Irradiance at 800 W/m², Ambient Temperature 20°C, Wind Speed 1 m/s.

MECHANICAL DATA				
Solar cells	Monocrystalline 156.75×156.75 mm, 5BB			
Cell configuration	72 cells (6×12)			
Module dimensions	1956×992×40mm			
Weight	22kg			
Superstrate	3.2 mm, High Transmission, Low Iron, Tempered ARC Glass			
Substrate	White Back-sheet			
Frame	Anodized Aluminium Alloy type 6063T5, Silver Color			
J-Box	Potted, IP67, 1500VDC, 3 Schottky bypass diodes			
Cables	4.0mm² (12AWG), 1200mm length			
Connector	Risen Twinsel PV-SY02, IP67			

TEMPERATURE & MAXIMUM RATINGS			
Nominal Module Operating Temperature (NMOT)	45°C±2°C		
Temperature Coefficient of Voc	-0.29%/°C		
Temperature Coefficient of Isc	0.05%/°C		
Temperature Coefficient of Pmax	-0.39%/°C		
Operational Temperature	-40°C~+85°C		
Maximum System Voltage	1500VDC		
Max Series Fuse Rating	20A		
Limiting Reverse Current	20A		


PACKAGING CONFIGURATION					
	40ft	20ft			
Number of modules per container	648	270			
Number of modules per pallet	27	27			
Number of pallets per container	24	10			
Packaging box dimensions (LxWxH) in mm	1980×1130×1130	1980×1130×1130			
Box gross weight[kg]	640	640			

CAUTION: READ SAFETY AND INSTALLATION INSTRUCTIONS BEFORE USING THE PRODUCT.

©2019 Risen Energy. All rights reserved. Specifications included in this datasheet are subject to change without notice.

Three Phase Inverters

For the 277/480V Grid for North America SE10KUS / SE20KUS / SE30KUS / SE33.3KUS



INVERTERS

The best choice for SolarEdge enabled systems

- Specifically designed to work with power optimizers
- Superior efficiency (98.5%)
- Integrated arc fault protection and rapid shutdown for NEC 2014 and 2017, per article 690.11 and 690.12
- UL1741 SA certified, for CPUC Rule 21 grid compliance
- Built-in module-level monitoring

- Internet connection through Ethernet or Wireless
- Small, lightweight, and easy to install outdoors or indoors on provided bracket
- Fixed voltage inverter for longer strings
- Integrated Safety Switch
- Supplied with RS485 Surge Protection Device, to better withstand lightning events



/ Three Phase Inverters

For the 277/480V Grid⁽¹⁾ for North America SE10KUS / SE20KUS / SE30KUS / SE33.3KUS

All the control of th	SE10KUS	SE20KUS	SE30KUS	SE33.3KUS	
OUTPUT					
Rated AC Power Output	10000	20000	30000	33300	VA
Maximum AC Power Output	10000	20000	30000	33300	VA
AC Output Line Connections		4-wire WYE (L1-L	2-L3-N) plus PE		
AC Output Voltage Minimum-Nominal-Maximum ⁽²⁾ (L-N)		244-27	77-305		Vac
AC Output Voltage Minimum-Nominal-Maximum ⁽²⁾ (L-L)		422.5-4	80-529		Vac
AC Frequency Min-Nom-Max [©]		59.3 - 6	0 - 60.5		Hz
Max. Continuous Output Current (per Phase)	12	24	36.5	40	А
GFDI Threshold		1			А
Utility Monitoring, Islanding Protection, Country Configurable Set Points		Ye	25		
INPUT					
Maximum DC Power (Module STC)	13500	27000	40500	45000	W
Fransformer-less, Ungrounded		Ye	es	1	
Maximum Input Voltage DC to Gnd		49	00		Vdc
Maximum Input Voltage DC+ to DC-		98	80		Vdc
Nominal Input Voltage DC to Gnd		42	10		Vdc
Nominal Input Voltage DC+ to DC-		84	10		Vdc
Maximum Input Current	13.5	26.5	39	40	Adc
Maximum Input Short Circuit Current		4	5	1	Adc
Reverse-Polarity Protection		Ye	·s		
Ground-Fault Isolation Detection	1MΩ Se	nsitivity	350kΩ Se	ensitivity ⁽³⁾	
CEC Weighted Efficiency	98	3	98	3.5	%
Night-time Power Consumption	< 3		4	W	
ADDITIONAL FEATURES					
upported Communication Interfaces		RS485, Ethernet, 2	ZigBee (optional)		T
Rapid Shutdown – NEC 2014 and 2017 690.12	Auto	omatic Rapid Shutdown	upon AC Grid Disconr	nect	
RS485 Surge Protection	Supplied with the inverter				
STANDARD COMPLIANCE					
afety	UL1741, UL1	741 SA, UL1699B, CSA C		ccording to	
Grid Connection Standards	IEEE1547, Rule 21, Rule 14 (HI)				
missions		FCC part1	5 class B		
NSTALLATION SPECIFICATIONS					- Angelia
AC output conduit size / AWG range	3/4" minimum / 12-6 AWG 3/4" minimum / 8-4 AWG		m / 8-4 AWG		
DC input conduit size / AWG range	3/4" minimum / 12-6 AWG				
Number of DC inputs	2 pairs 3 pairs ⁽⁴⁾		irs ⁽⁴⁾		
Dimensions (H x W x D)		21 x 12.5 x 10.5 /	540 x 315 x 260		in / mr
Dimensions with Safety Switch (H x W x D)	30.5 x 12.5 x 10.5 / 775 x 315 x 260			in / mr	
Veight	73.2 / 33.2 99.5 / 45		/ 45	lb / kg	
Veight with Safety Switch	79.7 / 36.2 106 / 48			lb / kc	
Cooling		Fans (user re			
Voise	< 5	0	<	55	dBA
Operating Temperature Range		-40 to +140 /			°F / °C
Protection Rating	NEMA 3R				

[©] For 208V inverters refer to: http://www.solaredge.com/files/pdfs/products/inverters/se-three-phase-us-inverter-208V-datasheet.pdf © For other regional settings please contact SolarEdge support © Where permitted by local regulations

 ${}^{\text{(s)}} \ For power de-rating information refer to: https://www.solaredge.com/sites/default/files/se-temperature-derating-note-na.pdf$

⁴⁹ Field replacement kit for 1 pair of inputs P/N: DCD-3PH-1TBK; Field replacement kit for 3 pairs of fuses and holders P/N: DCD-3PH-6FHK-S1



PLANNING AND ZONING DEPARTMENT

PLANNER'S REPORT

DATE: June 5, 2019

TO: Tonya Hutson

FROM: Lynn M. Patterson

Compliant:

Not Compliant:

Incomplete:

RE: Design Review - 3365 Northside Drive

BACKGROUND

The City of Hapeville has received a design review application from Paula Smith to construct a 1.5 story single-family dwelling with an attached garage at 3365 Northside Drive. The dwelling will have 3,548 SF of finished heated floor area with an additional 525 SF of unfinished space available. It will include four bedrooms and three and a half bathrooms, with an optional unfinished fifth bedroom.

The property is zoned R-0, One-Family Residential, and is subject to the Neighborhood Conservation Area, Subarea D, of the Architectural Design Standards.

CODE

SEC. 81-1-7. NEIGHBORHOOD CONSERVATION AREA

Based on goals established in this chapter, the following standards are required in the neighborhood conservation area identified in section 81-1-3. This includes two subareas: subarea D and subarea E. All of the standards contained in this section shall apply to all development in all subareas. Subarea requirements are found within the applicable subsection.

This section shall govern subarea C of the commercial/mixed-use area. It may also govern one-family detached dwellings and two-family dwellings in the commercial/mixed-use area, provided that the section is applied in its entirety.

(a) Site development standards

- ✓ Except where indicated, setbacks shall be established by zoning.
- On corner lots the principal building shall be located adjacent to the street intersection, subject to setback or build-to line requirements of zoning.
- ✓ Minimum building heights shall be established by zoning.
- Within subareas D and E maximum building heights shall be as established by zoning, except that:

Where this chapter provides a more-stringent standard as compared to the zoning code, the more-stringent standard shall prevail. The only exception to this shall be a use grandfathered under the zoning code.

Portions of buildings equal to or less than five feet from a side or rear lot line shall be limited in height to the greater of 16 feet.

Portions of buildings between five and ten feet of a side or rear lot line shall be limited in height to the greater of 25 feet.

- ✓ Portions of buildings ten feet or greater from a side or rear lot line shall be limited in height to 35 feet.
- Outside of subareas D and E maximum building heights shall be as established by zoning.
- All buildings shall provide first-story occupiable space, for the first ten feet of building depth along the enfronting facade.
- Sidewalks shall be located along all public and private streets. Sidewalks shall consist of two areas: a landscape area and a clear area.
 - Developments less than one acre shall provide a minimum one-foot landscape zone and a minimum four-foot clear zone.
 Development of one acre or more shall provide a minimum two-foot landscape zone and a minimum five-foot clear zone.
 The above notwithstanding, multifamily developments and all developments along Dogwood Drive shall provide a minimum five-foot landscape zone and a minimum six-foot clear zone.

STAFF COMMENT: The plans should include a new sidewalk on each enfronting street, with a minimum 1' landscape zone and 4' clear zone.

(b) Supplemental Area and Fence Standards

- Developments shall locate landscape supplemental areas adjacent to first-story residential uses and place a minimum of one tree every 50 feet in the supplemental area. See list of allowed trees in section 93-2-14.
- Chain link fencing is not permitted in areas visible from a public right-of-way.
- On all lots a fence, wall, curb or hedge between six and 48 inches in height is encouraged at the back of the required sidewalk, except at openings to access steps, drives or pedestrian walkways.
- Fences adjacent to the street shall be picket-wood, stone, composite materials or ornamental metal, with the finished side facing the street.
- Retaining walls adjacent to the required sidewalk shall not exceed 32 inches in height unless required by topography.
- All street-facing walls shall be faced with stone, brick, or smooth stucco.
- Small planting between retaining walls and the required sidewalk are encouraged and should have a minimum width of six inches.

STAFF COMMENT:

A minimum of one tree is required every 50' in the supplemental area. The application should be revised to ensure at least one tree is located every 50' along both Northside Drive and Old Jonesboro Road frontages.

(c) Utility Standards

- Mechanical features shall not be located in the supplemental area or front yard and shall be screened from view from any park or along any public right-of-way with planting, walls or fences of equal or greater height. Acceptable materials for screening shall include those materials found in subsection (f)1., provided they are compatible with the principal structure.
- When located on rooftops, mechanical features shall be incorporated in the design of the building and screened with materials similar to the building.
- Street lights may be provided by the developer in an effort to maintain a safe, walkable and well-lit public area throughout the city; pedestrian-
- x All developments shall provide a light at the front door. Lighting designed to illuminate the path to the front door is allowed. Spotlighting may
- Trees shall not be planted directly above storm drains.

STAFF COMMENT:

The Applicant should clarify how the mechanical features on the west side of the dwelling will be screened. A light at the front door should be included in plans.

(d) Parking and Traffic Standards

- One-family detached dwellings and two-family dwellings shall meet the following requirements:
 - ${f x}$ Driveways shall have a minimum width of nine feet and a maximum width of 15 feet.

Circular drives are permitted.

A grass strip in the middle of driveways is encouraged.

O All other buildings shall meet the following requirements:

Parcels are permitted a maximum of one driveway curb cut per street. In cases where a property abuts multiple streets the total number of curb cuts or portions thereof may be allocated to a single street.

Driveways shall have a maximum width of 12 feet for one-way and 24 feet for two-way.

Two curb cuts serving two one-way driveways shall be counted as one curb cut.

Public or private alleys, or driveway providing vehicular access to two or more parcels shall not constitute a curb cut.

New public streets shall not count as curb cuts.

Parcels are permitted a maximum of one driveway curb cut per street frontage. In cases where a property abuts multiple streets the total number of curb cuts or portions thereof may be allocated to a single street.

 $\ensuremath{\mathbb{Q}}$ Carports are only permitted subject to the following requirements:

Carports shall be located in the rear or side yard, but shall not be visible from a public right-of-way.

Carport roofs shall be supported by columns with a minimum width and depth of eight inches.

The base of carport columns shall be faced in stacked brick or stacked stone to a minimum height of three feet above grade.

- On-site parking shall be prohibited in the supplemental areas. This shall not be interpreted as restricting on-street parking located along a public street.
- O Garage access on single-family lots shall be prohibited in the front yard of the home.

STAFF COMMENT: The driveway is 15' wide at the curb but expands towards the garage, which is not compliant.

(e) Roof and Chimney Standards

Principal building roofs for one-family detached dwellings shall have a minimum usable life of thirty (30) years, per manufacturer's warranty.

- ✓ Roof shingles shall be slate, cedar, or asphalt.

Allowed on one-family and two-family detached dwellings;

Permitted on multifamily and townhouse dwellings only when screened form the adjacent street by a parapet wall.

- The state of the s
- nownspouts shall match gutters in material and finish.
- Roof forms shall be based on architectural style.
- ✓ All roofs, excluding dormers, shall overhang a minimum of 12 inches beyond the facade.
- O Dormers are permitted on all style homes (unless specified), but shall not be taller than the main roof to which they are attached.
- Chimneys exposed to the public view may not be faced in wood or cement based siding and may not be of an exposed metal or ceramic pipe.
 - All chimneys shall be wrapped in a brick, stone or suitable masonry finish material.
- O Chimneys on exterior building walls shall begin at grade.
- Chimneys shall begin at grade and be faced with brick or stacked stone; extend chimneys between three and six feet above the roof line.

STAFF COMMENT:

The Applicant should ensure the roof shingles have a warranty of at least 30 years and indicate the warranty on the plans. The Applicant should indicate the material of the gutters and downspouts and show downspouts on the plans.

(f) Street Facing Facade and Style Standards.

- ✓ Exterior facade materials shall be limited to:
 - √ Full-depth brick;

Natural or cast stone;

- √ Smooth natural-wood siding and/or cement-based siding;
- ✓ Shake siding:

Painted fish-scale style shingles, but only when used in front gables;

True, smooth hard-coat stucco, provided that its use is limited to gables of Tudor revival-style buildings.

- ✓ Exterior building materials shall not be:
 - Simulated brick veneer, such as Z-Brick;

Exterior insulation and finish systems (EIFS);

Exposed concrete block;

Metal siding or other metal exterior treatment;

Glass curtain walls;

Liquid vinyl;

T-1-11 siding;

Vinyl siding, except that existing one-family detached homes with vinyl siding covering more than 70 percent of the exterior facade may replace said siding or construct an addition faced in vinyl siding.

- ✓ Facade materials shall be combined horizontally, with the heavier below the lighter.
- \checkmark Blank, windowless walls are prohibited along all facades. See subsection 81-1-7(g)11.
- Foundations shall be constructed as a distinct building element that contrasts with facade materials. Foundations that are exposed above the ground, must be parged with cement, stuccoed over or be faced in brick, natural stone, or cast stone.
- ✓ All exterior stair risers visible from a street shall be enclosed.
- ✓ Porches, stoops, and balconies may be located in the front or side yard.
- Porches, stoops, and balconies along front and side building facades shall not be enclosed with screens, plastics, or other materials that hinder visibility and/or natural air flow.
- Porches, stoops, and balconies shall be made of painted or stained wood, stone, brick, or ornamental metal, subject to the additional restrictions below.
- Wooden porches, stoops, and balconies shall provide top and bottom horizontal members on railings. The top railing shall consist of two elements. The upper element shall measure two [inches] by six inches and the lower element shall measure two [inches] by four inches. The bottom railing shall measure two [inches] by four inches.
- ✓ Front porches and front stoops of principal buildings shall face and be parallel to the front lot line or build-to line.
- ✓ Porch and stoop foundations shall be enclosed.
- Front and side porches and stoops shall not have unpainted, unstained or otherwise untreated or exposed pressure treated lumber along the building line that abuts a public right-of-way.

- Balconies shall have not less than two clear unobstructed open or partially open sides. Partially open is to be constructed as 50 percent open or more. The total combined length of the open or partially open sides shall exceed 50 percent of the total balcony perimeter.
- Stoops and porch[es] shall be a minimum of two feet and a maximum of four feet from grade to the top of the stairs, unless existing topography is greater.
- Stoops shall provide a minimum top landing of four feet by four feet.
- Stoop stairs and landings shall be of similar width.
- Stoops may be covered or uncovered.
- When provided, porches shall have a minimum clear depth of eight feet from building facade to outside face of column.
- Front porch widths shall be between 80 percent and 100 percent of the adjacent facade.
- Side porch widths (including wraparound porches) shall be between 25 percent and 100 percent of the adjacent facade.
- Enfronting porches may have multistory verandas, living space, or balconies above.
- Porch columns shall be spaced a maximum distance of eight feet on center.
- ✓ Front porch columns shall have foundation piers extending to grade.
- ✓ All porches shall be covered.
- Enfronting balconies are only permitted on attached or detached one-family home facades when porches are not provided on said facades.
- O Enfronting balconies shall have a minimum clear depth of four feet.
- © Enfronting balcony widths shall be between 25 percent and 100 percent of the adjacent facade.
- Salconies may be covered or uncovered.

The Applicant should provide the material used for the porch columns. Porches must be made of painted or stained wood, stone, brick, or ornamental metal.

House is built on a slab foundation. A design exception is required for a porch built at grade.

STAFF COMMENT:

The minimum clear depth between the front façade and the outside of the porch columns is 8'. The clear depth is 6' at its narrowest, which is not compliant.

Front porch widths must be between 80% and 100% of the adjacent façade. The porch is 70% of the façade, which is not compliant.

The Applicant should provide the spacing between porch columns, ensuring they are spaced no more than 8' on center.

(g) Door and window standards.

- ✓ The main entry door to enfronting principal buildings shall face, be visible from, and be accessible from the adjacent public sidewalk.
- The main entry door to all uses shall be linked to the sidewalk via a pedestrian walkway or wheelchair access.
- Building numbers at least six inches in height shall be located above or beside the street-facing pedestrian entrance, or above or beside the stairs accessing a front porch.
- Window panes shall be recessed a minimum of three inches and a maximum of eight inches from the adjacent facade, except on frame houses, on which panes shall be recessed a minimum of two inches.
- Where windows lights are utilized they shall be true divided lights, simulated divided lights, or one-over-one lights. Grids-between-glass (GBGs) are prohibited.
- $\checkmark \qquad \qquad \text{Window trim shall not be flush with the exterior facade and shall provide a minimum relief of one-quarter inch or greater.}$
- where used, window shutters shall match one-half the width of the window opening.
- Painted window or door glass is prohibited.
- Enfronting windows and door glass (except on churches and fire stations) shall utilize clear glass or tinted glass. Tinted glass shall have a transmittance factor of 50 percent or greater and shall have a visible light reflectance factor of ten or less.
- Windows shall be provided for a minimum of thirty (30) percent and a maximum of 50 percent of the total street-facing facade of the principal building, with each facade and story calculated independently.
- Street-facing window units shall not exceed 28 square feet with minimum height of three feet, with the exception of transoms and fan lights.
- Wood trim between four and six inches wide shall surround windows of wood frame structures. Windows grouped together shall have center mullions two inches wider than the side trim.
- x Sills shall be of masonry, wood, stone, cast stone, or terra cotta.

The front door should be linked to the sidewalk/street via a pedestrian walkway.

Building numbers are required and should be shown on plans.

The Applicant should indicate the distance windowpanes are recessed from the adjacent façade, ensuring they are recessed at

least 2".

The Applicant should ensure divided lights, if used, are not GBGs.

STAFF COMMENT:

Window shutters must match one-half the width of the window opening.

Windows must enfront for between 30% and 50% of the Old Jonesboro Road facing façade.

The Applicant should ensure the window trim is made of wood.

Windows grouped together must have center mullions two inches wider than the side trim.

Windowsills are required and must be made of masonry, wood, stone, cast stone, or terra cotta.

(h) Detached one-family dwellings/ two-family dwellings. In addition to the requirements of subsections (a) through (g), the following shall apply to detached one-family dwellings and two-family dwellings.

- First Stories . First stories shall be elevated above the grade between two and four feet, unless existing topography is greater or unless wheelchair access is desired and cannot be provided from the side or rear.
- Window Sills. Enfronting first story window sills should be no less than two and one-half feet and no more than three and one-half feet above finished floor elevation.
- Wheelchair access. Where practical, wheelchair access, when provided, should be installed at the side or rear of the home in order to preserve the architectural character of the primary facade.
- Architectural style. Architecture is one of the most critical components of place, and nowhere is this more evident than on building facades.

 The design and character of street-facing facades is a reflection of both buildings and their users, and must be carefully considered for its

Ranch homes. Ranch homes shall include:

impact on the overall sense of place.

- x i.No more than one story as measured closest to the primary building line and excluding basements.
- √ ii. A building footprint that is rectangular or "L-shaped," with the end of the short leg of the "L" facing a street.
- iii. Hipped or gabled roofs having gables with a minimum pitch of 15 and a maximum pitch of 35 degrees from horizontal, with roof lines running parallel to the street.
- ✓ iv. Enclosed roof rafters where roofs overhang. No dormers.
- v. Varied, but primarily equal, height windows along a single floor.
- √ vi. A symmetrical or asymmetrical front facade.
- vii. No front porch.

House uses a slab foundation. A design exception is required to allow the first story to be at grade.

The Applicant should ensure windowsills are between 2.5' and 3.5' above finished floor elevation.

STAFF COMMENT:

0

The design of the house is closest to a ranch, but with craftsman-like elements such as the porch, higher gable pitch and perpendicular roof lines. As such, it does not conform to the established historical architectural standards.

Outbuildings. In conventional development, outbuildings are often designed and located as an afterthought. Yet in traditional towns and cities, outbuildings serve to enrich the quality of design through their placement, design and use. In Hapeville, where outbuildings are provided on many residential lots, their design must be to the same high standards found in the community's neighborhoods.

The following standards shall apply to construction of new outbuildings in residential districts.

- i. On lots with one street frontage, set outbuildings back at least 15 feet behind the front facade of the principal building.
- ii. On corner lots, outbuildings should be setback at least 15 feet behind the front facade of the principal building and with a setback greater than or equal to that of the facade along the side lot line.
- iii. Outbuilding may be linked to the principal building with covered walks, trellises or enclosed breezeway.
- iv. Outbuildings shall be of compatible material and architectural style to the principal building.
- v. Outbuildings shall have a minimum height of 14 feet and a maximum height of that of the principal building or 25 feet, whichever is less.
- vi. Outbuildings shall be set a minimum of ten feet from any other outbuilding on adjoining lots.

STAFF COMMENT:

RECOMMENDATIONS

Sec. 81-1-5. Applicability

Upon review of the information provided by the Applicant, the following items have been found to be missing or deficient and should be addressed prior to formalizing a recommendation:

The plans should include a new sidewalk on each enfronting street, with a minimum 1' landscape zone and 4' clear zone.

A minimum of one tree is required every 50' in the supplemental area. The application should be revised to ensure at least one tree is located every 50' along both Northside Drive and Old Jonesboro Road frontages.

The Applicant should clarify how the mechanical features on the west side of the dwelling will be screened.

A light at the front door should be included in plans.

The driveway is 15' wide at the curb but expands towards the garage, which is not compliant.

The Applicant should ensure the roof shingles have a warranty of at least 30 years and indicate the warranty on the plans.

The Applicant should indicate the material of the gutters and downspouts and show downspouts on the plans.

The Applicant should provide the material used for the porch columns. Porches must be made of painted or stained wood, stone, brick, or ornamental metal.

House is built on a slab foundation. A design exception is required for a porch built at grade.

The minimum clear depth between the front façade and the outside of the porch columns is 8'. The clear depth is 6' at its narrowest, which is not compliant.

Front porch widths must be between 80% and 100% of the adjacent façade. The porch is 70% of the façade, which is not compliant.

The Applicant should provide the spacing between porch columns, ensuring they are spaced no more than 8' on center.

The front door should be linked to the sidewalk/street via a pedestrian walkway.

Building numbers are required and should be shown on plans.

The Applicant should indicate the distance windowpanes are recessed from the adjacent façade, ensuring they are recessed at least 2".

The Applicant should ensure divided lights, if used, are not GBGs.

Window shutters must match one-half the width of the window opening.

Windows must enfront for between 30% and 50% of the Old Jonesboro Road facing façade.

The Applicant should ensure the window trim is made of wood.

Windows grouped together must have center mullions two inches wider than the side trim.

Windowsills are required and must be made of masonry, wood, stone, cast stone, or terra cotta.

House uses a slab foundation. A design exception is required to allow the first story to be at grade.

The Applicant should ensure windowsills are between 2.5' and 3.5' above finished floor elevation.

The design of the house is closest to a ranch, but with craftsman-like elements such as the porch, higher gable pitch and perpendicular roof lines. As such, it does not conform to the established historical architectural standards.

Once these items are addressed to the satisfaction of Staff and/or the Design Review Committee, the application can be approved.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE:	
NOTE:	All applications must be typed or neatly authorized representative is required to personal Meeting to answer questions.	
	The Design Review Committee meets the thin Every attempt will be made to place your app month's agenda following the submittal of supporting documents; however, that may not reserves the right to schedule applications as deep	lication for review on the next a completed application with always be possible. The City
Applicant:	AUJA SMÍTH Contact Nun	nber:
Applicants Ad	dress: PO Box 5 Ellenwood Q	A 30294
E-Mail Address	s: Zoning Cla	ssification: R-O
Address of Pro	oposed Work: O Northside Dr. Hap	eville GA 30354
Parcel ID# (INF	FORMATION MUST BE PROVIDED): 14-009	5-0010-022-9
Property Owne	er: PAULA SMITH Contact Nu	mber:
Project Desci	ription (including occupancy type): <u>constru</u>	ct craftsman-style
	Man with Attached 2 carryphs. with Bonus expansion is	Available.
Contractors N	Name: Creative Homes cont	act Number:
Contact Pers	on: Paul & Smith Cont	act Number:
property. I do I accurate, and I application and reserves that rig I further unders full. I hereby acwrite the Englis voluntarily com	application to the City of Hapeville, to the Design Review hereby swear or affirm that the information provided he understand that any inaccuracies may be considered a lany action taken on this application. I understand the pht to enforce any and all ordinances regardless of any action that it is my/our responsibility to conform with all exhowledge that all requirements of the City of Hapeville is hanguage and/or this document has been read and expleted this application. I understand that it is a felony to exille, Georgia pursuant to O.C.G.A. 16-10-20 and I may be	re and above is true, complete and just cause for invalidation of this hat the City of Hapeville, Georgia, ction or approval on this application. of City of Hapeville's Ordinances in shall be adhered to. I can read and explained to me and I have full and make false statements or writings to
ans	la fruth	5-13-19
Applicants S	Signature	Date

Project Class (check one):	
ResidentialCommercial	Mixed-Use Development
Project Type:	
New Commercial Construction	Addition to Existing Commercial Building
Addition to Existing Residential Structure	Accessory Structure
Site Plan, Grading & LandscapingNew Sin	gle Family Residential Construction
Other	
Total Square Footage of proposed New Construction: 24	198 sq Pt.
Total Square Footage of existing building:	
Estimated Cost of Construction: #250K	
List/Describe Building Materials on the exterior of the existing	ng structure: NA
List/Describe Building Materials <u>proposed</u> for the exterior far AR shingles with a brick water to mixed with cement siding in both along with smooth lap pattern a fiction of the bonus room is	Able below windows, ands a batter style

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does MOT make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)

swear or affirm that before receipt of an application, I have received this notice and I read and write the English language or I have had someone read and explain this document to me.



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

	e undersigned, agree that with my signature and submission to the City of Hapeville, I howing:	ave done the
	Read the City of Hapeville's Architectural Design Guidelines and relevant Code sections proposed project. The Architectural Design Guidelines may be found here: s://library.municode.com/ga/hapeville/codes/code of ordinances?nodeId=PTIICOOR ()	
	Ensured that my proposed project meets all of the required criteria per the City of Hap of Ordinances.	eville Code
<u> </u>	_Submitted my application materials in full by the published deadline for review by Staf Design Review Committee meeting.	f prior to the
	Identified and explained all deficiencies or components of the proposed project that do with the requirements set forth in the Code. This explanation should be submitted as document in the application.	
√	Understood that any deficiencies in the application must be resolved at least 10 days processing Design Review Committee meeting or the application may not be presented to the DR	
	_ Submitted architectural drawings and details for all projects unless allowed in writing becommunity Services or Planning & Zoning Department.	by the
_	Agreed to submit any required revisions by the Design Review Committee with update to the Community Services Department for review prior to requesting any permits.	d drawings
T	PANIA Smith Paula Smith 5-1	13-19
Printe	ted Name Signature	Date

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.


Exhibit "A" Legal description 0 Northside Drive, Hapeville, Georgia


ALL THAT TRACT OR PARCEL OF LAND LYING AND BEING IN LAND LOT 95 OF THE 14th DISTRICT OF FULTON COUNTY, GEORGIA, AND BEING LOT 16, BLOCK A OF UNIT A SUBDIVISION OF THE PROPERTY OF JOANN SIMPSON HOLMES, FORMERLY PROPERTY OF S. R. YOUNG AND GEORGE LONGINO ACCORDING TO PLAT RECORDED IN PLAT BOOK 32, PAGE 25, FULTON COUNTY RECORDS AND MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT AT THE INTERSECTION OF THE WEST SIDE OF NORTHSIDE DRIVE (FORMERLY BORING STREET) AND THE NORTHEAST SIDE OF OLD JONESBORO ROAD (IF THE LINES WERE EXTENDED RATHER THAN FORMING A CURVE) THENCE RUNNING 175.9 FEET NORTHWESTERLY ALONG THE NORTHEAST SIDE OF OLD JONESBORO ROAD TO LOT 17; THENCE NORTHEASTERLY 105 FEET TO A POINT; THENCE EASTERLY 120 FEET ALONG THE SOUTH SIDE OF LOT 15 TO THE WEST SIDE OF NORTHSIDE DRIVE, THENCE SOUTHERLY 132.3 FEET ALONG THE WEST SIDE OF NORTHSIDE DRIVE TO THE POINT OF BEGINNING. SAID LOT IS UNIMPROVED.

PARCEL 14-0095-0010-022-9

Subject to easements, covenants, restrictions, agreements, right of way deeds, agreements, matters of plat, governmental ordinances and other lawful matters affecting said property





GC TO PRESERVE AND PROTECT ANY USEABLE EX. UTILITIES

corcure	DATE (A CDE	n went name	PERT	RTILIZER	
SPECIES	RATE/ACRE	PLANTING DATES	ANALYSIS	RATE/ACRI	
PESPEDEZA UNSCARIFIED	75 LBS.	1/1 - 12/1	6-12-12	1500 LB5.	
LOVEGRA55	4 LB5.	3/1 - 6/1	6-12-12	1500 LB5.	
TALL FESCUE GRASS	50 LB5.	8/1 - 10/1	6-12-12	1500 LB5.	
COMMON BERMUDA GRASS (UNHULLED)	40 LB5.	11/1 - 4/1	6-12-12	1500 LBS.	
COMMON BERMUDA GRASS (HULLED)	20 LB5.	5/1 - 7/1	6-12-12	1500 LBS.	
PERENIAL RYE GRASS (FOR TEMPORARY USE ONLY)	100 LB5.	10/1 - 1/15 3/1 - 5/30	10-10-10	1500 LBS.	
RYE GRASS (FOR TEMPORARY USE ONLY)	168 LB5.	8/1 - 12/1	10-10-10	1500 LBS.	
SUDANGRASS (FOR TEMPORARY USE ONLY)	60 LBS.	4/1 - 8/1	10-10-10	1500 LB5.	


APPROX. STARTING DATE: 8-21-19 APPROX. COMPLETION DATE: 1-21-20

ITFM	DESCRIPTION	MONTHS OF ACTIVITY				/ITY	
I I L IVI	DESCRIPTION	1	2	3	4	5	
1	SILT BARRIER INSTALLATION						
2	CLEARING AND GRUBBING						
3	RETAINING WALL						
4	GRADING						
5							
6	UTILITIES						
7	TEMPORARY GRASSING						
8	BUILDING						
9	CURB AND GUTTERS						
10	SIDEWALKS						
11	BASE AND PAVING						
12	FINAL GRASSING & REMOVAL OF TEMPORARY STRUCTURES						
13	MAINTENANCE OF EROSION CONTROL STRUCTURES						

SITE PLAN INFORMATION PROVIDED FOR PERMITTING

"NO WATERS OF THE STATE WITHIN 200 FEET OF PROJECT SITE."

"NO INERT OR BURY PITS ON SITE" TREES TO BE DESTROYED OR REMOVED.



TREE PROTECTION FENCE

"THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND-DISTRUBING ACTIVITIES".


"EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE".

"EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AT LEAST WEEKLY, AFTER EACH RAIN, AND REPAIRED AS NECESSARY."

"DISTURBED AREAS LEFT IDLE SHALL BE STABILIZED WITH TEMPORARY VEGETATION AFTER 14 DAYS: AFTER 30 DAYS, PERMANENT VEGETATION SHALL BE ESTABLISHED".

"SILT FENCE SHALL BE TYPE C AS PER THE MANUAL FOR SEDIMENT & EROSION CONTROL IN GEORGIA, AND BE WIRE REINFORCED".

"ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IF DETERMINED NECESSARY BY ON-SITE INSPECTION."








GC TO VERIFY ALL ELEVATIONS IN FIELD.


"NO WATERS OF THE STATE WITHIN TONY DAWSON 200 FEET OF PROJECT SITE."


LEVEL II CERTIFIED DESIGN PROFESSIONAL CERTIFICATION NUMBER 0000039605 "NO INERT OR BURY PITS ON SITE" ISSUED: 3/9/2007 EXPIRES: 3/9/2022




NOTE: SILT FENCE TO MEET REQUIREMENTS OF SECTION 171, GEORGIA D.O.T. SPECS., LATEST EDITION









N.S.A. R-2 (1.5-3.5") _ COARSE AGGREGATE

NOT TO SCALE

24HR CONTACT/DEVELOPER

OWNER

PAULA SMITH

404-427-8558

ELLENWOOD, GA 30294

P05T B0X 5

GEOTEXTILE UNDERLINER —

0.22 ACRES DISTURBED

0.41 ACRES, 17,859 SF

TOTAL HOUSE SF = 2,498 SF

FAR= 2498/17859 = 0.14 < 0.5

PROP. HOUSE SF = 2,498 SF

PROP. GARAGE SF = 500 SF

PROP. PORCH SF = 212 SF

PROP. DRIVE SF = 780 SF


TOTAL IMPERV. SF. = 3,990 SF

22% LOT COVERAGE = 3990/17859 SF


MAX. 70% LOT COVERAGE = 12,501 SF


SITE INFO

ZONED R















SITE PLAN



GC TO PRESERVE AND PROTECT ANY USEABLE EX. UTILITIES

SPECIES RATE/ACRE PLANTING DATES		FERTI	LIZER	
SPECIES	RATE/ACRE	PLANTING DATES	ANALYSIS	RATE/ACRE
PESPEDEZA UNSCARIFIED	75 LBS.	1/1 - 12/1	6-12-12	1500 LB5.
LOVEGRASS	4 LB5.	3/1 - 6/1	6-12-12	1500 LB5.
TALL FESCUE GRASS	50 LB5.	8/1 - 10/1	6-12-12	1500 LB5.
COMMON BERMUDA GRASS (UNHULLED)	40 LB5.	11/1 - 4/1	6-12-12	1500 LB5.
COMMON BERMUDA GRASS (HULLED)	20 LB5.	5/1 - 7/1	6-12-12	1500 LB5.
PERENIAL RYE GRASS (FOR TEMPORARY USE ONLY)	100 LB5.	10/1 - 1/15 3/1 - 5/30	10-10-10	1500 LB5.
RYE GRASS (FOR TEMPORARY USE ONLY)	168 LB5.	8/1 - 12/1	10-10-10	1500 LB5.
SUDANGRASS (FOR TEMPORARY USE ONLY)	60 LB5.	4/1 - 8/1	10-10-10	1500 LB5.


APPROX. STARTING DATE: 8-21-19 APPROX. COMPLETION DATE: 1-21-20

ITEM	DESCRIPTION	MONTHS OF ACTIVITY					
I I L IVI	DESCRIPTION	1	2	3	4	5	
1	SILT BARRIER INSTALLATION						
2	CLEARING AND GRUBBING						
3	RETAINING WALL						
4	GRADING						
5							
6	UTILITIES						
7	TEMPORARY GRASSING						
8	BUILDING						
9	CURB AND GUTTERS						
10	SIDEWALKS						
11	BASE AND PAVING						
12	FINAL GRASSING & REMOVAL OF TEMPORARY STRUCTURES						
13	MAINTENANCE OF EROSION CONTROL STRUCTURES						

SITE PLAN INFORMATION PROVIDED FOR PERMITTING

"NO WATERS OF THE STATE WITHIN 200 FEET OF PROJECT SITE."

"NO INERT OR BURY PITS ON SITE"



TREE PROTECTION FENCE

"THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND-DISTRUBING ACTIVITIES".

"EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE".


"EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AT LEAST WEEKLY, AFTER EACH RAIN, AND REPAIRED AS NECESSARY."


"DISTURBED AREAS LEFT IDLE SHALL BE STABILIZED WITH TEMPORARY VEGETATION AFTER 14 DAYS: AFTER 30 DAYS, PERMANENT VEGETATION SHALL BE ESTABLISHED".


"SILT FENCE SHALL BE TYPE C AS PER THE MANUAL FOR SEDIMENT & EROSION CONTROL IN GEORGIA, AND BE WIRE REINFORCED".

"ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IF DETERMINED NECESSARY BY ON-SITE INSPECTION."

LOT# 15 PB.32, PG.25 LOT# 17 PB.32, PG.25 BRICK OVER P/L LOT 16, BLOCK A 18"PINE 26'HT FFE 930.5 Ds2/Ds3 OLD JONESBORO RD.
50FT. R/W







NOT TO SCALE

0.22 ACRES DISTURBED

SITE INFO 0.41 ACRES, 17,859 SF ZONED R

MAX. 70% LOT COVERAGE = 12,501 SF

TOTAL HOUSE SF = 2,498 SF FAR= 2498/17859 = 0.14 < 0.5

PROP. HOUSE SF = 2,498 SF PROP. GARAGE SF = 500 SF PROP. PORCH SF = 212 SF PROP. DRIVE SF = 780 SF

TOTAL IMPERV. SF. = 3,990 SF 22% LOT COVERAGE = 3990/17859 SF

24HR CONTACT/DEVELOPER OWNER PAULA SMITH POST BOX 5 ELLENWOOD, GA 30294 404-427-8558

GC TO VERIFY ALL ELEVATIONS


"NO WATERS OF THE STATE WITHIN TONY DAWSON 200 FEET OF PROJECT SITE."

IN FIELD.

LEVEL II CERTIFIED DESIGN PROFESSIONAL CERTIFICATION NUMBER 0000039605 "NO INERT OR BURY PITS ON SITE" | ISSUED: 3/9/2007 | EXPIRES: 3/9/2022

20 10 0 SCALE IN FEET

 $\boldsymbol{\omega}$



- UNDERGROUND UTILITIES IS SHOWN HEREON. THE INFORMATION IS BASED ON THE LOCATION OF ABOVE GROUND APPURTENANCES, AVAILABLE SITE PLANS, AND PAINT PLACED BY UNDERGROUND SERVICES "NO CERTIFICATION IS MADE AS TO THE ACCURACY"
- 5. ALL BEARINGS AND DISTANCES WERE MEASURED AND USED
- This survey was prepared without benefit of a title report which
 may reveal additional conveyances, easements or rights—of—way
 not shown hereon.

No. 2642
No. 2642
No. 2642
No. 2642
No. MARREL

A'NGEL M. MARRERO P.L.S. #2642 Certified Design Professional # 4479 RETRACEMENT SURVEY FOR:

PAULA SMITH "CREATIVE HOMES"

Land Lot 95 14TH Dist. CITY OF HAPEVILLE FULTON County, GA

Drawn By: AMM SR. Scale: 1"=40'

Fax: (770) 320-8098

LSF000831

PROVIDE SUPPORT FOR PORCH AND STEPS TO GRADE AS REQ'D.

NOTE: WHEN TWO ROOFS INTERSECT WITH DIFFERENT ROOF PITCHES, BLOCK TOP OF STUD WALLS AS REQ'D. TO LINE UP FASCIAS AT A MINIMUM OF 1'-O" OVERHANG

NOTE: ELEVATIONS REFLECT A SLAB FOUNDATION, IF ANOTHER FOUNDATION IS USED, BUILDER SHOULD DISREGARD FOUNDATION SHOWN

NOTE: RAFTERS ARE PITCHED FROM TOP OF CEILING JOISTS

NOTE: ATTIC VENTILATION PER LOCAL CODES AND REQUIREMENTS

GENERAL FRAMING NOTES

THE FOLLOWING NOTES ARE SUGGESTED MINIMUM REQUIREMENTS ONLY. DUE TO A VARIANCE OF CODES PER REGION, PLEASE REFER AND COMPLY WITH ALL YOUR LOCAL CODES. CONSULT WITH LOCAL ENGINEERS FOR ALL STRUCTURAL REQUIREMENTS.

- PROVIDE PURLINS AT MID HEIGHT OF ALL WALLS.
 ALL JOISTS AND RAFTERS SHALL BE ALIGNED OVER STUDS BELOW.
- 2. ALL JOISTS AND RAFTERS SHALL BE ALIGNED OVER STUDS BELOW.

 3. ALL HEADERS SHALL BE 2-2x/0's WITH 1/2" PLYWOOD FLITCH PLATE UNLESS OTHERWISE NOTED.

 4. FRAMER TO INSTALL DOUBLE FLOOR JOISTS UNDER PARTITION WALL PARALLEL TO JOIST DIRECTION.

 5. PROVIDE 1x4 CROSS BRIDGING AT MID POINT OF SPAN OR 8'-0"
- PROVIDE IX4 CROSS BRIDGING AT MID POINT OF SPAN OR 8'-O"
 O.C. MAXIMUM IN ALL FLOORS.
 ALL EXTERIOR CORNERS (INSIDE AND OUTSIDE CORNERS) SHALL BE
 BRACED WITH I/2" CDX PLYWOOD. NAILING SCHEDULE SHALL BE 8d
 COMMONS AT 6" O.C. AT ALL EDGES AND 8d COMMONS AT 12" O.C.
 AT ALL INTERMEDIATE STUDS. (OPTION APPROVED DIAGONAL
 CORNER BRACES BOTH DIRECTIONS AT ALL CORNERS).
 ALL COLUMNS OR SOLID FRAMING SHALL EXTEND DOWN THRU ALL
 LEVELS AND TERMINATE AT THE BASEMENT FLOOR AND BE SUPPORTED
 BY A THICKENED SLAB, GRADE BEAM, OR FOOTING DESIGNED TO CARRY
 LOAD
- 8. PROVIDE DOUBLE 2x8 STRONGBACK AT MID SPAN FOR CEILING JOISTS WITH SPAN GREATER THAN 10'-0'
- 9. PROVIDE COLLAR TIES AT UPPER 1/3 OF VERTICAL DISTANCE BETWEEN RIDGE BOARD AND CEILING JOISTS AT 4'-0" O.C. MAXIMUM.
 10. HIP, VALLEY RAFTERS, AND RIDGE BOARDS SHALL BE ONE "2x" SIZE
- IO. HIP, VALLEY RAFTERS, AND RIDGE BOARDS SHALL BE ONE "2x" SIZE LARGER THAN RAFTERS.

 II. ROOF DECKING SHALL BE 1/2" CDX PLYWOOD MINIMUM.

 12. WHERE PRE ENGINEERED FLOOR AND ROOF TRUSSES ARE USED, TRUSS MANUFACTURER MUST PROVIDE SHOP DRAWINGS WHICH BEAR SEAL OF REGISTERED ENGINEER IN STATE IN WHICH WORK IS TO BE PERFORMED.

 13. ALL CEILING JOISTS AND RAFTER BRACING TO BEAR ON LOAD BEARING WALLS DESIGNED TO CARRY LOAD THRU ALL LEVELS AND TERMINATE AT BASEMENT FLOOR AND BE SUPPORTED BY THICKENED SLAB GRADE BEAM OR FOOTING DESIGNED TO CARRY LOAD
- OR FOOTING DESIGNED TO CARRY LOAD.
- 14. ALL BASEMENT WALLS, BEAMS, AND COLUMNS TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.
 15. ALL SOLID FRAMING, COLUMNS, BEAMS, ETC., TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.
- 16. ALL FRAMED WALL DIMENSIONS ARE BASED ON 2 x 4 STUDS UNLESS OTHERWISE NOTED.

GENERAL NOTES

- I. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, REGULATIONS, AND FHA/VA MPS.

 2. CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT SITE BEFORE BEGINING CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO SPENCER RESIDENTIAL, INC. FOR JUSTIFICATION AND/OR CORRECTION BEFORE PROCEEDING WITH WORK. CONTRACTORS SHALL ASSUME RESPONSIBILITY FOR ERRORS THAT ARE NOT REPORTED.

 3. ALL DIMENSIONS SHOULD BE READ OR CALCULATED AND NEVER SCALED.


 4. ALL FOOTINGS TO BE BELOW FROST LINE (SEE LOCAL CODE) AND MUST REST ON UNDISTURBED SOIL CAPABLE OF HANDLING THE BUILDING. CONSULT LOCAL ENGINEER FOR PROPER FOOTING AND REINFORCING SIZES.

 5. CONTRACTOR SHALL INSURE COMPATIBILITY OF THE BUILDING WITH ALL SITE REQUIREMENTS.

 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE

- 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE
- 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE AS PER CODE.
 7. ALL FOUNDATION AND STRUCTURAL MEMBERS SHOULD BE VERIFIED AND STAMPED BY AN ENGINEER IN THE STATE WHERE CONSTRUCTION IS OCCURING DUE TO A WIDE VARIANCE IN LOCAL CODES, SOIL BEARING CONDITIONS, FROST LINE DEPTH, GEOLOGICAL AND WEATHER CONDITIONS, ETC. THE CONTRACTOR IS RESPONSIBLE FOR ADJUSTING AND VERIFYING ALL STRUCTURAL DETAILS AND CONDITIONS TO MEET ALL LOCAL CODES AND TO INSURE A QUALITY AND SAFE STRUCTURE.
 8. ALL WOOD, CONCRETE, AND STEEL STRUCTURAL MEMBERS SHALL BE OF A GOOD GRADE AND QUALITY AND MEET ALL NATIONAL, STATE, AND LOCAL BUILDING CODES WHERE APPLICABLE.
 9. ALL COLUMNS OR SOLID FRAMING SHOULD BE DESIGNED TO CARRY LOADS AND SHOULD EXTEND DOWN THRU THE LEVELS BELOW AND TERMINATE AT THE BASEMENT FLOOR OR AT OTHER BEARING POINTS DESIGNED TO CARRY THE LOAD.





~ ОШ

 $\sum \square$ OШ Ω \vdash **ഡ** 0√ Ⅲ O \mathbb{T} \exists Z

CHECKED JOB NUMBER 19-034 SCALE 4.25.2019

SHEET

PROVIDE SUPPORT FOR PORCH AND STEPS TO GRADE AS REQ'D.

NOTE: WHEN TWO ROOFS INTERSECT WITH DIFFERENT ROOF PITCHES, BLOCK TOP OF STUD WALLS AS REQ'D. TO LINE UP FASCIAS AT A MINIMUM OF 1'-O" OVERHANG

NOTE: ELEVATIONS REFLECT A SLAB FOUNDATION, IF ANOTHER FOUNDATION IS USED, BUILDER SHOULD DISREGARD FOUNDATION SHOWN

NOTE: RAFTERS ARE PITCHED FROM TOP OF CEILING JOISTS

NOTE: ATTIC VENTILATION PER LOCAL CODES AND REQUIREMENTS

GENERAL FRAMING NOTES

THE FOLLOWING NOTES ARE SUGGESTED MINIMUM REQUIREMENTS ONLY. DUE TO A VARIANCE OF CODES PER REGION, PLEASE REFER AND COMPLY WITH ALL YOUR LOCAL CODES. CONSULT WITH LOCAL ENGINEERS FOR ALL STRUCTURAL REQUIREMENTS.

- PROVIDE PURLINS AT MID HEIGHT OF ALL WALLS.
 ALL JOISTS AND RAFTERS SHALL BE ALIGNED OVER STUDS BELOW.
- 2. ALL JOISTS AND RAFTERS SHALL BE ALIGNED OVER STUDS BELOW.

 3. ALL HEADERS SHALL BE 2-2x/0's WITH 1/2" PLYWOOD FLITCH PLATE UNLESS OTHERWISE NOTED.

 4. FRAMER TO INSTALL DOUBLE FLOOR JOISTS UNDER PARTITION WALL PARALLEL TO JOIST DIRECTION.

 5. PROVIDE 1x4 CROSS BRIDGING AT MID POINT OF SPAN OR 8'-0"
- O.C. MAXIMUM IN ALL FLOORS.

 6. ALL EXTERIOR CORNERS (INSIDE AND OUTSIDE CORNERS) SHALL BE BRACED WITH 1/2" CDX PLYWOOD. NAILING SCHEDULE SHALL BE 8d COMMONS AT 6" O.C. AT ALL EDGES AND 8d COMMONS AT 12" O.C. AT ALL INTERMEDIATE STUDE (OPTION APPROVED DIAGONAL CORNER BRACES BOTH DIRECTIONS AT ALL CORNERS) CORNER BRACES BOTH DIRECTIONS AT ALL CORNERS).

 1. ALL COLUMNS OR SOLID FRAMING SHALL EXTEND DOWN THRU ALL LEVELS AND TERMINATE AT THE BASEMENT FLOOR AND BE SUPPORTED BY A THICKENED SLAB, GRADE BEAM, OR FOOTING DESIGNED TO CARRY
- 8. PROVIDE DOUBLE 2x8 STRONGBACK AT MID SPAN FOR CEILING JOISTS
- WITH SPAN GREATER THAN 10'-0' 9. PROVIDE COLLAR TIES AT UPPER 1/3 OF VERTICAL DISTANCE BETWEEN RIDGE BOARD AND CEILING JOISTS AT 4'-O" O.C. MAXIMUM.

 10. HIP, VALLEY RAFTERS, AND RIDGE BOARDS SHALL BE ONE "2x" SIZE

- IO. HIP, VALLEY RAFTERS, AND RIDGE BOARDS SHALL BE ONE "2x" SIZE LARGER THAN RAFTERS.

 II. ROOF DECKING SHALL BE 1/2" CDX PLYWOOD MINIMUM.

 12. WHERE PRE ENGINEERED FLOOR AND ROOF TRUSSES ARE USED, TRUSS MANUFACTURER MUST PROVIDE SHOP DRAWINGS WHICH BEAR SEAL OF REGISTERED ENGINEER IN STATE IN WHICH WORK IS TO BE PERFORMED.

 13. ALL CEILING JOISTS AND RAFTER BRACING TO BEAR ON LOAD BEARING WALLS DESIGNED TO CARRY LOAD THRU ALL LEVELS AND TERMINATE AT BASEMENT FLOOR AND BE SUPPORTED BY THICKENED SLAB GRADE BEAM OR FOOTING DESIGNED TO CARRY LOAD
- OR FOOTING DESIGNED TO CARRY LOAD.

 14. ALL BASEMENT WALLS, BEAMS, AND COLUMNS TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.

 15. ALL SOLID FRAMING, COLUMNS, BEAMS, ETC., TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.
- 16. ALL FRAMED WALL DIMENSIONS ARE BASED ON 2 x 4 STUDS UNLESS OTHERWISE NOTED.

GENERAL NOTES

- 1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES, REGULATIONS, AND FHA/VA MPS.

 2. CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT SITE BEFORE BEGINING CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO SPENCER RESIDENTIAL, INC. FOR JUSTIFICATION AND/OR CORRECTION BEFORE PROCEEDING WITH WORK. CONTRACTORS SHALL ASSUME RESPONSIBILITY FOR ERRORS THAT ARE NOT REPORTED.


 3. ALL DIMENSIONS SHOULD BE READ OR CALCULATED AND NEVER SCALED.


 4. ALL FOOTINGS TO BE BELOW FROST LINE (SEE LOCAL CODE) AND MUST REST ON UNDISTURBED SOIL CAPABLE OF HANDLING THE BUILDING. CONSULT LOCAL ENGINEER FOR PROPER FOOTING AND REINFORCING SIZES.

 5. CONTRACTOR SHALL INSURE COMPATIBILITY OF THE BUILDING WITH ALL SITE REQUIREMENTS.

 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE AS PER CODE.

- 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE AS PER CODE.
 7. ALL FOUNDATION AND STRUCTURAL MEMBERS SHOULD BE VERIFIED AND STAMPED BY AN ENGINEER IN THE STATE WHERE CONSTRUCTION IS OCCURING DUE TO A WIDE VARIANCE IN LOCAL CODES, SOIL BEARING CONDITIONS, FROST LINE DEPTH, GEOLOGICAL AND WEATHER CONDITIONS, ETC. THE CONTRACTOR IS RESPONSIBLE FOR ADJUSTING AND VERIFYING ALL STRUCTURAL DETAILS AND CONDITIONS TO MEET ALL LOCAL CODES AND TO INSURE A QUALITY AND SAFE STRUCTURE.
 8. ALL WOOD, CONCRETE, AND STEEL STRUCTURAL MEMBERS SHALL BE OF A GOOD GRADE AND QUALITY AND MEET ALL NATIONAL, STATE, AND LOCAL BUILDING CODES WHERE APPLICABLE.
 9. ALL COLUMNS OR SOLID FRAMING SHOULD BE DESIGNED TO CARRY LOADS AND SHOULD EXTEND DOWN THRU THE LEVELS BELOW AND TERMINATE AT THE BASEMENT FLOOR OR AT OTHER BEARING POINTS DESIGNED TO CARRY THE LOAD.






Q ~

/ednesday, May 8, 2019


Ü Щ Ū $\Sigma \cap \Pi$ OШ \Box $\overline{\Diamond}$ \Box Ω **₩ ₩** O \mathbb{T} \exists

CHECKED JOB NUMBER 19-034 CALE 4.25.2019 SHEET



MIN. I/2" REVEAL —
CONT. VENT —
2 x 4 OUTLOOKER —
CROWN MOULDING —
1 x 8 FRIEZE W/
PANEL MOULDING —

3/4" = 1'-0"




SLAB FOUNDATION PLAN (

DATE OF THIS PLOT Wednesday, May 8, 2019 ш С О Ш \bigcap $\exists \\ \square \\ Z$

о и ш п ⊢ > O UŽ <


CHECKED JOB NUMBER 19-034 SCALE 4.25.2019 SHEET

 \mathcal{J} . \mathcal{V}



SPEC HOME FOR: ORTHSIDE DRIVE PEVILLE, GEORGIA

JOB NUMBER 19-034 SCALE AS NOTED DATE 4.25.2019



Knight Design Group, Inc.
1270 CAROLINE STREET SUITE D416

DATE OF THIS PLOT Wednesday, May 8, 2019

> NEW SPEC HOME FOR: Northside drive Hapeville, georgia

DRAWN C.S.K.
CHECKED C.S.K.
JOB NUMBER 19-034
SCALE AS NOTED
DATE 4.25.2019
SHEET

A-5,0

PROVIDE SUPPORT FOR PORCH AND STEPS TO GRADE AS REQ'D.

NOTE: WHEN TWO ROOFS INTERSECT WITH DIFFERENT ROOF PITCHES, BLOCK TOP OF STUD WALLS AS REQ'D. TO LINE UP FASCIAS AT A MINIMUM OF 1'-O" OVERHANG

NOTE: ELEVATIONS REFLECT A SLAB FOUNDATION, IF ANOTHER FOUNDATION IS USED, BUILDER SHOULD DISREGARD FOUNDATION SHOWN

NOTE: RAFTERS ARE PITCHED FROM TOP OF CEILING JOISTS

NOTE: ATTIC VENTILATION PER LOCAL CODES AND REQUIREMENTS

GENERAL FRAMING NOTES

THE FOLLOWING NOTES ARE SUGGESTED MINIMUM REQUIREMENTS ONLY.
DUE TO A VARIANCE OF CODES PER REGION, PLEASE REFER AND COMPLY
WITH ALL YOUR LOCAL CODES, CONSULT WITH LOCAL ENGINEERS FOR ALL
STRUCTURAL REQUIREMENTS.

- PROVIDE PURLINS AT MID HEIGHT OF ALL WALLS.
 ALL JOISTS AND RAFTERS SHALL BE ALIGNED OVER STUDS BELOW.
 ALL HEADERS SHALL BE 2-2x/0's WITH 1/2" PLYWOOD FLITCH PLATE UNLESS OTHERWISE NOTED.
 FRAMER TO INSTALL DOUBLE FLOOR JOISTS UNDER PARTITION WALL PARALLEL TO JOIST DIRECTION.
 PROVIDE IX4 CROSS BRIDGING AT MID POINT OF SPAN OR 8'-O" O.C. MAXIMUM IN ALL FLOORS.
 ALL EXTERIOR CORNERS (INSIDE AND OUTSIDE CORNERS) SHALL BE BRACED WITH 1/2" CDX PLYWOOD. NAILING SCHEDULE SHALL BE 8d COMMONS AT 6" O.C. AT ALL EDGES AND 8d COMMONS AT 12" O.C. AT ALL INTERMEDIATE STUDS. (OPTION APPROVED DIAGONAL CORNER BRACES BOTH DIRECTIONS AT ALL CORNERS).
 ALL COLUMNS OR SOLID FRAMING SHALL EXTEND DOWN THRU ALL LEVELS AND TERMINATE AT THE BASEMENT FLOOR AND BE SUPPORTED BY A THICKENED SLAB, GRADE BEAM, OR FOOTING DESIGNED TO CARRY LOAD.
- 8. PROVIDE DOUBLE 2x8 STRONGBACK AT MID SPAN FOR CEILING JOISTS
- WITH SPAN GREATER THAN 10'-0".

 9. PROVIDE COLLAR TIES AT UPPER 1/3 OF VERTICAL DISTANCE BETWEEN RIDGE BOARD AND CEILING JOISTS AT 4'-0" O.C. MAXIMUM.

 10. HIP, VALLEY RAFTERS, AND RIDGE BOARDS SHALL BE ONE "2x" SIZE LARGER THAN RAFTERS.

- LARGER THAN RAFTERS.

 II. ROOF DECKING SHALL BE 1/2" CDX PLYWOOD MINIMUM.

 I2. WHERE PRE ENGINEERED FLOOR AND ROOF TRUSSES ARE USED, TRUSS MANUFACTURER MUST PROVIDE SHOP DRAWINGS WHICH BEAR SEAL OF REGISTERED ENGINEER IN STATE IN WHICH WORK IS TO BE PERFORMED.

 I3. ALL CEILING JOISTS AND RAFTER BRACING TO BEAR ON LOAD BEARING WALLS DESIGNED TO CARRY LOAD THRU ALL LEVELS AND TERMINATE AT BASEMENT FLOOR AND BE SUPPORTED BY THICKENED SLAB GRADE BEAM OR FOOTING DESIGNED TO CARRY LOAD.

 I4. ALL BASEMENT WALLS, BEAMS, AND COLUMNS TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.

 I5. ALL SOLID FRAMING, COLUMNS, BEAMS, ETC., TO BE DESIGNED BY LOCAL STRUCTURAL ENGINEER AND MEET ALL LOCAL CODES.

 I6. ALL FRAMED WALL DIMENSIONS ARE BASED ON 2 x 4 STUDS UNLESS
- 16. ALL FRAMED WALL DIMENSIONS ARE BASED ON 2 x 4 STUDS UNLESS OTHERWISE NOTED.

GENERAL NOTES

- I. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE
- NATIONAL, STATE, AND LOCAL CODES, REGULATIONS, AND FHA/VA MPS.

 CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT SITE BEFORE BEGINING CONSTRUCTION. ANY DISCREPANCIES SHALL BE REPORTED TO SPENCER RESIDENTIAL, INC. FOR JUSTIFICATION AND OR CORRECTION BEFORE PROCEEDING WITH WORK. CONTRACTORS AND/OR CORRECTION BEFORE PROCEEDING WITH WORK, CONTRACTORS
 SHALL ASSUME RESPONSIBILITY FOR ERRORS THAT ARE NOT REPORTED.

 3. ALL DIMENSIONS SHOULD BE READ OR CALCULATED AND NEVER SCALED.

 4. ALL FOOTINGS TO BE BELOW FROST LINE (SEE LOCAL CODE) AND MUST
 REST ON UNDISTURBED SOIL CAPABLE OF HANDLING THE BUILDING.
 CONSULT LOCAL ENGINEER FOR PROPER FOOTING AND REINFORCING SIZES.


 5. CONTRACTOR SHALL INSURE COMPATIBILITY OF THE BUILDING WITH ALL
 SITE REQUIREMENTS.
- SITE REQUIREMENTS.
- 6. IF BACKFILL EXCEEDS 4' AGAINST ANY FOUNDATION WALL, REINFORCE AS PER CODE.

 1. ALL FOUNDATION AND STRUCTURAL MEMBERS SHOULD BE VERIFIED AND STAMPED BY AN ENGINEER IN THE STATE WHERE CONSTRUCTION IS OCCURING DUE TO A WIDE VARIANCE IN LOCAL CODES, SOIL BEARING CONDITIONS, FROST LINE DEPTH, GEOLOGICAL AND WEATHER CONDITIONS, ETC. THE CONTRACTOR IS RESPONSIBLE FOR ADJUSTING AND VERIFYING
- ALL STRUCTURAL DETAILS AND CONDITIONS TO MEET ALL LOCAL CODES
 AND TO INSURE A QUALITY AND SAFE STRUCTURE.

 8. ALL WOOD, CONCRETE, AND STEEL STRUCTURAL MEMBERS SHALL BE OF A
 GOOD GRADE AND QUALITY AND MEET ALL NATIONAL, STATE, AND LOCAL

BUILDING CODES WHERE APPLICABLE.

9. ALL COLUMNS OR SOLID FRAMING SHOULD BE DESIGNED TO CARRY LOADS AND SHOULD EXTEND DOWN THRU THE LEVELS BELOW AND TERMINATE AT THE BASEMENT FLOOR OR AT OTHER BEARING POINTS DESIGNED TO CARRY THE LOAD.



DATE OF THIS PLOT Sunday, May 5, 2019

ОШ Щ 0 Ш O \overline{O} \square \vdash S DY \mathbb{H}_{N}

CHECKED JOB NUMBER 19-034 SCALE 4.25.2019 SHEET

6.



PLANNING AND ZONING DEPARTMENT

PLANNER'S REPORT

 DATE:
 June 13, 2019
 Key:

 TO:
 Tonya Hutson
 Compliant: ✓

 FROM:
 Lynn M. Patterson
 Not Compliant: ✓

 Incomplete: ∜
 Incomplete: ∜

BACKGROUND

The City of Hapeville has received a Design Review application from Michael Miles to remodel the exterior of an existing 1,800 square foot, two-story single-family dwelling at 831 Custer Street. The proposed changes include replacement fiber-cement siding, additional windows, the removal of a rear porch, and the conversion of an enclosed second-story side room to a screened-in porch.

The property is zoned R-SF, Residential Single-Family, and is subject to the Neighborhood Conservation Area of the Architectural Design Standards.

CODE

SEC. 81-1-7. NEIGHBORHOOD CONSERVATION AREA

Based on goals established in this chapter, the following standards are required in the neighborhood conservation area identified in section 81-1-3. This includes two subareas: subarea D and subarea E. All of the standards contained in this section shall apply to all development in all subareas. Subarea requirements are found within the applicable subsection.

This section shall govern subarea C of the commercial/mixed-use area. It may also govern one-family detached dwellings and two-family dwellings in the commercial/mixed-use area, provided that the section is applied in its entirety.

(a) Site development standards

- Except where indicated, setbacks shall be established by zoning.
 - On corner lots the principal building shall be located adjacent to the street intersection, subject to setback or build-to line requirements of zoning.
- zoning.Minimum building heights shall be established by zoning.
- Within subareas D and E maximum building heights shall be as established by zoning, except that:

Where this chapter provides a more-stringent standard as compared to the zoning code, the more-stringent standard shall prevail. The only exception to this shall be a use grandfathered under the zoning code.

Portions of buildings equal to or less than five feet from a side or rear lot line shall be limited in height to the greater of 16 feet.

Portions of buildings between five and ten feet of a side or rear lot line shall be limited in height to the greater of 25 feet. Portions of buildings ten feet or greater from a side or rear lot line shall be limited in height to 35 feet.

- Outside of subareas D and E maximum building heights shall be as established by zoning.
- ✓ All buildings shall provide first-story occupiable space, for the first ten feet of building depth along the enfronting facade.
- x Sidewalks shall be located along all public and private streets. Sidewalks shall consist of two areas: a landscape area and a clear area.
 - Developments less than one acre shall provide a minimum one-foot landscape zone and a minimum four-foot clear zone.
 Development of one acre or more shall provide a minimum two-foot landscape zone and a minimum five-foot clear zone.
 The above notwithstanding, multifamily developments and all developments along Dogwood Drive shall provide a minimum five-foot landscape zone and a minimum six-foot clear zone.

STAFF COMMENT: The project is a remodel of an existing structure. Plans do not include changes to placement or height. The property does not have an existing sidewalk.

(b) Supplemental Area and Fence Standards

- Developments shall locate landscape supplemental areas adjacent to first-story residential uses and place a minimum of one tree every 50 feet in the supplemental area. See list of allowed trees in section *93-2-14*.
- Chain link fencing is not permitted in areas visible from a public right-of-way.
- On all lots a fence, wall, curb or hedge between six and 48 inches in height is encouraged at the back of the required sidewalk, except at openings to access steps, drives or pedestrian walkways.
- Fences adjacent to the street shall be picket-wood, stone, composite materials or ornamental metal, with the finished side facing the street.
- Retaining walls adjacent to the required sidewalk shall not exceed 32 inches in height unless required by topography.
- All street-facing walls shall be faced with stone, brick, or smooth stucco.
- Small planting between retaining walls and the required sidewalk are encouraged and should have a minimum width of six inches.

STAFF COMMENT: The scope of the proposed work does not include changes to the supplemental area.

(c) Utility Standards

- Mechanical features shall not be located in the supplemental area or front yard and shall be screened from view from any park or along any public right-of-way with planting, walls or fences of equal or greater height. Acceptable materials for screening shall include those materials found in subsection (f)1., provided they are compatible with the principal structure.
- When located on rooftops, mechanical features shall be incorporated in the design of the building and screened with materials similar to the building.
- Street lights may be provided by the developer in an effort to maintain a safe, walkable and well-lit public area throughout the city; pedestrian-
- x All developments shall provide a light at the front door. Lighting designed to illuminate the path to the front door is allowed. Spotlighting may

STAFF COMMENT:

The scope of the proposed work does not include changes to utilities.

The current structure does not have a light at the front door.

(d) Parking and Traffic Standards

x One-family detached dwellings and two-family dwellings shall meet the following requirements:

Driveways shall have a minimum width of nine feet and a maximum width of 15 feet.

Circular drives are permitted.

A grass strip in the middle of driveways is encouraged.

Parcels are permitted a maximum of one driveway curb cut per street. In cases where a property abuts multiple streets the total number of curb cuts or portions thereof may be allocated to a single street.

Driveways shall have a maximum width of 12 feet for one-way and 24 feet for two-way.

Two curb cuts serving two one-way driveways shall be counted as one curb cut.

Public or private alleys, or driveway providing vehicular access to two or more parcels shall not constitute a curb cut.

New public streets shall not count as curb cuts.

Parcels are permitted a maximum of one driveway curb cut per street frontage. In cases where a property abuts multiple streets the total number of curb cuts or portions thereof may be allocated to a single street.

Carports shall be located in the rear or side yard, but shall not be visible from a public right-of-way.

Carport roofs shall be supported by columns with a minimum width and depth of eight inches.

The base of carport columns shall be faced in stacked brick or stacked stone to a minimum height of three feet above grade.

- On-site parking shall be prohibited in the supplemental areas. This shall not be interpreted as restricting on-street parking located along a public street.
- O Garage access on single-family lots shall be prohibited in the front yard of the home.

The property does not have a driveway. Access is via a curb cut shared with a neighboring property and parking takes place in the supplemental area.

The scope of the proposed work does not include changes to the supplemental area or on-site parking.

(e) Roof and Chimney Standards

STAFF COMMENT:

Principal building roofs for one-family detached dwellings shall have a minimum usable life of thirty (30) years, per manufacturer's warranty. 0 0 Roof shingles shall be slate, cedar, or asphalt. Roof tiles shall be clay, terra cotta or concrete. 0 0 Metal roofs are: Allowed on one-family and two-family detached dwellings; Permitted on multifamily and townhouse dwellings only when screened form the adjacent street by a parapet wall. Gutters shall be copper, aluminum or galvanized steel. 0 0 Downspouts shall match gutters in material and finish. 0 Roof forms shall be based on architectural style. 0 All roofs, excluding dormers, shall overhang a minimum of 12 inches beyond the facade. 0 Dormers are permitted on all style homes (unless specified), but shall not be taller than the main roof to which they are attached. Chimneys exposed to the public view may not be faced in wood or cement based siding and may not be of an exposed metal or ceramic pipe. 0 All chimneys shall be wrapped in a brick, stone or suitable masonry finish material. 0 Chimneys on exterior building walls shall begin at grade. Chimneys shall begin at grade and be faced with brick or stacked stone; extend chimneys between three and six feet above the roof line. 0

STAFF COMMENT: The scope of the proposed work does not include changes to the roof.

(f) Street Facing Facade and Style Standards.

Exterior facade materials shall be limited to:

Full-depth brick;

Natural or cast stone;

✓ Smooth natural-wood siding and/or cement-based siding;

Shake siding;

Painted fish-scale style shingles, but only when used in front gables;

True, smooth hard-coat stucco, provided that its use is limited to gables of Tudor revival-style buildings.

x Exterior building materials shall not be:

Simulated brick veneer, such as Z-Brick;

Exterior insulation and finish systems (EIFS);

Exposed concrete block;

Metal siding or other metal exterior treatment;

Glass curtain walls;

Liquid vinyl;

T-1-11 siding;

Vinyl siding, except that existing one-family detached homes with vinyl siding covering more than 70 percent of the exterior facade may replace said siding or construct an addition faced in vinyl siding.

- ✓ Facade materials shall be combined horizontally, with the heavier below the lighter.
- \checkmark Blank, windowless walls are prohibited along all facades. See subsection 81-1-7(g)11.
- Foundations shall be constructed as a distinct building element that contrasts with facade materials. Foundations that are exposed above the ground, must be parged with cement, stuccoed over or be faced in brick, natural stone, or cast stone.
- All exterior stair risers visible from a street shall be enclosed.
- Porches, stoops, and balconies may be located in the front or side yard.
- Porches, stoops, and balconies along front and side building facades shall not be enclosed with screens, plastics, or other materials that hinder visibility and/or natural air flow.
- Porches, stoops, and balconies shall be made of painted or stained wood, stone, brick, or ornamental metal, subject to the additional restrictions below.
- Wooden porches, stoops, and balconies shall provide top and bottom horizontal members on railings. The top railing shall consist of two elements. The upper element shall measure two [inches] by six inches and the lower element shall measure two [inches] by four inches. The bottom railing shall measure two [inches] by four inches.
- S Front porches and front stoops of principal buildings shall face and be parallel to the front lot line or build-to line.
- ✓ Porch and stoop foundations shall be enclosed.
- Front and side porches and stoops shall not have unpainted, unstained or otherwise untreated or exposed pressure treated lumber along the building line that abuts a public right-of-way.

- Balconies shall have not less than two clear unobstructed open or partially open sides. Partially open is to be constructed as 50 percent open or more. The total combined length of the open or partially open sides shall exceed 50 percent of the total balcony perimeter.
- Stoops and porch[es] shall be a minimum of two feet and a maximum of four feet from grade to the top of the stairs, unless existing topography is greater.
- Stoops shall provide a minimum top landing of four feet by four feet.
- Stoop stairs and landings shall be of similar width.
- Stoops may be covered or uncovered.
- When provided, porches shall have a minimum clear depth of eight feet from building facade to outside face of column.
- Second to the state of the adjacent facade.
 Second to the adjacent facade.
- ✓ Side porch widths (including wraparound porches) shall be between 25 percent and 100 percent of the adjacent facade.
- Enfronting porches may have multistory verandas, living space, or balconies above.
- O Porch columns shall be spaced a maximum distance of eight feet on center.
- Front porch columns shall have foundation piers extending to grade.
- ✓ All porches shall be covered.
- Enfronting balconies are only permitted on attached or detached one-family home facades when porches are not provided on said facades.
- O Enfronting balconies shall have a minimum clear depth of four feet.
- Enfronting balcony widths shall be between 25 percent and 100 percent of the adjacent facade.
- Salconies may be covered or uncovered.

The proposed plans replace existing asbestos siding with cement-based siding on the second story but retain existing painted concrete block on the first story. Concrete blocks are not a permitted façade material.

The structure is built on a slab foundation and has no simulated foundation.

It is unclear if exterior stairs leading to the porch will be replaced. If so, the applicant should ensure the stairs have enclosed risers.

STAFF COMMENT:

Porches may not be enclosed with screens or other materials that hinder visibility. The proposed porch is screened, which is not compliant.

The applicant should provide the proposed materials used in the porch and attached stairs, ensuring they are stained wood, stone, brick, or ornamental metal.

Stoops and porches shall be a maximum of four feet from grade to the top of the stairs. A second story porch is not compliant. Porches must have a clear depth of at least 8'. The proposed porch has a clear depth of approximately 7', which is not compliant.

(g) Door and window standards.

- x The main entry door to enfronting principal buildings shall face, be visible from, and be accessible from the adjacent public sidewalk.
- The main entry door to all uses shall be linked to the sidewalk via a pedestrian walkway or wheelchair access.
- Building numbers at least six inches in height shall be located above or beside the street-facing pedestrian entrance, or above or beside the stairs accessing a front porch.
- O Doors that operate as sliders are prohibited along enfronting facades.
- Window panes shall be recessed a minimum of three inches and a maximum of eight inches from the adjacent facade, except on frame houses, on which panes shall be recessed a minimum of two inches.
- Where windows lights are utilized they shall be true divided lights, simulated divided lights, or one-over-one lights. Grids-between-glass (GBGs) are prohibited.
- 👸 Window trim shall not be flush with the exterior facade and shall provide a minimum relief of one-quarter inch or greater.
- Where used, window shutters shall match one-half the width of the window opening.
- Painted window or door glass is prohibited.
- Enfronting windows and door glass (except on churches and fire stations) shall utilize clear glass or tinted glass. Tinted glass shall have a transmittance factor of 50 percent or greater and shall have a visible light reflectance factor of ten or less.
- Windows shall be provided for a minimum of thirty (30) percent and a maximum of 50 percent of the total street-facing facade of the principal building, with each facade and story calculated independently.
- Street-facing window units shall not exceed 28 square feet with minimum height of three feet, with the exception of transoms and fan lights.
- Wood trim between four and six inches wide shall surround windows of wood frame structures. Windows grouped together shall have center mullions two inches wider than the side trim.

🖑 Sills shall be of masonry, wood, stone, cast stone, or terra cotta.

The main entry door is not accessible by and connected to the adjacent sidewalk/street by a pedestrian walkway.

Building numbers at least six inches in height adjacent to the front entrance should be shown on plans. The applicant should ensure windowpanes are recessed between 2" and 8" from the adjacent façade.

The applicant should ensure no grids-between-glass are utilized.

STAFF COMMENT: The applicant should ensure

The applicant should ensure window trim provides a minimum relief of 1/2" or greater from the exterior façade.

Window shutters must match one-half the width of the window opening.

The applicant should ensure windows have wood trim between 4" and 6" wide.

Center mullions must be 2" wider than the side trim.

The applicant should ensure windows have sills made of masonry, wood, stone, cast stone, or terra cotta.

(h) Detached one-family dwellings/ two-family dwellings. In addition to the requirements of subsections (a) through (g), the following shall apply to detached one-family dwellings and two-family dwellings.

- First Stories . First stories shall be elevated above the grade between two and four feet, unless existing topography is greater or unless wheelchair access is desired and cannot be provided from the side or rear.
- Window Sills. Enfronting first story window sills should be no less than two and one-half feet and no more than three and one-half feet above finished floor elevation.
- Wheelchair access. Where practical, wheelchair access, when provided, should be installed at the side or rear of the home in order to preserve the architectural character of the primary facade.
 - Architectural style. Architecture is one of the most critical components of place, and nowhere is this more evident than on building facades.
- The design and character of street-facing facades is a reflection of both buildings and their users, and must be carefully considered for its impact on the overall sense of place.

House is built on a slab foundation. The first story is not elevated between 2' and 4' above grade.

The dwelling does not match any recognized historical architectural style.

STAFF COMMENT: The scope of the proposed work does not include changes to the structure of the building.

The applicant should ensure enfronting first story windowsills are between 2'-6" and 3'-6" above the finished floor elevation.

Outbuildings. In conventional development, outbuildings are often designed and located as an afterthought. Yet in traditional towns and cities, outbuildings serve to enrich the quality of design through their placement, design and use. In Hapeville, where outbuildings are provided on many residential lots, their design must be to the same high standards found in the community's neighborhoods.

The following standards shall apply to construction of new outbuildings in residential districts.

- i. On lots with one street frontage, set outbuildings back at least 15 feet behind the front facade of the principal building.
- ii. On corner lots, outbuildings should be setback at least 15 feet behind the front facade of the principal building and with a setback greater than or equal to that of the facade along the side lot line.
- iii. Outbuilding may be linked to the principal building with covered walks, trellises or enclosed breezeway.
- iv. Outbuildings shall be of compatible material and architectural style to the principal building.
- v. Outbuildings shall have a minimum height of 14 feet and a maximum height of that of the principal building or 25 feet, whichever is less.
- vi. Outbuildings shall be set a minimum of ten feet from any other outbuilding on adjoining lots.

STAFF COMMENT:

RECOMMENDATIONS

Sec. 81-1-5. Applicability

Upon review of the information provided by the Applicant, the following items have been found to be missing or deficient and should be addressed prior to formalizing a recommendation:

The project is a remodel of an existing structure. Plans do not include changes to placement or height.

The property does not have an existing sidewalk.

The current structure does not have a light at the front door.

The property does not have a driveway. Access is via a curb cut shared with a neighboring property and parking takes place in the supplemental area. The proposed plans replace existing asbestos siding with cement-based siding on the second story but retain existing painted concrete block on the first story. Concrete blocks are not a permitted façade material.

The structure is built on a slab foundation and has no simulated foundation.

It is unclear if exterior stairs leading to the porch will be replaced. If so, the applicant should ensure the stairs have enclosed risers.

Porches may not be enclosed with screens or other materials that hinder visibility. The proposed porch is screened, which is not compliant.

The applicant should provide the proposed materials used in the porch and attached stairs, ensuring they are stained wood, stone, brick, or ornamental metal.

Stoops and porches shall be a maximum of four feet from grade to the top of the stairs. A second story porch is not compliant.

Porches must have a clear depth of at least 8'. The proposed porch has a clear depth of approximately 7', which is not compliant.

The main entry door is not accessible by and connected to the adjacent sidewalk/street by a pedestrian walkway.

 $Building\ numbers\ at\ least\ six\ inches\ in\ height\ adjacent\ to\ the\ front\ entrance\ should\ be\ shown\ on\ plans.$

The applicant should ensure windowpanes are recessed between 2" and 8" from the adjacent façade.

The applicant should ensure no grids-between-glass are utilized.

The applicant should ensure window trim provides a minimum relief of "" or greater from the exterior façade.

Window shutters must match one-half the width of the window opening.

The applicant should ensure windows have wood trim between 4" and 6" wide.

Center mullions must be 2" wider than the side trim.

The applicant should ensure windows have sills made of masonry, wood, stone, cast stone, or terra cotta.

The applicant should ensure enfronting first story windowsills are between 2'-6" and 3'-6" above the finished floor elevation.

Additionally, as the project includes the removal of asbestos siding, the applicant must ensure all work meets environmental safety standards.

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL [DATE: 3/3///					
i	All applications must be typed or neatly printed. Applications or an authorized representative is required to personally appear at the Design Review Meeting to answer questions.					
 	The Design Review Committee meets the thin Every attempt will be made to place your appropriate agenda following the submittal of supporting documents; however, that may not reserves the right to schedule applications as de	plication for review on the next a completed application with always be possible. The City				
Applicant:	1CHAEL MILES Contact Nu	mber:				
Applicants Add	ress: 405 LAKEFRONT CT					
E-Mail Address:	Zoning Cla	assification: <u>h-SF</u>				
Address of Prop	posed Work: 631 CUSTER ST HAR	EVILLE GA				
Parcel ID# (INFO	ORMATION MUST BE PROVIDED): 14 0098	00080220				
Property Owner	TE MILES AHEAD LLC Contact N	umber:				
with focade modification, demolish rear porch and add screened porch on right side						
Contractors Na	ame: CAMEGN G/BSON Con	stact Number:				
Contact Person	n: Con	tact Number:				
hereby make application to the City of Hapeville, to the Design Review Committee for the above referenced property. I do hereby swear or affirm that the information provided here and above is true, complete and accurate, and I understand that any inaccuracies may be considered just cause for invalidation of this application and any action taken on this application. I understand that the City of Hapeville, Georgia, esserves that right to enforce any and all ordinances regardless of any action or approval on this application. further understand that it is my/our responsibility to conform with all of City of Hapeville's Ordinances in all. I hereby acknowledge that all requirements of the City of Hapeville shall be adhered to. I can read and write the English language and/or this document has been read and explained to me and I have full and coluntarily completed this application. I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for violation thereof.						
Applicants Sign	gnature	Date				

Project Class (check or	ne):	
Residential	Commercial	Mixed-Use Development
Project Type:		
New Commercial C	onstruction	Addition to Existing Commercial Building
Addition to Existing	Residential Structure	Accessory Structure
Site Plan, Grading &	LandscapingNe	w Single Family Residential Construction
Other		
Total Square Footage of pr	oposed New Construction:	1860
Total Square Footage of ex	xisting building:	0
Estimated Cost of Construc	tion: <u>35,600</u>	
List/Describe Building Mate	rials <u>proposed</u> for the exter	rior facade of the new structure:

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does **NOT** make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)

I MICHAEL MILES swear or affirm that before receipt of an application, I have received this notice and I read and write the English language or I have had someone read and explain this document to me.



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

	the undersigned, agree that with my signature and llowing:	I submission to the City of Hap	eville, I have done the
	Read the City of Hapeville's Architectural Desig proposed project. The Architectural Design Gu tps://library.municode.com/ga/hapeville/codes/co	idelines may be found here:	
	ego. J. martar J. martines delegating Edy Trape ville, codes, et	or oraniances: nodela=r i	HCOOK CHOLANDEST
~	Ensured that my proposed project meets all of of Ordinances.	the required criteria per the Ci	ty of Hapeville Code
<u>m</u>	Submitted my application materials in full by the Design Review Committee meeting.	e published deadline for review	w by Staff prior to the
nc-	Identified and explained all deficiencies or com with the requirements set forth in the Code. The document in the application.	ponents of the proposed proje nis explanation should be subm	ct that do not meet nitted as a separate
	Understood that any deficiencies in the applica Design Review Committee meeting or the appli		
	Submitted architectural drawings and details fo Community Services or Planning & Zoning Depa		writing by the
	Agreed to submit any required revisions by the to the Community Services Department for rev		
MI	MICHAEL MUES AM		5/2//11
Printe	nted Name Sign	ture	Date

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.

Michael Miles 831 Custer Street



Front Elevation



Rear Elevation



Right Side Elevation




Left Side Elevation









CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219

A1.0

DESIGNER: DANA T DESIGNS 678-596-8590 danatdesignsi@gmail.com RELEASE FOR CONSTRUCTION









CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219

A1.1

DESIGNER: DANA T DESIGNS 678-596-8590 <u>danatdesignsi@gmail.com</u> RELEASE FOR CONSTRUCTION





CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219

B1.0

DESIGNER: DANA T DESIGNS 678-596-8590 <u>danatdesignsi@gmail.com</u> RELEASE FOR CONSTRUCTION






PROPOSED LEFT SIDE ELEVATION

SCALE: 1/4" = 1'-0"

CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219

B1.1



PARTITION LEGEND:

SOLID PARTITION REPRESENTS PERMINANT PARTITION


DOTTED LINE PARTITION REPRESENTS PARTITION BEING REMOVED

SLANTED LINE PARTITION REPRESENTS NEWLY BUILT PARTITION


1/2 PARTITION (SEE NOTES FOR HEIGHT OF PARTITION)

BUBBLE ICON REPRESENTS CHANGE IN DOORS, WINDOWS OR STAIRS

BLACK DOT REPRESENTS (3) 2X4 VERTICAL LOAD BEARING POST










CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219 C1.0


DESIGNER: DANA T DESIGNS 678-596-8590 danatdesignsi@gmail.com RELEASE FOR CONSTRUCTION NOTE: ALL FLOOR JOISTS FOR 1ST FLOOR ARE 2X10 @ 16" O.C.



CEILING FRAME PLAN-1ST FLOOR

SCALE: 1/4" = 1'-0"

NOTE: ALL CEILING JOISTS FOR 2ND FLOOR ARE 2X8 @ 16" O.C.





CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219 D1.0


DESIGNER: DANA T DESIGNS 678-596-8590 danatdesignsi@gmail.com RELEASE FOR CONSTRUCTION

NOTE


- 1. CODES: ALL WORK SHALL BE IN ACCORDANCE W/ APPLICABLE REQUIREMENTS OF THE 2012 (OR CURRENT) INTERNATIONAL RESIDENTIAL CODE (IRC) W/ GEORGIA STATE AND DEKALB COUNTY AMENDMENTS, AND THE INTERNATIONAL ENERGY CODE COUNCIL.
- 2. CONTRACTOR SHALL PERFORM SITE INSPECTIONS AND BECOME FAMILIAR W/ ALL EXISTING CONDITIONS AFFECTING THE WORK.
- 3. VERIFY ALL ROUGHT OPENINGS AND CLEARANCES REQUIRED FOR DOORS, WINDOWS, MILLWORK, FIXTURES AND EQUIPENT W/ ACTUAL PRODUCTS TO BE INSTALLED.
- 4. EXTERIOR DIMENSTION SHOWN ARE TO FACE OF STUD/FACE OF SLAB.

INTERIOR DIMENSIONS SHOWN ARE TO THICKENED SLAB.

6. CONCRETE SHALL BE 3000 PSI MINIMUM COMPRESSIVE STRENGTH.









CLIENT: ATYP, LLC PROJECT: 831 CUSTER AVENUE DATE: 05-22-19 PROJECT #52219 E1.0

DESIGNER: DANA T DESIGNS 678-596-8590 <u>danatdesignsi@gmail.com</u> RELEASE FOR CONSTRUCTION

CITY OF HAPEVILLE DESIGN REVIEW APPLICATION

SUBMITTAL	DATE: MAR 2 0 2019
NOTE:	All applications must be typed or neatly printed. Applications or an authorized representative is required to personally appear at the Design Review Meeting to answer questions.
	The Design Review Committee meets the third Wednesday of each month. Every attempt will be made to place your application for review on the next month's agenda following the submittal of a completed application with supporting documents; however, that may not always be possible. The City reserves the right to schedule applications as deemed necessary.
Applicant:	MMer Lowry Avelopments Contact Number: 478-952-6662
	Idress: 2964 Penchtee R.J. NW. Svite S40 Atlanta, 6H 3>3
E-Mail Addres	ss: Obo Mas Caville 100 g. O. Zoning Classification: Village
Address of Pr	roposed Work: Shuted between Central, Glore the + WM mg han
Parcel ID# (IN	FORMATION MUST BE PROVIDED): 140/27000 204 29 , 140/27000 2037
Property Own	er: Huperme Dev. Arthorn Contact Number: 404-328-8130
	cription (including occupancy type): See attacked nearther.
Contractors	Name: MMer Lary Developments Contact Number: 773-953-4422
Contact Pers	son: Rob Ropas Contact Number:
property. I do accurate, and application and reserves that right	application to the City of Hapeville, to the Design Review Committee for the above referenced hereby swear or affirm that the information provided here and above is true, complete and I understand that any inaccuracies may be considered just cause for invalidation of this d any action taken on this application. I understand that the City of Hapeville, Georgia, ght to enforce any and all ordinances regardless of any action or approval on this application.
full. I hereby a	cknowledge that all requirements of the City of Hapeville shall be adhered to. I can read and shall shall be adhered to the comment has been read and explained to me and I have full and
voluntarily com	pleted this application. I understand that it is a felony to make false statements or writings to
tile City of mape	eville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for violation thereof.
Applicants	3/19/19 Signature Date
· · · · · · · · · · · · · · · · · · ·	g

Project Class (check one):
ResidentialCommercialMixed-Use Development
Project Type:
New Commercial ConstructionAddition to Existing Commercial Building
Addition to Existing Residential StructureAccessory Structure
Site Plan, Grading & LandscapingNew Single Family Residential Construction
Other
Total Square Footage of proposed New Construction: \$67,700
Total Square Footage of existing building:
Estimated Cost of Construction:
List/Describe Building Materials on the exterior of the <u>existing</u> structure: MH — faw (cno
List/Describe Building Materials <u>proposed</u> for the exterior facade of the new structure: Touthous = first cement board + buffer siding, fiber Cement lop siding, asphalt 100f Shingles, aluminum clad windows, cluminum getters + downsports Connercial = bride vener, hard coat strees, fibric aurings

NOTICE

Please be advised that the Community Service Department is here to assist all applicants regarding application procedures, meeting schedules and necessary deadlines. The Community Service Department does **NOT** make any final decisions for the Design Review Committee, Sign Committee, Planning Commission, Board of Appeals or rezoning request to Mayor and Council.

A complete application must be submitted before the Community Service Department will accept an application and forward the same to the appropriate entity.

Building inspections issued by the City of Hapeville are contracted out to State of Georgia Certified Inspectors. These inspectors make the final decisions regarding building, electrical, plumbing and HVAC work completed in the City of Hapeville. The Hapeville Fire Marshal conducts inspections issued through the Community Services Department as needed. Both the Certified Inspectors and Fire Marshal make the final decisions before Certificates of Occupancy's are issued.

Please be advised that the Community Service Department shall not be responsible for your purchasing materials, equipment, items, signs, etc... before you receive final approval by any entity whose approval is required.

I understand that it is a felony to make false statements or writings to the City of Hapeville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosecuted for a violation thereof.

(Please Print & Initial)



DEPARTMENT OF PLANNING AND ZONING

DESIGN REVIEW APPLICATION INSTRUCTIONS AND ACKNOWLEDGEMENT

I, the undersigned, agree that following:	with my signature and submission to the City of Hapev	ille, I have done the
proposed project. The A	e's Architectural Design Guidelines and relevant Code s rchitectural Design Guidelines may be found here: /ga/hapeville/codes/code of ordinances?nodeId=PTIIC	•
Ensured that my propose of Ordinances.	ed project meets all of the required criteria per the City	of Hapeville Code
Submitted my application Design Review Committee	n materials in full by the published deadline for review ee meeting.	by Staff prior to the
· · · · · · · · · · · · · · · · · · ·	all deficiencies or components of the proposed project et forth in the Code. This explanation should be submit tion.	
Understood that any defi	iciencies in the application must be resolved at least 10 ee meeting or the application may not be presented to	
	drawings and details for all projects unless allowed in w lanning & Zoning Department.	riting by the
	quired revisions by the Design Review Committee with test Department for review prior to requesting any perm	nits.
Phoh Propes	n-h	3/2/19
Printed Name	Signature	Date

Should you have any questions, please do not hesitate to contact the Community Services Department at 404-669-2120.

Thank you for interest and investment in the City of Hapeville.

All that parcel of land lying in and being located in Land Lot 98 and 127 of the 14th District, Fulton County, Georgia, and being more particularly described as follows:

Commencing at a 1/2 inch capped rebar set at the southwest quadrant of the intersection of Central Ave and Colville Ave, said capped rebar being the ture point of beginning (POB).

Thence leaving said POB, S 01° 12' 25.9" W for a distance of 215.6095 feet to a point on a line.

Thence, N 73° 02' 33.1" W for a distance of 153.8800 feet to a point on a line.

Thence, N 08° 10' 44.9" E for a distance of 5.7000 feet to a point on a line.

Thence, N 72° 56' 24.1" W for a distance of 406.1516 feet to a point on a line.

Thence, N 17° 16′ 55.5″ E for a distance of 10.0437 feet to a point on a line.

Thence, N 73° 14' 01.5" W for a distance of 94.5067 feet to a point on a line.

Thence, N 72° 45' 36.0" W for a distance of 49.9771 feet to a point on a line.

Thence, N 10° 05' 03.5" E for a distance of 104.7466 feet to a point on a line.

Thence, N 65° 51' 37.7" E for a distance of 59.9364 feet to a point on a line.

Thence, N 65° 53' 01.3" E for a distance of 97.4780 feet to a point on a line.

Thence, S 78° 08' 45.4" E for a distance of 36.0818 feet to a point on a line.

Thence, S 69° 13′ 19.6″ E for a distance of 50.0000 feet to a point on a line.

Thence, N 20° 46′ 40.4″ E for a distance of 15.0000 feet to a point on a line.

Thence, S 69° 45′ 39.2″ E for a distance of 77.7820 feet to a point on a line.

Thence, S 68° 50' 14.8" E for a distance of 49.8439 feet to a point on a line.

Thence, S 68° 57' 42.6" E for a distance of 200.3277 feet to a point on a line.

Thence, S 68° 48' 41.0" E for a distance of 49.9678 feet to a point on a line.

Thence S 69° 16' 47.1" E a distance of 77.0059 feet to a 1/2 inch rebar set, said rebar being the true point of beginning.

Said parcel of land contains 3.255 acres (141,786.66 square feet).



2964 Peachtree Rd. NW Suite 540 Atlanta, GA 30305

March 20, 2019

Community Service Department 3474 North Fulton Avenue Hapeville, GA 30354

To whom it may concern,

Miller Lowry Developments respectfully requests your positive consideration for the attached Design Review Committee Application. Our intent is to develop "The Village Walk at Hapeville", a new +/- 3.25 acre mixed-use community, located at the gateway to Hapeville. The specific property is nestled between Central Avenue, Colville Avenue, and Willingham Dr. just east of I-85. Our proposed site plan includes 20 townhomes and approximately 7,132 sf of boutique commercial space, with the townhomes being no taller than 2.5 stories each.

Since our original submittal to staff on 12.11.18 for site plan approval, Miller Lowry has made significant changes to the site plan design and architecture to address staff's comments, and or concerns, along with designing a site that works well with the City's current characteristics. Much thought has been put into the plan in making the project an extension of the commercial developments to the east of the site across from Colville Avenue, while also making the residential portion of the site an extension of the residential neighborhoods south of the site across Willingham Dr.

Each townhome will have a 2 car garage accessed by a rear drive aisle and all front entry facades will face a Village Green that preserves many of the existing trees on site. The intent of the Village Green concept is to conserve the openness of the site, by not overwhelming the site from a density perspective. Additional amenities to the residents will be a pervious walking path around the Green and a common area firepit, not to mention the walkable retail options nearby.

The commercial space will be in two single-level buildings located along the eastern border of the site and will incorporate architecture that compliments the immediate areas buildings.

Miller Lowry Developments will be submitting to the Board of Appeals for approval of 4 total variances including: waving the sidewalk requirement for Willingham in order to conserve trees and the sites topography, decreasing the required distance between buildings from 20' to 10' which we already have approval from the Fire Marshall on, decreasing the commercial off street

parking from 36 to 32 parks, and lastly reducing the building height on the commercial portion to 18'.

Sincerely,

Miller Lowry Developments



2964 Peachtree Rd. NW Suite 540 Atlanta, GA 30305

March 19, 2019

To Whom It May Concern,


This letter is to serve that the Development Authority of Hapeville, GA is the property owner of Parcel Identification Numbers: 14012700020429, 140127000379. The Development Authority is aware that Miller Lowery Developments is applying for a Design Review Committee for the property located at the Parcel ID Numbers above.

Sincerely, Robert Rojas

Miller Lowry Developments


Agreed to and accepted by current owners:


Katrina Bradbury (Chairman of The City of Hapeville DDA):















DIEDRICH CHI





DIEDRICH CHI

730 PEACHTREE STREET, NE STUDIO 325 ATLANTA, GEORGIA 30308 678.244.6270

www.KDCarchitects.com

06.14.19
03.20.19
DATE
D.R.C. REVISION
D.R.C. APPLICATION
DESCRIPTION

VILLAGE WALK AT HAPEVILLE LAND LOTS 89 & 127, 14TH DIST. CITY OF HAPEVILLE FULTON CO. GEORGIA

18030


01.22.2019

CHECKED


TITLE

ELEVATIONS

A201










STUDIO 325 ATLANTA, GEORGIA 30308 678.244.6270

VILLAGE WALK AT






STUDIO 325 ATLANTA, GEORGIA 30308

www.KDCarchitects.com

89 & 127, 14TH DIST. CITY OF HAPEVILLE



AGE

LANDSCAPE WORK SHALL INCLUDE, BUT IS NOT LIMITED TO, THE SUPPLYING OF ALL PLANT MATERIALS SPECIFIED, THE FURNISHING OF ALL LABOR, EQUIPMENT WATER, ELECTRICITY, EQUIPMENT AND ALL MATERIALS CALLED. THE WORK SHALL INCLUDE MAINTAINING OF ALL PLANTS AND PLANTING AREAS UNTIL FINAL ACCEPTANCE BY THE OWNER. THE LC SHALL ASSIGN A QUALIFIED PROJECT MANAGER AND FIELD SUPERVISOR TO WORK DIRECTLY WITH THE LA AND SUPERVISE THE WORK AT ALL TIMES THROUGH FINAL OWNER ACCEPTANCE.

VERIFICATION OF EXISTING CONDITIONS IS THE RESPONSIBILITY OF THE LC. THIS INCLUDES BUT IS NOT LIMITED TO: SOI CONDITIONS, UTILITIES (UNDERGROUND AND ABOVE GROUND), EXISTING STRUCTURES, ETC. THE LC SHOULD BE COMPLETELY FAMILIAR WITH LANDSCAPE PLANS PRIOR TO COMMENCEMENT OF WORK. POTENTIAL PROBLEMS, ETC. SHOULD BE MADE KNOWN TO THE LA PRIOR TO COMMENCEMENT OF WORK

4

EXISTING OR PROPOSED DRAINAGE PATTERNS ARE NOT TO BE DISTURBED BY THE LC IN A WAY THAT IS INCONSISTENT WITH THE LANDSCAPE PLANS. ALL REASONABLE SAFEGUARDS ARE TO BE TAKEN IN ORDER TO PROTECT EXISTING STRUCTURES, PAVEMENT, FURNISI LAWN AND LANDSCAPING. THE LC IS RESPONSIBLE FOR DAMAGE THAT OCCURS AS A RESULT OF LC NEGLIGENCE.

THE LC IS RESPONSIBLE FOR COORDINATING WORK TO BE PERFORMED WITH THE WORK OF OTHER SUBCONTRACTORS ON THE SITE, INCLUDING SCHEDULING AND PHYSICAL INTERFERENCE.

C MUST CONFIRM THE AVAILABILITY OF ALL SPECIFIED PLANT MATERIAL PRIOR TO THE COMMENCEMENT OF WORK. THE LC ARRANGE FOR APPROVAL FOR PLANT MATERIALS BY THE LA VIA FIELD VISITS/TAGGING AND OR SUBMISSION OF PLANT ES AT THE DISCRETION OF THE LA.

ALL PLANT MATERIAL SHALL MEET OR EXCEED THE AMERICAN STANDARDS FOR NURSERY STOCK AS ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMAN AND APPROVED BY THE AMERICAN NATIONAL STANDARDS INSTITUTE INC.

ALL PLANT MATERIAL SIZES SPECIFIED ARE MINIMUM SIZES. ALL CONTAINER AND TREE CALIPER SIZES ARE MINIM CONTAINER OR CALIPER SIZE MAY BE INCREASED IF NECESSARY TO PROVIDE OVERALL PLANT SIZE SPECIFIED.

NO PLANT SUBSTITUTIONS WILL BE PERMITTED WITHOUT PRIOR WRITTEN APPROVAL FROM THE LA. ANY SUBSTITUTIONS MUST BE SUBMITTED IN WRITING ACCOMPANIED BY PICTURES OR SAMPLES FOR APPROVAL BY THE LA PRIOR TO INSTALLATION.

5

THE LC IS RESPONSIBLE FOR ENSURING THAT THE SOIL IN ALL PLANTED AREAS IS OF AN APPROPRIATE TYPE AND CONSISTENCY FOR PLANTING AND AT THE CORRECT PH. THE LC IS RESPONSIBLE FOR FIELD VERIFYING SOIL AND SUITABILITY, AND ANY NECESSARY AMENDMENTS SHOULD BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE LA. L SHRUB BEDS SHALL BE TILLED TO MINIMUM DEPTH OF 12". PLANTING BEDS TO BE SEPARATED FROM LAWN AREAS WITH A 4" EP EXCAVATED TRENCH. THE TRENCH SHALL HAVE A VERTICAL FACE AGAINST THE LAWN AREA, AND A GENTLY TAPERED GE LEADING INTO THE SHRUB BED.

THE LC SHALL BE RESPONSIBLE FOR REMOVING EXISTING VEGETATION AS REQUIRED AND PFTO INSTALLATION OF PLANT MATERIALS. RING PLANTING AREAS PRIOR

ANDSCAPE CONTRACTOR SHALL TEST PROJECT SOILS TO VERIFY THAT THE SOILS ON-SITE ARE ACCEPTABLE FOR PROPER THAN THE LANDSCAPE CONTRACTOR SHALL OF PLANT MATERIALS AND ADEQUATE DRAINAGE IN PLANT BEDS AND PLANTERS. THE LANDSCAPE CONTRACTOR SHALL DINATE THE LOCATION, AND PROCUREMENT OF EXISTING ON-SITE SOIL SAMPLES WITH THE LANDSCAPE ARCHITECT. SENTATIVE SAMPLES SHALL BE SUBMITTED TO A CERTIFIED TESTING LABORATORY FOR ANALYSIS. THE FINDINGS, THER WITH RECOMMENDATIONS FOR AMENDING THE SOILS SHALL BE REVIEWED AND APPROVED BY THE OWNER AND SCAPE ARCHITECT PRIOR TO DELIVERY AND INSTALLATION OF PLANT MATERIALS AT THE JOB.

ALL PLANTING BEDS SHALL BE STAKED AND OR PAINTED BY THE LC FOR APPROVAL BY THE LA PRIOR TO PLANT INSTALLATION. TREES SHALL BE LOCATED WITH STAKES OR FLAGS FOR APPROVAL BY THE LA PRIOR TO INSTALLATION. THE LANDSCAPE CONTRACTOR SHALL ENSURE ADEQUATE VERTICAL DRAINAGE IN ALL PLANT BEDS AND PLANTERS. VERTICAI DRIILING THROUGH HARDPAN AND COMPACTED FILL SHALL BE ACCOMPLISHED TO ENSURE DRAINAGE.

ALL PROPOSED TREES SHALL BE INSTALLED EITHER ENTIRELY IN OR ENTIRELY OUT OF PLANTING BEDS. PLANTING BED OUTLINES SHALL NOT BE OBSTRUCTED AND SHALL BE SMOOTH AND FLOWING. IF TREES ARE LOCATED OUTSIDE PLANTING BEI IN SOD AREAS, MAINTAIN A MINIMUM 3' WIDE OFFSET. PLANT QUANTITIES SHOWED ON THE LANDSCAPE CONTRACT DOCUMENTS ARE FOR THE CONVENIENCE OF THE LANDSCAPE RACTOR. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL QUANTITIES AND REPORTING ANY REPANCIES TO THE LANDSCAPE ARCHITECT FOR CLARIFICATION PRIOR TO CONTRACT AWARD AND COMMENCEMENT OF

6

(A 4" LAYER OF MULCH AS SPECIFIED. AL TREES SHALL HAVE A 4" THICK MUCH RING HE LANDSCAPE SCOPE OF WORK INCLUDES MULCHING AS AN INTEGRAL PART OF TEM.

ATE WATERING BY THE LC AS REQUIRED UNTIL THE LANDSCAPE IRRIGATION IAL ACCEPTANCE BY OWNER.

NO TREES SHALL BE PLANTED WITHIN DESIGNATED UTILITY CORRIDORS, PUBLIC RIGHT OF WAY (WITHOUT RIGHT OF WAY UTILIZATION PERMIT) NOR ANY PLANTS LOCATED WITHIN FOUR FEET (4') OF ANY SWALE CENTERLINE IDENTIFIED ON THE DRAWINGS. FIELD ADJUSTMENTS AS NECESSARY AND REVIEW ADJUSTMENTS WITH THE LA PRIOR TO INSTALLATION. THE LC SHALL BE RESPONSIBLE FOR PROVIDING EFFECTIVE TRAFFIC CONTROL AND REI BACKFILL OFF-SITE ON A DAILY BASIS AT NO ADDITIONAL COST TO THE OWNER. THE CONSTRUCTION LIMIT LINE SHALL BE LEFT UNDISTURBED. EXISTING TREES BE LEFT UNDISTURBED AND PROTECTED BY BARRICADES ERECTED AT THE FIGHE SHALL TRAVERSE THIS AREA NOR SHALL ANY STORAGE OF MATERIALS OR FITHE TREE DRIPLINE(S). ANY EXISTING PLANT BEDS OR TREES DAMAGED BY BY THE RESPONSIBLE PARTY AT THEIR OWN EXPENSE.

• NOTE: QUANTITIES NECESSARY TO COMPLETE T ESTIMATES HAVE BEEN MADE CAREFULLY, BUT T HIS ESTIMATES ARE ONLY AN AID FOR CLARIFICA OWN ESTIMATES. DIFFERENCES SHALL BE BROU COMPENSATION SHALL BE ALLOWED FOR EXTRA RESPONSIBLE FOR INSTALLATION OF PLANT MATE HEIGHT AND SPREAD DIMENSIONS SPECIFIED RANGE OF SIZE IS GIVEN, NO PLANT SHALL BE SHALL BE AS LARGE AS THE MAXIMUM SIZE SP WARRANTY: ALL PLANTS SHALL BE WARRANTED TO REMAIN ALIVE AND HEALTHY AND IN THRIVING CONDITION FOR ONE YEAR FROM THE DATE OF JOB ACCEPTANCE. PLANTS SHALL BE SPECIMEN QUALITY. PLANTS SHALL BE SOUND, HEALTHY AND VIGOROUS, WELL BRANCHED, AND DENSELY FOLIATED WHEN IN LEAF. THE WORK ON THE DRAWING SHALL BE FURNISHED BY THE LC. QUANTITY
THE LANDSCAPE ARCHITECT ASSUMES NO LIABILITY FOR OMISSIONS OR ERRORS
CATION OF UNITS AND A CHECK FOR THE CONTRACTOR TO COMPARE WITH HIS
DUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT. NO EXTRA
RA QUANTITIES NECESSARY TO COMPLETE THE WORK. CONTRACTOR SHALL BE
ATERIAL ACCORDING TO DRAWINGS. EFER TO THE MAIN BODY OF THE PLANT AND NOT FROM BRANCH TI9P TO TIP. ESS THAN THE MINIMUM SIZE AND NOT LESS THAN 5 PERCENT OF THE PLANTS)(FIED.

ERWISE SPECIFIED. SEE SPECIFICATIONS FOR FERTILIZER AND AMENDMENT

RE BASKETS SHOULD HAVE TOP RUNG CUT PRUNED AT THE MIDPOINT OF THEIR LIFE SPAN IN THE NURSERY OR AFTER. NFORMATION REGARDING NURSERY GROWING PRACTICES AND PROVISION OF THE IZONTALLY, AND REMAINDER OF BA CET TO REI

ALL B&B TREES SHALL BE MOVED WITH STRAF TRUNK. CONTAINER PLANTS SHALL BE MOVEI TRUNK. PING CONNECTED TO WIRE BASKET ONLY, NEVER ATTACHED DIRECTLY TO TREE IN A WAY THAT IS COMPLETELY SUPPORTED BY THE CONTAINER, NOT THE TREE

PLANTS SHALL BE SUBJECT TO REVIEW BY LANDSCAPE ARCHITECT AT THE NURSERY. LAND SOLE JUDGE OF THE QUALITY AND ACCEPTABILITY OF MATERIALS AND PLACEMENT. LL TREES TO BE INSTALLED WITH MOST ATTR

LC TO ENSURE ALL TREE ROOTS BE STURDIL' WITH TWINE OR WIRE, OR PINNED.

TREES SPECIFIED TO HAVE CLEAR TRUNK HE FIELD-PRUNED BY CONTACTOR.

THE CONTRACTOR SHALL BE REQUIRED TO PERFORM ALL EARTHWORK AND SITE GRADING NECES FINISHED GRADES NOTED ON THE DRADING PLANS ACCORDING TO THE SPECIFICATIONS.

SSARY TO ACHIEVE THE

ANY TREES NOT TAGGED BY THE LANDSCAPE ARCHITECT IN ADVANCE OF INSTALLATION ARE SUBJECT TO REMOVAL AND REPLACEMENT AT NO ADDITIONAL EXPENSE TO THE OWNER OR LANDSCAPE ARCHITECT. TREES ARE TO BE REMOVED AS SPECIFIED BY LANDSCAPE ARCHITECT.

ANDSCAPE CONTRACTOR IS TO PROVIDE PHOTOGRAPHS OF ALL SHRIFO DELIVERY TO JOB SITE FOR APPROVAL.

OUNDCOVER MATERIAL TO LANDSCAPE ARCHITECT PR

NOTE: ALL TREES TO BE TAGGED BY THE LANDSCAPE ARCHITECT AT SOURCE NURSERY PRIOR TO PROCUREMENT BY LANDSCAPE CONTRACTOR. CONSULT L9-01 FOR NURSERY SOURCE INFORMATION. LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING THE LANDSCAPE ARCHITECT A MINIMUM OF THIRTY DAYS IN ADVANCE OF TAGGING FOR SCHEDULING PURPOSES.

DRC review

PC review

03.06.19

CONTRACTOR / LANDSCAPE CONTRACTOR PLEASE NOTE

ENERAL GRADING NOTES

FINISHED GRADE IN PLANTING BED AREAS SHALL BE 1" TO 2" BELOW THE FINISHED ELEVATIONS SURFACES (SEE DETAILS FOR VARYING CONDITIONS). NUMEROUS UNDERGROUND UTILITIES, CONDUIT, SLEEVES, DRAINAGE PIPES, ETC., HAVE BEEN PREVIOUSLY INSTALLED OR SCHEDULED FOR FUTURE INSTALLATION BY OTHERS. CONTRACTOR SHALL COORDINATE AND WORK CLOSELY WITH OTHER CONTRACTORS, TRADES, AND THE OWNER'S REPRESENTATIVE TO AVOID DAMAGE TO THESE UNDERGROUND AND AT GRAD ELEMENTS. ANY DAMAGES SHALL BE REPORTED IMMEDIATELY TO THE OWNER'S REPRESENTATIVE.

ALL FILL REQUIRED SHALL BE CLEAN, WELL DRAINING SOIL. FILL SHALL BE CLEAN AND FREE OF ALL MATERIAL HARMFUL TO PLANT GROWTH AND DELETERIOUS MATERIAL SUCH AS ROCKS (LAGER THAN 2" DIA.), COMPACTED CLAY, ROADBED OR SURFACING MATERIAL, MUCK, ROOTS, BRANCHES, ETC... ALL UTILITIES, SLEEVES, MANHOLES, OUTFALL STRUCTURES, SWALES, AND OTHER STRUCTURES OR TOPOGRAPHICAL FEATU SHALL BE FIELD STAKED AND VERIFIED PRIOR TO CONSTRUCTION. NOTIFY THE OWNERS REPRESENTATIVE OF ANY EXISTING UTILITY WHICH NEEDS TO BE RAISED TO MATCH FINISHED GRADES SHOWN IN THE DRAWINGS.

CONTOURS FOR BERMING SHALL BE SMOOTH, CONTINUOUS ARCS. SIDE SLOPES SHALL BE SMOOTH AND EVEN IN TRANSITION AND VOID OF DEPRESSIONS AND SURFACE IRREGULARITIES. ALL BERMS SHALL HAVE A MAXIMUM SIDE SLOPE OF FOUR FEET (4) HORIZONTAL TO ONE FOOT (1) VERTICAL (IE., 4 TO 1), UNLESS OTHERWISE NOTED. MAXIMUM SIDEWALK SLOPE SHALL BE 5% (1' IN 20') AND MEET ALL HANDICAP REQUIREMENTS. MINIMUM SIDEWALK SLOPE SHALL BE 1%. MAXIMUM SIDEWALK CROSS SLOPE SHALL BE 2% PITCHED TOWARD DRAINAGE STRUCTURES.

ANY LIMITS OF WORK ABUTTING JURISDICTIONAL BOUNDARIES OR EXISTING WATER BODIES SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. CONTRACTOR SHALL FURNISH AND INSTALL ALL NECESSARY FENCES, BARRICADES, AND SEDIMENT CONTROL DEVICES AS WEL AS MAINTAIN AND REPAIR ANY DAMAGE WHICH MAY IMPEDE THEIR EFFECTIVENESS AND AS DIRECTED BY THE OWNER'S REPRESENTATIVE.

REFER TO HARDSCAPE PLANS AND DETAILS AS WELL AS THE STRUCTURAL DOCUMENTS FOR ADDITIONAL LAYOUT INFORMATION CONTRACTOR SHALL COORDINATE AND VERIFY ALL POINTS OF BEGINNING AND BENCHMARKS FOR THE SITE WITH THE OWNER'S REPRESENTATIVE PRIOR TO INITIATING LAYOUT OF SITE ELEMENTS. ANY DISCREPANCIES SHALL BE IMMEDIATELY BROUGHT TO ATTENTION OF THE OWNER'S REPRESENTATIVE AND THE LANDSCAPE ARCHITECT. SEE SITE LAYOUT DRAWINGS FOR CONSTRUCTION LAYOUT GEOMETRY OF THE PROJECT'S SITE DEVELOP

CONTRACTOR SHALL USE THE DIMENSIONING AND STAKING LAYOUTS INDICATED ON THE SITE LAYOUT PLANS TO LAYOUT ALL SITE ELEMENTS, PAVEMENT AND PAVEMENT PATTERNS, ETC., BRING ANY DISCREPANCIES, INCONSISTENCIES OR ERRORS TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE AND LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION. WHEREVER POSSIBLE, THE CONTRACTOR SHALL COORDINATE THE LAYOUT OF THE PAVEMENT AND THE LOCATION OF THE DRAIN INLETS AND OTHER AT GRADE UTILITY ELEMENTS.

ALL PAVEMENT AND LANDSCAPE AREAS OF THE PROJECT SHALL POSITIVELY DRAIN TO DRAINAGE STRUCTURES INDICATED ON THE SITE GRADING AND CIVIL ENGINEERING PLANS.

IRRIGATION FOR PROJECT TO BE DESIGN/BUILD BY CONTRACTOR. CONTRACTOR IS RESPONSIBLE FOR ALL DESIGN, COORDINATION, AND INSTALLATION RELATED TO IRRIGATION ON BOTH THE GROUND PLANE AND AMENITY DECK. CONTRACTOR RESPONSIBLE FOR SUPPLYING IRRIGATION TO ALL PLANT MATERIAL.

CONTRACTOR IS RESPONSIBLE FOR SUPPLY OF ALL NECESSARY PARTS FOR IRRIGATION INCLUDING BUT NOT LIMITED TO: HEADS SLEEVES, WATER LINES, WATER METER, CONTROLLERS, VALVES, ETC. PROVIDE A PROPOSAL AND PRICING FOR AN IRRIGATION SYSTEM THAT DRAWS WATER FROM THE MUNICIPAL WATER SYSTEM, AND AN ALTERNATE PROPOSAL AND PRICING FOR A SYSTEM THAT DRAWS WATER FROM AN ON SITE WELL. (STUDIES WILL NEED TO BE DONE TO SEE IF AN ON SITE WELL IS VIABLE.)

SEAL GEORGIA GEO/STERR


Submission DRC

PLANTING

QLLC Project #: Drawn by: Reviewed by:

19157 JCY

PLAN



 \bigcirc

RECOMPENSE TANION BOTANION TREES

BOTANICAL

TREE SCHEDULE

COMMON NAME

COND.

SIZE

NOTES*

ARO-4 QNP-4 QPH-6 UPE-4

Acer rubrum 'October Glory' Quercus nattallii 'Ochlocknee' Quercus phellos 'Hightower' Ulmus parvifolia 'Elmer II'

'October Glory' Red Maple 'Ochlocknee' Nuttall Oak

4" cal 4" cal 6" cal

See # below See # below


Quercus

4" cal.

See # below

below

Hightower Willow Oak Allee Lacebark Elm



PLANT SPECIFIC CONDITION NOTES

GROUNDCOVER

PT-1 LM-1 HFM-

Pachysandra terminalis Liriope muscari 'Big Blue' Hemerocallis 'Fooled Me'

Japanese Pachysandra 'Big Blue' Liriope

Cont Cont

pot 1 gal. 1 gal.

See # below
See # below
See # below
See # below

Fat at

Perriwinkle

VM-1

Vinca minor

MSA-3

Miscanthus sinensis 'Adagio'

'Adagio' Maiden Grass

Cont

3 gal

See # below

DATE:

03.06.19

PRINTING:

2

06 15 19

DRC review

03 06 19

PC review

VOC-7

Itea virginica 'Henry's Garnet' Itea virginica 'Henry's Garnet' Viburnum x 'Chindo'

'Henry's Garnet' Sweetspire 'Henry's Garnet' Sweetspire 'Chindo' Viburnum

Cont Cont

See # below See # below

Developments, LLC

eachtree Rd., NW Suite 540 Atlanta, GA 30305

Miller Lowry

Cont

See # below

EVERGREE BMG-3 BMJ-1 IP-7 RI-3 IVH-3 IVH-7

Illicium parviflorum Rhaphiolepsis indica

Indian Hawthorne

Cont Cont

See # below See # below

3 gal. 1 gal. 7 gal. 3 gal. 3 gal. 7 gal. 7 gal.

Buxus microphylla 'Green Mtn' Buxus microphylla 'Winter Gem'

'Green Mtn' Korean Boxwood 'Winter Gem' Boxwood

Cont

Cont

See See

below below

City of Hapeville, Fulton County, Georgia

SHRUBS

PSK-2.5

Prunus

serrulata 'Kwanzan'

'Kwanzan' Cherry

Cont Cont

2.5" cal

See # below
. See # below

8' ht.

Chaste Tree

Vitex agnus-castus

ACCENT VAC-8

LCB-3 FI-7

Forsythia x intermedia

Forsythia

Burgundy Loropetalum

Cont Cont

3 gal. 7 gal.

See # below See # below

HAPEVILLE

WALK@

VILLAGE

Loropetalum chinensis

EVERGREEN
TGG-12
INS-10
MVG-6

Magnolia virginiana 'Green Mile'

'Nellie R. Stevens' Holly 'Green Mile' Sweetbay Mag.

Cont

Cont

12' ht. 10' ht. 6' ht.

See # below See # below See # below

PLACE MAKING + MASTER PLANNING + LANDSCAPE ARCHITECTURE

below

Cont

Thuja 'Green Giant'

llex x 'Nellie R. Stevens' Thuja plicata 'Green Giant'

- ALL PLANTS SHALL HAVE MATCHED CHARACTERISTICS IN FORM, COLOR, VIGOR, GROWTH HABIT, AND FOLIAGE DENSITY. ANY PLANT THAT DEVIATES SUBSTANTIALLY FROM THE ACCEPTED NORM WILL BE REJECTED ON-SITE.
- ALL LIKE PLANTS SHALL HAVE A SIMILAR CENTRAL GROWTH **LEADER** AT A CONSISTENT HEIGHT ABOVE THE ROOT COLOR WITHOUT ANY VISIBLE DAMAGE. ALL PLANTS WITH A BROKEN OR DAMAGED CENTRAL LEADER WILL BE REJECTED ON-SITE. EACH PLANT SHALL HAVE MULTIPLE TRUNKS WITH SIMILAR DIAMETER, STRENGTH, VIGOR, AND HABIT. THE PLANT SHALL BE LIMBED UP WITH ACCEPTABLE NURSERY PRUNING PRACTICES TO HIGHLIGHT THE MULTI-TRUNK FORM.


 \bigcirc

(2)

- EACH PLANT SHALL EXHIBIT EXEMPLARY **SPECIMEN** QUALITIES THAT BEST PORTRAY THE UNIQUENESS OF THE SPECIFIED SPECIES FORM, HABIT, COLOR, TEXTURE, SIZE, VIGOR.
- EACH <u>STANDARD</u> PLANT SHALL HAVE A CLEAR, SINGLE, STRAIGHT TRUNK WITH NO VISIBLE DAMAGE. THE LIMBED UP CLEAR HEIGHT SHALL BE COMPLIANT WITH DESIGN INTENT, LOCAL CODE, AND NURSERY BEST PRACTICES.

5

ARRANGE THE PLANTS SPECIFIED IN A <u>HEDGE</u> FORMATION SO THAT THE FOLIAGE FROM ONE PLANT OVERLAPS THE FOLIAGE OF THE ADJACENT PLANT AFTER 5 YEARS OF GROWTH. GROWTH RATES WILL VARY BY SPECIES AND MICRO-CLIMATE.



Submission DRC


QLLC Project #: Drawn by: Reviewed by: 19157 JCY

PLANTING

PLAN

FOR CONSTRUCTION

SEAL GEORGIA PEGISTERA



ALL LIKE PLANTS SHALL HAVE A SIMILAR CENTRAL GROWTH **LEADER** AT A CONSISTENT HEIGHT ABOVE THE ROOT COLOR WITHOUT ANY VISIBLE DAMAGE. ALL PLANTS WITH A BROKEN OR DAMAGED CENTRAL LEADER WILL BE REJECTED ON-SITE. EACH PLANT SHALL HAVE MULTIPLE TRUNKS WITH SIMILAR DIAMETER, STRENGTH, VIGOR, AND HABIT. THE PLANT SHALL BE LIMBED UP WITH ACCEPTABLE NURSERY PRUNING PRACTICES TO HIGHLIGHT THE MULTI-TRUNK FORM. **3**

KECOMPENSE	PENSE - REF SCHEDOLE				
TDEEC				1	
DECIDUOUS					
ARO-4	Acer rubrum 'October Glory'	'October Glory' Red Maple	B&B	4" cal.	See # below
QNP-4	Quercus nattallii 'Ochlocknee'	'Ochlocknee' Nuttall Oak	B&B	4" cal.	See # below
QPH-6	Quercus phellos 'Hightower'	Hightower Willow Oak	B&B	6" cal.	See # below
UPE-4	Ulmus parvifolia 'Elmer II'	Allee Lacebark Elm	B&B	4" cal	See # below
EVERGREEN					
TGG-12	Thuja plicata 'Green Giant'	Thuja 'Green Giant'	Cont	12' ht.	See # below
NS-10	llex x 'Nellie R. Stevens'	'Nellie R. Stevens' Holly	Cont	10' ht.	See # below
MVG-6	Magnolia virginiana 'Green Mile'	'Green Mile' Sweetbay Mag.	Cont	6' ht.	See # below
ACCENT					
VAC-8	Vitex agnus-castus	Chaste Tree	Cont	8' ht.	See # below
PSK-2.5	Prunus serrulata 'Kwanzan'	'Kwanzan' Cherry	Cont	2.5" cal	2.5" cal. See # below
SHRUBS					
DECIDUOUS					
LCB-3	Loropetalum chinensis	Burgunay Loropetalum	Cont	ડ gal.	See # Delow
FI-7	Forsythia x intermedia	Forsythia	Cont	7 gal.	See # below
EVERGREEN					
BMG-3	Buxus microphylla 'Green Mtn'	'Green Mtn' Korean Boxwood	Cont	3 gal.	See # below
BMJ-1	Buxus microphylla 'Winter Gem'	'Winter Gem' Boxwood	Cont	1 gal.	See # below
IP-7	Illicium parviflorum	Anise	Cont	7 gal.	See # below
RI-3	Rhaphiolepsis indica	Indian Hawthorne	Cont	3 gal	See # below
IVH-3	Itea virginica 'Henry's Garnet'	'Henry's Garnet' Sweetspire	Cont	3 gal.	See # below
IVH-7	Itea virginica 'Henry's Garnet'	'Henry's Garnet' Sweetspire	Cont	7 gal.	See # below
VOC-7	Viburnum x 'Chindo'	'Chindo' Viburnum	Cont	7 gal.	See # below
NATIVE GRASSES					
MSA-3	Miscanthus sinensis 'Adagio'	'Adagio' Maiden Grass	Cont	3 gal.	See # below
GROUNDCOVER	OVER				
VM-1	Vinca minor	Perriwinkle	Flat	pot	See # below
PT-1	Dachveandra terminalie	Jananese Pachysandra	Flat	pot	See # below
		Japanese i aciiysanaa			り~~ # トヘlow
LM-1	Liriope muscari 'Big Blue'	'Big Blue' Liriope	Cont	1 gal.	MOIA # DAIOM

HAPEVILLE

WALK@

VILLAGE

City of Hapeville, Fulton County, Georgia

PLACE MAKING + MASTER PLANNING + LANDSCAPE ARCHITECTURE

Quercus

DATE:

03.06.19

Developments, LLC


eachtree Rd., NW Suite 540 Atlanta, GA 30305

Miller Lowry

PRINTING:

DRC review

PC review



EACH PLANT SHALL EXHIBIT EXEMPLARY **SPECIMEN** QUALITIES THAT BEST PORTRAY THE UNIQUENESS OF THE SPECIFIED SPECIES - FORM, HABIT, COLOR, TEXTURE, SIZE, VIGOR.

EACH <u>STANDARD</u> PLANT SHALL HAVE A CLEAR, SINGLE, STRAIGHT TRUNK WITH NO VISIBLE DAMAGE. THE LIMBED UP CLEAR HEIGHT SHALL BE COMPLIANT WITH DESIGN INTENT, LOCAL CODE, AND NURSERY BEST PRACTICES.

ARRANGE THE PLANTS SPECIFIED IN A <u>HEDGE</u> FORMATION SO THAT THE FOLIAGE FROM ONE PLANT OVERLAPS THE FOLIAGE OF THE ADJACENT PLANT AFTER 5 YEARS OF GROWTH. GROWTH RATES WILL VARY BY SPECIES AND MICRO-CLIMATE.

SEAL

GEORGIA PEGISTERA


Submission DRC


QLLC Project #: Drawn by: Reviewed by: 19157 JCY JC

PLANTING

PLAN

FOR CONSTRUCTION





Acer rubrum 'October Glory' Quercus nattallii 'Ochlocknee' Quercus phellos 'Hightower' Ulmus parvifolia 'Elmer II' Itea virginica 'Henry's Garnet' Itea virginica 'Henry's Garnet' Viburnum x 'Chindo' Pachysandra terminalis Liriope muscari 'Big Blue' Hemerocallis 'Fooled Me' Illicium parviflorum Rhaphiolepsis indica Vinca minor Prunus Miscanthus sinensis 'Adagio' Magnolia virginiana 'Green Mile' Buxus microphylla 'Green Mtn' Buxus microphylla 'Winter Gem' Thuja plicata 'Green Giant' llex x 'Nellie R. Stevens' Forsythia x intermedia Vitex agnus-castus BOTANICAL oropetalum chinensis serrulata 'Kwanzan' TREE SCHEDULE 'Henry's Garnet' Sweetspire 'Henry's Garnet' Sweetspire 'Chindo' Viburnum Perriwinkle Japanese Pachysandra 'Big Blue' Liriope 'October Glory' Red Maple 'Ochlocknee' Nuttall Oak 'Adagio' Maiden Grass 'Green Mtn' Korean Boxwood 'Winter Gem' Boxwood 'Nellie R. Stevens' Holly 'Green Mile' Sweetbay Mag. Hightower Willow Oak Forsythia Indian Hawthorne Burgundy Loropetalum 'Kwanzan' Cherry Chaste Tree Thuja 'Green Giant' Allee Lacebark Elm COMMON NAME COND. Cont Cont Cont Cont Cont Cont Cont Cont Cont Cont Cont Cont Cont Fat at Cont Cont Cont Cont 3 gal. 1 gal. 7 gal. 3 gal. 3 gal. 7 gal. 7 gal. 4" cal 4" cal 6" cal 2.5" cal 12' ht. 10' ht. 6' ht. 3 gal. 7 gal. 4" cal. SIZE 3 gal 1 gal. 1 gal. 8' ht. pot See # below . See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See # below See See See # below NOTES* # below # below # below # below # below below

PLACE MAKING + MASTER PLANNING + LANDSCAPE ARCHITECTURE

Quercus

DATE:

03.06.19

Developments, LLC

eachtree Rd., NW Suite 540 Atlanta, GA 30305

Miller Lowry

HAPEVILLE

WALK@

VILLAGE

City of Hapeville, Fulton County, Georgia

PRINTING:

2 06.15.19

DRC review

PC review

PLANT SPECIFIC CONDITION NOTES

- ALL PLANTS SHALL HAVE MATCHED CHARACTERISTICS IN FORM, COLOR, VIGOR, GROWTH HABIT, AND FOLIAGE DENSITY. ANY PLANT THAT DEVIATES SUBSTANTIALLY FROM THE ACCEPTED NORM WILL BE REJECTED ON-SITE.
- ALL LIKE PLANTS SHALL HAVE A SIMILAR CENTRAL GROWTH **LEADER** AT A CONSISTENT HEIGHT ABOVE THE ROOT COLOR WITHOUT ANY VISIBLE DAMAGE. ALL PLANTS WITH A BROKEN OR DAMAGED CENTRAL LEADER WILL BE REJECTED ON-SITE.
- EACH PLANT SHALL HAVE MULTIPLE TRUNKS WITH SIMILAR DIAMETER, STRENGTH, VIGOR, AND HABIT. THE PLANT SHALL BE LIMBED UP WITH ACCEPTABLE NURSERY PRUNING PRACTICES TO HIGHLIGHT THE MULTI-TRUNK FORM.
- EACH PLANT SHALL EXHIBIT EXEMPLARY **SPECIMEN** QUALITIES THAT BEST PORTRAY THE UNIQUENESS OF THE SPECIFIED SPECIES FORM, HABIT, COLOR, TEXTURE, SIZE, VIGOR.
- EACH <u>STANDARD</u> PLANT SHALL HAVE A CLEAR, SINGLE, STRAIGHT TRUNK WITH NO VISIBLE DAMAGE. THE LIMBED UP CLEAR HEIGHT SHALL BE COMPLIANT WITH DESIGN INTENT, LOCAL CODE, AND NURSERY BEST PRACTICES.
- ARRANGE THE PLANTS SPECIFIED IN A <u>HEDGE</u> FORMATION SO THAT THE FOLIAGE FROM ONE PLANT OVERLAPS THE FOLIAGE OF THE ADJACENT PLANT AFTER 5 YEARS OF GROWTH. GROWTH RATES WILL VARY BY SPECIES AND MICRO-CLIMATE.

SEAL

GEORGIA PEGISTERA


Submission DRC


QLLC Project #: Drawn by: Reviewed by: 19157 JCY

PLANTING

PLAN

FOR CONSTRUCTION





PLACE MAKING + MASTER PLANNING + LANDSCAPE ARCHITECTURE

Quercus

ANT SPECIFIC CONDITION NOTES

Pachysandra terminalis Liriope muscari 'Big Blue' Hemerocallis 'Fooled Me'

Japanese Pachysandra 'Big Blue' Liriope

Cont Cont

pot 1 gal. 1 gal.

See # below
See # below
See # below
See # below

DATE:

03.06.19

Developments, LLC

eachtree Rd., NW Suite 540 Atlanta, GA 30305

Miller Lowry

HAPEVILLE

WALK@

VILLAGE

City of Hapeville, Fulton County, Georgia

PRINTING:

03 06 19

PC review


DRC review


Fat at

Perriwinkle

Vinca minor

- ALL PLANTS SHALL HAVE MATCHED CHARACTERISTICS IN FORM, COLOR, VIGOR, GROWTH HABIT, AND FOLIAGE DENSITY. ANY PLANT THAT DEVIATES SUBSTANTIALLY FROM THE ACCEPTED NORM WILL BE REJECTED ON-SITE.
- ALL LIKE PLANTS SHALL HAVE A SIMILAR CENTRAL GROWTH LEADER AT A CONSISTENT HEIGHT ABOVE THE ROOT COLOR WITHOUT ANY VISIBLE DAMAGE. ALL PLANTS WITH A BROKEN OR DAMAGED CENTRAL LEADER WILL BE REJECTED ON-SITE.
- EACH PLANT SHALL HAVE MULTIPLE TRUNKS WITH SIMILAR DIAMETER, STRENGTH, VIGOR, AND HABIT. THE PLANT SHALL BE LIMBED UP WITH ACCEPTABLE NURSERY PRUNING PRACTICES TO HIGHLIGHT THE MULTI-TRUNK FORM.
- EACH PLANT SHALL EXHIBIT EXEMPLARY **SPECIMEN** QUALITIES THAT BEST PORTRAY THE UNIQUENESS OF THE SPECIFIED SPECIES FORM, HABIT, COLOR, TEXTURE, SIZE, VIGOR.
- EACH **STANDARD** PLANT SHALL HAVE A CLEAR, SINGLE, STRAIGHT TRUNK WITH NO VISIBLE DAMAGE. THE LIMBED UP CLEAR HEIGHT SHALL BE COMPLIANT WITH DESIGN INTENT, LOCAL CODE, AND NURSERY BEST PRACTICES.
- ARRANGE THE PLANTS SPECIFIED IN A <u>HEDGE</u> FORMATION SO THAT THE FOLIAGE FROM ONE PLANT OVERLAPS THE FOLIAGE OF THE ADJACENT PLANT AFTER 5 YEARS OF GROWTH. GROWTH RATES WILL VARY BY SPECIES AND MICRO-CLIMATE.





SEAL GEORGIA PEGISTERA


Submission DRC

QLLC Project #: Drawn by: Reviewed by: 19157 JCY

PLANTING

FOR CONSTRUCTION

PLAN



				Š H I I I		<u>D</u> >> 24
				;PECIFIED	* SEE PLANT SPECIFIC CONDITION NOTES BELOW FOR EACH PLANT AS SPECIFIED	* SEE PLANT SPEC
WOK	See # below	1 gal.	Cont	Daylily	Hemerocallis 'Fooled Me'	HFM-1
WO	See # below	1 gal.	Cont	'Big Blue' Liriope	Liriope muscari 'Big Blue'	LM-1
below below	See # below See # below	pot	Flat	Perriwinkle Japanese Pachysandra	Vinca minor Pachysandra terminalis	VM-1 PT-1
					OVER	GROUNDCOVER
below	See # be	3 gal.	Cont	'Adagio' Maiden Grass	Miscanthus sinensis 'Adagio'	NATIVE GRASSES MSA-3
below	See # be	7 gal.	Cont	'Chindo' Viburnum	Viburnum x 'Chindo'	VOC-7
below	See # be	7 gal	Cont	'Henry's Garnet' Sweetspire	Itea virginica 'Henry's Garnet'	IVH-7
below	See # be	3 gal.	Cont	'Henry's Garnet' Sweetspire		IVH-3
below	See # be	3 gal.	Cont	Indian Hawthorne	Rhaphiolepsis indica	RI-3
below	See # be	7 gal.	Cont	Anise	Illicium parviflorum	IP-7
below	See # be		Cont	'Winter Gem' Boxwood	Buxus microphylla 'Winter Gem'	BMJ-1
below	See # be	3 gal.	Cont	'Green Mtn' Korean Boxwood	Buxus microphylla 'Green Mtn'	EVERGREEN BMG-3
below	See # be	7 gal.	Cont	Forsythia	Forsythia x intermedia	FI-7
below	See # be		Cont	Burgundy Loropetalum	Loropetalum chinensis	LCB-3
						SHRUBS
WOK	. See # below	2.5" cal.	Cont	'Kwanzan' Cherry	Prunus serrulata 'Kwanzan'	PSK-2.5
WOK	See # below	8' ht	Cont	Chaste Tree	Vitex agnus-castus	VAC-8
						ACCENT
WO	See # below	6' ht.	Cont	'Green Mile' Sweetbay Mag.	Magnolia virginiana 'Green Mile'	MVG-6
WO	See # below	10' ht.	Cont	'Nellie R. Stevens' Holly	llex x 'Nellie R. Stevens'	INS-10
below	See # be	12' ht.	Cont	Thuja 'Green Giant'	Thuja plicata 'Green Giant'	EVERGREEN TGG-12
WO	See # below	4" cal.	B&B	Allee Lacebark Elm	Ulmus parvifolia 'Elmer II'	UPE-4
WOK	See # below	6" cal.	B&B	Hightower Willow Oak	Quercus phellos 'Hightower'	QPH-6
below	#	4" cal.	B&B	'Ochlocknee' Nuttall Oak	Quercus nattallii 'Ochlocknee'	QNP-4
below	See # be	4" cal	B&B	'October Glory' Red Maple	Acer rubrum 'October Glory'	ARO-4
						TREES
•	NOTES*	SIZE	COND.	COMMON NAME	BOTANICAL NAME	ABBR.
				F	PENSE TREE SCHEDULE	RECOMPENSE

PLACE MAKING & MASTER PLANNING & LANDSCAPE ARCHITECTURE

Quercus

DATE:

03.06.19

Developments, LLC

eachtree Rd., NW Suite 540 Atlanta, GA 30305

Miller Lowry

HAPEVILLE

WALK@

VILLAGE

City of Hapeville, Fulton County, Georgia

PRINTING:

2 06.15.19


DRC review


03.06.19

PC review

PLANT SPECIFIC CONDITION NOTES

- ALL PLANTS SHALL HAVE MATCHED CHARACTERISTICS IN FORM, COLOR, VIGOR, GROWTH HABIT, AND FOLIAGE DENSITY. ANY PLANT THAT DEVIATES SUBSTANTIALLY FROM THE ACCEPTED NORM WILL BE REJECTED ON-SITE.
- ALL LIKE PLANTS SHALL HAVE A SIMILAR CENTRAL GROWTH **LEADER** AT A CONSISTENT HEIGHT ABOVE THE ROOT COLOR WITHOUT ANY VISIBLE DAMAGE. ALL PLANTS WITH A BROKEN OR DAMAGED CENTRAL LEADER WILL BE REJECTED ON-SITE.
- EACH PLANT SHALL HAVE MULTIPLE TRUNKS WITH SIMILAR DIAMETER, STRENGTH, VIGOR, AND HABIT. THE PLANT SHALL BE LIMBED UP WITH ACCEPTABLE NURSERY PRUNING PRACTICES TO HIGHLIGHT THE MULTI-TRUNK FORM.
- EACH PLANT SHALL EXHIBIT EXEMPLARY **SPECIMEN** QUALITIES THAT BEST PORTRAY THE UNIQUENESS OF THE SPECIFIED SPECIES FORM, HABIT, COLOR, TEXTURE, SIZE, VIGOR.
- EACH <u>STANDARD</u> PLANT SHALL HAVE A CLEAR, SINGLE, STRAIGHT TRUNK WITH NO VISIBLE DAMAGE. THE LIMBED UP CLEAR HEIGHT SHALL BE COMPLIANT WITH DESIGN INTENT, LOCAL CODE, AND NURSERY BEST PRACTICES.
- ARRANGE THE PLANTS SPECIFIED IN A <u>HEDGE</u> FORMATION SO THAT THE FOLIAGE FROM ONE PLANT OVERLAPS THE FOLIAGE OF THE ADJACENT PLANT AFTER 5 YEARS OF GROWTH. GROWTH RATES WILL VARY BY SPECIES AND MICRO-CLIMATE.







Submission DRC

QLLC Project #: Drawn by: Reviewed by: 19157 JCY JC

PLANTING

PLAN

FOR CONSTRUCTION